

3. Side slopes of excavations shall be trimmed of loose or fragmented material to accommodate a uniform transition between fills and natural materials.
4. The Contractor will not receive additional payment for overexcavation or refill material used for his convenience nor costs for correcting unauthorized overexcavation.

D. Rock Excavation

1. Carry rock excavation to foundation subgrade. Excavation shall be clean, free of loose material, and relatively smooth. Rock projection into bottom of foundations shall not exceed 1 inch. Local depressions in excess of 3 inches shall be filled to within 2 inches of foundation subgrade per Section 3H.
2. Side slopes in rock excavations shall be made to a uniformly inclined surface which will allow construction. No overhang rock projections will be permitted. Side slope stability shall be the Contractor's sole responsibility and shall afford sufficient safety as required by governing codes and safety orders as to workmen's safety.
3. Blasting: Blasting will not be permitted unless/until the Contractor applies for and obtains a blasting permit from the City of Westlake Village and approval of the District. Blasting operations and conditions would be detailed in the permit and during approval by the District. Permit conditions would be similar to the provisions required of KLK Communities, Inc. for blasting in the development of Tract 42801 of which the Filtration Plant site is a part of. The District is evaluating the possibility of pre-blasting, not including excavation, under separate contract for the sludge building foundation and pipe trench (24" and 30" pipe) excavations at the Filtration Plant site. Unless changed by addendum, the scope of work includes all excavation as required for the construction (i.e. a pre-blasted site is not provided by the District).

pre-blasting was pre-formed