



Las Virgenes - Triunfo Joint Powers Authority
Pure Water Demonstration Project

Technical Memorandum
PURE WATER DEMONSTRATION
TEST PLAN

FINAL | November 2020





PURE WATER PROJECT LAS VIRGENES-TRIUNFO

Bringing Our Water Full Circle

Las Virgenes - Triunfo Joint Powers Authority
Pure Water Demonstration Project

Technical Memorandum PURE WATER DEMONSTRATION TEST PLAN

FINAL | November 2020

Andrew Thomas Salveson
REGISTERED PROFESSIONAL ENGINEER
ANDREW THOMAS SALVESON
No. 56902
CIVIL
STATE OF CALIFORNIA
11/11/2020

Contents

| | |
|---|----|
| Section 1 - Pure Water Demonstration Test Plan | 1 |
| 1.1 Overview | 1 |
| 1.2 Treatment Train | 2 |
| 1.3 Ancillary Systems and Components | 5 |
| 1.4 Challenges | 6 |
| Section 2 - Test Plan | 9 |
| 2.1 Pure Water Quality Assessment (Phase 1) | 9 |
| 2.2 Membrane Operational Efficiency Analysis (Phase 1) | 9 |
| 2.3 Membrane Cleaning (Phase 1) | 13 |
| 2.3.1 MF and UF | 13 |
| 2.3.2 Reverse Osmosis | 13 |
| 2.4 Extended Water Quality Testing (Phase 1) | 14 |
| 2.4.1 CECs and the State of California | 21 |
| 2.5 Process Challenge Testing (Phase 1) | 22 |
| 2.5.1 UF Challenge Testing | 22 |
| 2.5.2 RO Challenge Testing | 22 |
| 2.5.3 UV AOP Challenge Testing | 23 |
| 2.6 Production Reliability (Phase 1) | 25 |
| 2.7 RO Concentrate Testing for NPDES Compliance (Phase 1 & Phase 2) | 26 |
| 2.8 RO Concentrate Scaling Evaluation (Phase 1 & Phase 2) | 26 |
| 2.8.1 Product Water Stabilization (Phase 2) | 27 |
| 2.8.2 Pathogen Monitoring (Phase 2) | 27 |
| 2.8.3 Seasonal Operations Simulation (Phase 2) | 28 |
| 2.8.4 Supplemental Flow Simulation (Phase 2) | 30 |
| Section 3 - Daily Operational Data | 33 |
| Section 4 - Quality Assurance/Quality Control | 35 |
| 4.1 Sample Replicates | 35 |
| 4.2 Precision | 35 |
| 4.3 Accuracy | 36 |
| 4.4 Method Detection Limit | 36 |

| | |
|-----------------------------------|----|
| 4.4.1 Comparability | 36 |
| 4.5 Sample Transport | 36 |
| 4.5.1 External Laboratory Samples | 37 |

Appendices

| | |
|------------|--|
| Appendix A | Process Flow Diagrams |
| Appendix B | Pure Water Startup Testing |
| Appendix C | Preliminary RO Concentrate NPDES Compliance Analysis |
| Appendix D | Daily Performance Logs |
| Appendix E | Calleguas Municipal Water District Salinity Management Pipeline NPDES Permit |

Tables

| | | |
|----------|--|----|
| Table 1 | Core Components of Test Plan | 3 |
| Table 2 | Online Water Quality Monitoring | 6 |
| Table 3 | MF, UF, and RO Operational Plans | 11 |
| Table 4 | UF Initial Cleaning Protocols | 13 |
| Table 5 | RO Initial Cleaning Protocols | 14 |
| Table 6 | Weekly Sampling | 15 |
| Table 7 | Twice Monthly Sampling | 16 |
| Table 8 | Monthly Sampling | 17 |
| Table 9 | Quarterly Sampling | 19 |
| Table 10 | Limited Sampling | 20 |
| Table 11 | Monitoring Requirements for CECs per SWRCB | 22 |
| Table 12 | Phase 2 Seasonal Simulation Operating Schedule | 31 |

Figures

| | | |
|----------|-----------------------------------|----|
| Figure 1 | Process Train Overview | 4 |
| Figure 2 | Tapia WRF Seasonal Flow Variation | 29 |

Abbreviations

| | |
|--------------------------------|--|
| AOP | advanced oxidation process |
| AWPF | Advanced Water Purification Facility |
| BDCM | bromodichloromethane |
| BOD | biochemical oxygen demand |
| Carollo | Carollo Engineers, Inc. |
| CCPP | calcium carbonate precipitation potential |
| CCTV | closed-caption television |
| CEC | chemicals of emerging concern |
| cfs | cubic feet per second |
| CIP | clean-in-place |
| CMWD | Calleguas Municipal Water District |
| COC | chain of custody |
| DBCM | dibromochloromethane |
| DBP | disinfection byproduct |
| DDW | State of California's Division of Drinking Water |
| Demo | Las Virgenes - Triunfo Joint Powers Authority (JPA) Pure Water Demonstration Project |
| EC | electrical conductivity |
| EPA | United States Environmental Protection Agency |
| F | Fahrenheit |
| gfd | gallons per square foot per day |
| gpm | gallons per minute |
| H ₂ SO ₄ | sulfuric acid |
| HDPE | high-density polyethylene |
| HMI | human machine interface |
| JPA | Las Virgenes - Triunfo Joint Powers Authority |
| LRV | log removal value |
| LSI | Langelier Saturation Index |
| mA | milliamperere |
| MC | maintenance cleaning |
| MCL | maximum contaminant level |
| MDL | method detection limit |
| MF | microfiltration |
| µg/L | micrograms per liter |
| µm | micrometer |
| mg/L | milligrams per liter |
| mgd | million gallons per day |

| | |
|---|---|
| mJ/cm ² | millijoule per square centimeter |
| MWD | Municipal Water District |
| Na ₂ S ₂ O ₄ | sodium dithionite |
| NaOCl | sodium hypochlorite |
| NaOH | sodium hydroxide |
| ND | non-detect |
| NDMA | N-nitrosodimethylamine |
| ng/L | nanograms per liter |
| NL | notification level |
| NMOR | N-nitrosomorpholine |
| NOEL | no observed effect level |
| NPDES | National Pollutant Discharge Elimination System |
| Ocean Plan | Water Quality Control Plan for the Ocean Waters of California |
| ORP | oxidation reduction potential |
| P&ID | process and instrumentation diagram |
| PAH | polynuclear aromatic hydrocarbon |
| PCB | polychlorinated biphenyl |
| pCi/L | picocurie/liter |
| PDT | pressure decay test |
| PFAS | per/polyfluoroalkyl substances |
| PFOA | perfluorooctanoic acid |
| PFOS | perfluorooctanesulfonic acid |
| pg/L | pictogram per liter |
| PLC | programmable logic controller |
| PMMoV | Pepper mild mottle virus |
| PPCP | pharmaceuticals, and personal care products |
| PSS | point source summation |
| QA/QC | quality assurance and quality control |
| qPCR | quantitative polymerase chain reaction |
| R | percent recovery |
| RC | recovery clean |
| RO | reverse osmosis |
| RPD | relative percent difference |
| RSD | relative standard deviation |
| RWQCB | Regional Water Quality Control Board |
| SD | standard deviation |
| SMP | Salinity Management Pipeline |
| SRM | standard reference material |
| SWRCB | State Water Resources Control Board |

| | |
|------|---------------------------------------|
| TBD | to be determined |
| TCDD | tetrachlorodibenzo-p-dioxin |
| TMDL | total maximum daily load |
| TMP | transmembrane pressure |
| TOC | total organic carbon |
| TOPA | total oxidizable perfluorinated assay |
| TSS | total suspended solids |
| TUa | acute toxic units |
| TUc | chronic toxic units |
| UF | ultrafiltration |
| UV | ultraviolet |
| UVI | ultraviolet intensity |
| UVT | ultraviolet transmittance |
| WQO | Water Quality Objective |
| WRF | water reclamation facility |
| WRP | water reclamation plant |

-This Page Intentionally Left Blank-

Section 1

PURE WATER DEMONSTRATION TEST PLAN

This Test Plan has evolved since the original publication (Spring 2019) to the current date. The system has been in operation and components of testing under this Test Plan have been started, or in some cases completed. As such, this Test Plan includes some preliminary findings that are used to guide revised testing goals and approaches.

1.1 Overview

The Las Virgenes - Triunfo Joint Powers Authority (JPA) Pure Water Demonstration Project (Demo) is a potable water reuse demonstration project. This Demo will develop the necessary information to successfully implement a future full-scale potable reuse Advanced Water Purification Facility (AWPF) for surface water augmentation to the Las Virgenes Reservoir. The existing Tapia Water Reclamation Facility (WRF) recycles wastewater through primary sedimentation, conventional activated sludge, media filtration, and chloramine disinfection, and will provide the influent for the Demo and the future AWPF.

At this time, planned future AWPF operation will be done seasonally when existing recycled water demands are low, a concept to be mimicked with this Demo. However, the JPA is seeking alternative sources of water (e.g., dry weather runoff, brackish groundwater) that would either be funneled through the wastewater collection system or supplied directly to the AWPF in the future.

JPA has identified the following as goals of the Demo:

- Provide opportunities for public education, acceptance, and public outreach to the JPA's customers.
- Develop design criteria and operational procedures to inform and improve the full-scale design and provide experience to operators.
- Provide technical documentation and support for permitting the project by the State of California's Division of Drinking Water (DDW) and the Regional Water Quality Control Board (RWQCB) as a surface water augmentation project.

This project was partially funded by the United States Bureau of Reclamation, Agreement Number R17AP00067.

This Test Plan is intended to be a fluid document. As new information is gathered, testing may be reduced or expanded depending upon what information is gathered. This Test Plan should be viewed as a starting point for collecting information that will evolve over the coming years. Some aspects of the Test Plan will be evaluated in 2020 and 2021 (Phase 1), while others may be examined subsequently (Phase 2).

1.2 Treatment Train

The Demo includes the following three critical purification processes. A process and instrumentation diagram (P&ID) is found in Appendix A. A few details on the processes include:

- **Microfiltration (MF) and Ultrafiltration (UF):** One open platform train that will produce approximately 100 gallons per minute (gpm) of filtered effluent using three different suppliers' membranes (and thus three modules) to undergo simultaneous testing. System documentation (e.g., human machine interface [HMI] labelling) has been set up to refer to any MF/UF as a UF and the term UF is used interchangeably throughout the document.
 - UF1: Dow/DuPont SFD-2880XP.
 - Reported Nominal Pore Size 0.03 micrometer (μm).
 - Classification: Ultrafilter.
 - UF2: Pall UNA-620A.
 - Reported Nominal Pore Size 0.1 μm .
 - Classification: Microfilter.
 - UF3: Toray HFU Type 2020AN.
 - Reported Nominal Pore Size 0.01 μm .
 - Classification: Ultrafilter.
- **Reverse Osmosis (RO)¹:** One train that will operate at 80 percent and 85 percent recovery in the following two modes of operation:
 - **Two-Stage:** 2:1 array with seven 4-inch elements per vessel and an interstage booster pump between stages to produce 10 - 15 gpm.
 - **Three-Stage:** 4:2:1 array with six 4-inch elements per vessel and an interstage booster pumps between stages 2 and 3 to produce 20 - 35 gpm.
- **Ultraviolet (UV) Advanced Oxidation Process (AOP):** One reactor capable of treating up to 20 gpm² with a dose up to 600 millijoules per square centimeter (mJ/cm^2) for N-nitrosodimethylamine (NDMA) destruction coupled with an upstream dose of sodium hypochlorite for a minimum removal of 0.5-log of 1,4-dioxane. Lower flows are currently being run (approximately 6 gpm) through the system to generate high dose values sufficient for NDMA destruction and to best understand future AWPf design criteria. At the current flow of 6 gpm, the UV supplier (Xylem/WEDECO) estimates a point source summation (PSS)-based UV dose of $\sim 1500 \text{ mJ}/\text{cm}^2$, which will be verified as part of testing detailed herein.

Figure 1 provides an overview of the process train and corresponding chemicals and flow rates. Appendix A contains the process flow diagrams that provide additional information on supporting systems.


Table 1 provides a summary of the key testing components detailed in this Test Plan.

¹ Exact flow set points should be determined using RO design projection software. The flowrates above are indicative based on system capacity and will vary depending on target recovery and operating temperature.

² Uncertainty in dose prediction accuracy and hydroxyl radical scavenging by the proposed UV system require flexibility by this team as to the production flow (gpm) of the proposed unit. These details will be made clear during the Demonstration Project.

Table 1 Core Components of Test Plan

| Test Component | Project Phase | Details | Schedule |
|--|---------------------|--|--|
| Pure Water Quality Assessment | Phase 1 | Evaluation of water quality in accordance with regulations as part of Grand Opening and Tasting Event. | Complete |
| Membrane Operational Efficiency Analysis | Phase 1 | Evaluation of MF, UF, and RO performance over a range of flux and clean-in-place (CIP) intervals. | Ongoing through Spring 2021 |
| Extended Water Quality Testing | Phase 1 | Extensive evaluation of water quality across the AWPf. | Ongoing through Spring 2021 |
| Process Challenge Testing | Phase 1 | Challenge testing of MF, UF, RO, and UV AOP systems. | Winter 2020 |
| Disinfection Byproduct Analysis | Phase 1 and Phase 2 | Evaluation of conventional and emerging disinfection byproducts (DBPs) will be included within Phase 1 UV AOP testing. Pipe loop studies with stabilized water should include DBP reformation during Phase 2 of testing. | Phase 1 - Winter 2020 Phase 2 - TBD |
| Production Reliability | Phase 1 | Evaluation of production reliability based upon down-time resulting from process and monitoring system challenges. | Ongoing through Spring 2021 |
| Artificial Intelligence Investigations | Phase 1 | Evaluation of water quality and membrane process performance as part of grants from MWD and METI. | Ongoing through Spring 2021 |
| RO Concentrate Analysis | Phase 1 and Phase 2 | Evaluation of RO concentrate quality as it may impact National Pollutant Discharge Elimination System (NPDES) discharge and RO brine line scaling. | Phase 1 - Winter 2020 Phase 2 - TBD |
| Product Water Stabilization | Phase 2 | Evaluation of purified water quality and determination (and testing) of stabilization methods | TBD |
| Pathogen Monitoring | Phase 2 | Evaluation of pathogen removal across the Tapia WRF. | TBD |
| Seasonal Operations Simulation | Phase 2 | There is a potential that future AWPf operations are seasonal. The system is designed to allow for some components of the RO to be "mothballed" for periods of time, as is currently being done for some of the membranes. | TBD |
| Supplemental Flow Simulation | Phase 2 | Testing of different water sources by the AWPf, such as brackish groundwater. | TBD |



Note - The table contains maximum flows.
 Maximum concentrate and feed calculated at 80% recovery for maximum permeate.
 Maximum permeate from H₂O process narrative.

Note 1 - Dosing point order can be changed to investigate NDMA formation potential. Preformed chloramine could be dosed at either location but would require additional dosing pumps, storage and blending tanks.

Figure 1 Process Train Overview

1.3 Ancillary Systems and Components

In addition to three treatment systems (UF, RO, UV AOP), this Demo includes:

- **Online Monitoring Systems:** Each of the three processes is being monitored online (both in real time and periodically) over the demonstration period by the instrumentation summarized in Table 2. In addition:
 - The UF system continuously monitors normalized flux, turbidity removal, and transmembrane pressure (TMP). It also conducts daily pressure decay tests (PDTs), and monitors oxidation reduction potential (ORP), pH, free ammonia and total chlorine on the filtrate.
 - The online turbidity meters have experienced some challenges, which have been rectified through better placement of bubble traps and removal of an accidental siphon.
 - No other monitoring system challenges have been noted.
 - The RO system continuously collects detailed online data which is coupled with daily logged data to monitor normalized flux, normalized salt passage/rejection, reduction of total organic carbon (TOC) across the membranes and normalized differential pressure. The RO performance is currently being tracked used calculations spreadsheets provided by Toray (the RO membrane supplier). Daily average flows and pressures are determined from logged data while the RO is operating and used to populate one point per day.
 - The online TOC probe has functioned well, with the exception of RO permeate data recording in which the HMI will read values higher than those logged within the system. To address this issue, the 4 - 20 milliampere (mA) scaling was optimized for RO permeate values between 0 - 1 mg/L.
 - No other monitoring system challenges have been noted.
 - The UV system continuously monitors UV dose, based upon a ultraviolet transmittance (UVT) input value (currently set to 98 percent), the online ultraviolet intensity (UVI) sensor, and flowrate using a PSS calculation. The system also monitors for free and combined chlorine and UVT ahead of and after the UV system, as well as pH in the feed to the UV reactor. The accuracy of that UV dose is undetermined at this point but testing within this document will determine the approximate dose delivery of the reactor and determine the accuracy of the online dose equation.
 - The UVI sensor maintained a consistent value and performance for the first several months of operation but has subsequently lost calibration and been replaced.
 - No other monitoring system challenges have been noted.
 - The intent is for all online meters to be calibrated weekly or monthly using either bench-scale calibrated devices or through laboratory analysis.
- **Equipment for Supporting Studies:** In adjacent rooms to the UF, RO, and UV AOP, the project team, depending upon need and budget, can study RO concentrate and finished water qualities through bench-scale or pipe loop studies.

Table 2 Online Water Quality Monitoring⁽⁴⁾

| Parameter | UF Feed | UF Filtrate | RO Feed | RO Permeate | UVAOP Feed | UV AOP Effluent |
|--------------------|---------|------------------|---------|------------------|------------|-----------------|
| pH | | ● | ● | | ● | |
| Turbidity | ● | ● ⁽¹⁾ | | | | |
| Temperature | ● | | ● | | | |
| Conductivity | | | ● | ● ⁽²⁾ | | |
| TOC ⁽³⁾ | | | ● | ● | | |
| ORP ⁽³⁾ | | ● | ● | | | |
| UVT ⁽³⁾ | | | | | ● | ● |
| Free Chlorine | | | ● | | ● | ● |
| Total Chlorine | | ● | | | ● | ● |
| Free Ammonia | | ● | | | | |

Notes:

- (1) On filtrate from each UF module.
- (2) On permeate from each RO stage.
- (3) ORP: oxidation reduction potential.
- (4) There are no online water quality sensors on the RO concentrate.

1.4 Challenges

This Demo includes evaluation of several novel challenges, which are summarized here and detailed in subsequent sections of this Test Plan:

- **High Run Time (Phase 1):** Increasingly stringent water quality requirements are making seasonal discharge to Malibu Creek very challenging and would trigger a significant investment in treatment at the Tapia Water Reclamation Facility. Therefore, the JPA has gone through a stakeholder-driven process to consider options for regulatory compliance and selected indirect potable reuse utilizing Las Virgenes Reservoir as a preferred scenario. With that understood, no treatment process will run effectively 100 percent of the time. Accordingly, this project must develop a clear understanding of reliability of treatment performance to DDW standards and conclude on the levels of redundancy of treatment and monitoring systems to attain a target Water Production Reliability Goal (value to be determined [TBD]).
- **Feed Water Quality (Phase 1):** The feed to the future system will be tertiary recycled water treated with filtration and chloramination. The feed water for the Demo comes from Reservoir 2, which will have a different water age (anticipated to be shorter) than water to the future full scale AWPf. Further, during periods of effluent discharge for Tapia (instead of non-potable water reuse), the Tapia effluent is dechlorinated, which would result in low to zero chlorine residual in Reservoir 2. With that variation, the following issues must be considered during testing:
 - Variation in chloramine concentrations and contact time through the distribution system will impact the chloramine levels at the AWPf and the chloramine dosing needs at the AWPf.

- That same variation in chloramine concentrations are anticipated to impact NDMA concentrations in the feed water to the AWPf.
- Some evaluation of NDMA concentrations at the future AWPf location, measured through sampling of the non-potable reuse system at that location, is recommended.
- **RO Concentrate (Phase 1 and Phase 2):** As stated above, the RO concentrate from the full-scale AWPf will require long transport for disposal through a pressurized line. Scaling of that line will be problematic at best. Accordingly, the scaling potential of the RO concentrate must be studied, either through bench or flow through pipe reactors.
- **Seasonal Operation (Phase 2):** The JPA is committed to maintaining its current successful non-potable water reuse program. Thus, a future pure water potable reuse project may run seasonally, with pure water to the Las Virgenes Reservoir being in the wet weather months only. Accordingly, this Test Plan must evaluate the approach and impact of membrane storage during the non-potable reclaimed water season.
- **Alternative Feed Water (Phase 2):** The JPA is seeking to augment the wastewater purification process with alternative water supplies. For example, dry weather runoff and brackish groundwater can be added to the sewer collection system, processed at Tapia, then sent to the AWPf. Brackish groundwater can also be sent directly to the AWPf.
 - While the simulation of these new flows through Tapia to the AWPf are already being done at a low level (i.e., brackish groundwater), impacts to AWPf are not anticipated.
 - Simulation of alternative flows directly to the AWPf are possible with infrastructure modifications at the Demo. These modifications would require sufficient tankage or connect to the alternative water supply to run the Demo at full capacity for a month to two months at a time.
- **Stabilization (Phase 2):** The new purified water will ideally match or surpass the quality of the existing finished potable water supply that is fed into Las Virgenes Reservoir. The finished water must also meet chemical concentrations found within the California Toxics Rule. To that end, this Demo should investigate stabilization of the purified water (to avoid corrosion) and pipe loop studies to document DBP reformation.
- **RO Recovery (Phase 2):** The Demo facility is designed for 80 percent to 85 percent recovery. The future full-scale project must dispose of RO concentrate through a long transport line. There may be economic benefits of using a higher recovery RO system, such as the closed-circuit RO (Desalitech), reverse flow RO (ROTEC), or pulsed flow RO (IDE), as examples. These and other conventional high recovery systems could increase the recovery to >95 percent. The Demo has been plumbed for future evaluations of these or other high recovery RO systems, with testing to be performed in the back rooms of the Demo building.

-This Page Intentionally Left Blank-

Section 2

TEST PLAN

Significant work has been accomplished based upon prior versions of the Test Plan. As such, some information is presented below along with a plan moving forward.

2.1 Pure Water Quality Assessment (Phase 1)

Each process, the MF/UF, RO, and UV AOP have performed well, and the combined system has been tested for a broad range of regulated and unregulated parameters and met all criteria for a high-quality potable water.

Appendix B contains a detailed summary of a limited Startup Testing. This work was done in advance of the Grand Opening and provided confidence in the purified water quality. Testing included:

- Process Performance Surrogates (e.g., turbidity, PDTs, TOC, electrical conductivity (EC), and UV dose).
- Pathogen Log Reduction Summaries.
- Regulated Chemical Constituent Monitoring.
- Unregulated Chemical Constituent Monitoring.

Results met or exceeded the water quality goals, demonstrating the ability to produce a high-quality purified water.

2.2 Membrane Operational Efficiency Analysis (Phase 1)

The membrane systems (MF, UF, and RO) are in the early phases of analysis, with experimentation being done to determine the optimum operational conditions (flux and chemical use). The MF/UF and RO systems have been in operation since June 26, 2020.

Since that time, the MF and UF systems have stepped through different flux values, 25 gallons per square foot per day (gfd), 30 gfd, and 35 gfd with little trouble. The RO system has seen some scaling challenges, but has been reprogrammed as of late September, and has now entered a new phase of operation. Moving forward (and looking back a bit), the membrane testing approach is shown in Table 3. Modifications to this testing approach is possible, and the project team will be flexible as we complete each phase and consider subsequent testing needs and understand the goals of the JPA and program management team. Only testing through March is defined, understanding that the results of testing will dictate subsequent membrane operational parameter, including flux and chemical use.

The results from the testing shown in Table 3 will be used to refine the MF/UF and RO design criteria (primary goal) as well as being used as part of the ongoing artificial intelligence grant efforts (secondary goal).

-This Page Intentionally Left Blank-

Table 3 MF, UF, and RO Operational Plans

| | September | October | November | December | January | February | March | April |
|------------------------------------|--|--|---|---|---|--|--------------------------------|--|
| MF/UF Flux | 35 gfd for all three systems | 35 gfd for all three systems | 40 gfd for all three systems | TBD gfd for all three systems | TBD gfd for all three systems | TBD gfd for all three systems | TBD gfd for all three systems | Flux Adjustments TBD |
| MF/UF Chemical Feed and CIP | ~2.5 mg/L chloramines, twice weekly MCs | ~2.5 mg/L chloramines, once weekly MCs | ~2.5 mg/L chloramines, once weekly MCs | ~2.5 mg/L chloramines, TBD MCs | ~2.5 mg/L chloramines, TBD MCs | ~2.5 mg/L chloramines, TBD MCs | ~2.5 mg/L chloramines, TBD MCs | Chemical Feed Adjustments TBD |
| RO Flux | Stage 1 - 11.2 gfd, Stage 2 - 10.6 gfd | Stage 1 - 11.2 gfd, Stage 2 - 10.6 gfd | Stage 1 - TBD gfd, Stage 2 - TBD gfd, Stage 3 - TBD | Stage 1 - TBD gfd, Stage 2 - TBD gfd, Stage 3 - TBD | Stage 1 - TBD gfd, Stage 2 - TBD gfd, Stage 3 - TBD | Stage 1 - 11.2 gfd, Stage 2 - 10.6 gfd | | Flux Values TBD |
| RO Stages and Recovery | 2-stage 80% recovery | 2-stage 80% recovery | 3-stage 80% recovery | 3-stage 85% recovery | 3-stage 85% recovery | 2-stage 85% recovery | | Stage and Recovery TBD |
| RO Chemical Feed and CIP | 2-2.5 mg/L chloramines, RC 45 days or 1000 hours | 2-2.5 mg/L chloramines, RC 45 days or 1000 hours | 2-2.5 mg/L chloramines, RC 45 days or 1000 hours | 2-2.5 mg/L chloramines, RC 45 days or 1000 hours | 2-2.5 mg/L chloramines, RC 45 days or 1000 hours | 2-2.5 mg/L chloramines, RC 45 days or 1000 hours | | anti-scalant acid, and other chemical dosing TBD |



-This Page Intentionally Left Blank-

2.3 Membrane Cleaning (Phase 1)

Membrane cleaning regimens are an important component of membrane performance.

2.3.1 MF and UF

The initial cleaning strategy is presented in Table 4. These parameters will be adjusted as necessary. Cleaning sequences, chemical type, chemical doses, cleaning sequence duration, and temperature may all be adjusted to maximize recovery clean (RC) permeability recovery.

Table 4 UF Initial Cleaning Protocols

| Cleaning Strategy | Parameter | Value |
|------------------------------------|---|------------------------------------|
| Sodium Hypochlorite (NaOCl) | | |
| Maintenance Cleaning (MC) | Interval (per week) | 1-2, as described in prior section |
| | Chemical Contact Duration (minutes) | 30 |
| | Target pH ⁽¹⁾ | c.8 |
| | Target Free Chlorine Residual (mg/L) ⁽³⁾ | 500 |
| NaOCl | | |
| Clean-in-Place (CIP) | Interval (days) | 30 |
| | Chemical Contact Duration (minutes) | 180 |
| | Heated Water Temperature (degrees Fahrenheit) | 95 |
| | Target pH ⁽²⁾ | 10 - 11 |
| | Target Free Chlorine Residual (mg/L) ⁽³⁾ | 2,000 |
| | Citric Acid | |
| Clean-in-Place (CIP) | Interval (days) | 30 |
| | Chemical Contact Duration (minutes) | 180 |
| | Heated Water Temperature (degrees Fahrenheit) | 95 |
| | Target pH ⁽⁴⁾ | 2 - 3 |
| | Target Dose (mg/L) | 2,000 |

Notes:

- (1) Target pH determined by sodium hypochlorite addition only.
- (2) Sodium hydroxide added to achieve target pH.
- (3) Sodium hypochlorite will be dosed to achieve free chlorine residual target.
- (4) Sulfuric acid will be dosed to achieve the target pH. On preliminary trials, 2000 mg/L achieved pH 2.8 so no sulfuric was dosed.

2.3.2 Reverse Osmosis

Online conductivity meters, temperature transducers, flow meters, and pressure gauges on the combined feed and on each stage of permeate will monitor the performance of the RO unit. From these instruments, the RO system programmable logic controller (PLC) will track permeate flow and pressures from each stage. This data can then be averaged and input into Toray provided normalization spreadsheets to calculate normalized permeate flow, differential pressure and salt passage.

The RO membrane modules require cleaning if one or more of the following parameters are applicable:

- Normalized permeate flow drops 10 percent.
- Normalized salt passage increases 5 percent.
- Normalize pressure drop increases (feed - concentrate) 10 to 15 percent.

Chemical cleaning strategies depend on the target foulant. At this time, a presumptive cleaning regime has been enacted using proprietary chemicals from Avista that are typically specified for use on RO membranes treating microfiltered WRF effluent as shown in Table 5.

Table 5 RO Initial Cleaning Protocols

| Target Foulant | Cleaning Chemical | Cleaning Solution pH | Cleaning Solution Temperature (°F) |
|--|-------------------|----------------------|------------------------------------|
| Inorganic Salts, Metal Oxides | RoClean L403 | low (1 - 3) | 100 |
| Inorganic Colloids Biofilms Organics | RoClean L212 | high (10 - 12) | 100 |

The general RO CIP procedure is outlined below:

- First cleaning solution (RO Clean L403) followed by a subsequent clean with RO Clean L212.
- Fill CIP tank with permeate and then shutdown the RO.
- Heat the CIP tank to 100 degrees Fahrenheit and then flush with hot RO permeate to drain at 20 gpm with 50 percent of the CIP tank volume.
- Add cleaning chemical to supplier recommended dosage (approx. 1.5 gal pail/50 percent CIP tank volume) and mix.
- Recirculate the mixed cleaning chemical, one stage at a time, at 10 gpm/pressure vessel for 20 minutes to start contact time.
- Then conduct 2 cycles where one stage at a time is circulated for 60 minutes at 10 gpm/pressure vessel for 60 minutes while the other stages soak. This achieves a total contact time of 4 - 6 hours.
- Conduct an optional soak overnight (Preliminary cleaning results suggest that this does not significantly enhance cleaning performance).
- Upon completion, flush the system with feedwater to drain.
- Then repeat the process with the second cleaning solution.

2.4 Extended Water Quality Testing (Phase 1)

Extensive testing is necessary to define the feed water quality, the impact of that water quality on treatment performance, and the finished water quality pertaining to how it meets various regulations.

For convenience to the sampling team, the testing below is separately into tables focusing up the frequency of sampling; weekly (Table 4), twice monthly (Table 5), monthly (Table 6),

quarterly (Table 7), and limited (Table 8). The testing focuses upon different values/benefits to the JPA’s potable reuse program, noted within each of the respective tables, as follows:

- **Process Monitoring:** Testing which examines water quality that either indicates the potential for process challenges (e.g., high silica) or the performance of the system for a key regulatory parameter (e.g., removal of total nitrogen). Many process monitoring tests are frequent and can be reduced after sufficient data has established confidence in a stable water quality.
- **Performance Surrogate:** Testing which demonstrates performance for a regulated constituent (e.g., pathogen removal) through the removal of another constituent (e.g., strontium). In some cases, a constituent may be important for process monitoring and also be a performance surrogate (e.g., TOC).
- **Key Regulated Chemicals:** There are some constituents which are regulated but also substantially can impact engineering process decisions (e.g., NDMA). As such, these parameters are monitored more frequently than other regulated parameters (i.e., compared to maximum contaminant levels [MCLs]).
- **Pathogen Monitoring:** Measurement of protozoa, virus, or bacteria allows for direct quantification of pathogen reduction without the use of performance surrogates.
- **Regulated Chemicals:** Regulated chemicals include MCLs, secondary MCLs, notification levels (NLs), and other chemicals. Most regulated chemicals will be sampled quarterly, similar to a full-scale operational potable reuse system.
- **RO Concentrate Monitoring:** RO concentrate testing is focused upon NPDES compliance at the discharge location of the RO concentrate (e.g., to a brine line).
- **Public Perception:** The public remains concerned about the existence of trace level “chemicals of emerging concern” (CECs) or as more clinically defined “pharmaceuticals, and personal care products” (PPCPs). Sampling for a broad range of these constituents is included with the quarterly sampling to demonstrate the removal of these unregulated chemicals by the advanced treatment train.

For each of these testing tables, changes can and will occur. Data sets will be evaluated for overlap, consistency, and gaps, resulting in some testing being reduced and other testing being added.

Table 6 Weekly Sampling

| Test | Method | Category | Sample Location | | | |
|------------|-----------|--|-----------------|---------|-------------|--------------|
| | | | UF Feed | RO Feed | RO Permeate | UVAOP Outlet |
| Alkalinity | SM 8221 | Process Monitoring | 1 | | | 1 |
| TSS | SM 2540 D | | 1 | | | |
| TOC | SM 5310 B | Performance Surrogate and Process Monitoring | | 1 | 1 | |

| Test | Method | Category | Sample Location | | | |
|-------------------|-----------|--------------------|-----------------|---------|-------------|--------------|
| | | | UF Feed | RO Feed | RO Permeate | UVAOP Outlet |
| Total Nitrogen | EPA 351.2 | Process Monitoring | 1 | 1 | 1 | 1 |
| Silica | EPA 200.7 | | 1 | 1 | 1 | |
| Iron (total) | EPA 200.7 | | 1 | 1 | | |
| Aluminum (total) | EPA 200.8 | | 1 | 1 | | |
| Manganese (total) | EPA 200.8 | | 1 | 1 | | |
| Bromide | EPA 300.1 | | | | 1 | 1 |
| Bromate | EPA 300.1 | | | | 1 | 1 |

Table 7 Twice Monthly Sampling

| Test | Method | Category | Sample Location | | |
|-----------|-----------|-----------------------|-----------------|---------|-------------|
| | | | UF Feed | RO Feed | RO Permeate |
| Sulfate | EPA 300.0 | Performance Surrogate | | 1 | 1 |
| Strontium | EPA 200.8 | | | 1 | 1 |
| Sucralose | SM 5310 B | | | 1 | 1 |
| BOD | SM 5210 B | Process Monitoring | 1 | | |
| COD | EPA 410.4 | | 1 | | |
| TOC | SM 5310C | | 1 | | |

Table 8 Monthly Sampling

| Test | Method | Category | Sample Location | | | | | |
|-------------------|-----------|--------------------|------------------------------------|---------|---------|-------------|----------------|--------------|
| | | | Raw Water (pre-NH ₂ Cl) | UF Feed | RO Feed | RO Permeate | RO Concentrate | UVAOP Outlet |
| Iron (total) | EPA 200.7 | Process Monitoring | | | | 1 | | |
| Aluminum (total) | EPA 200.8 | | | | | 1 | | |
| Manganese (total) | EPA 200.8 | | | | | 1 | | |
| Calcium | EPA 200.7 | | | | 1 | 1 | | |
| Magnesium | EPA 200.7 | | | | 1 | 1 | | |
| Sodium | EPA 200.7 | | | | 1 | 1 | | |
| Potassium | EPA 200.7 | | | | 1 | 1 | | |
| Barium | EPA 200.8 | | | | 1 | 1 | | |
| Chloride | EPA 300.0 | | | | 1 | 1 | | |
| Fluoride | EPA 300.0 | | | | 1 | 1 | | |
| Boron | EPA 200.7 | | | | 1 | 1 | | |
| NDMA | EPA 521 | | Key Regulated Chemicals | 1 | | 1 | 1 | |
| NMOR | EPA 521 | 1 | | | 1 | 1 | | 1 |

| Test | Method | Category | Sample Location | | | | | |
|---|--------------------|---------------------------|---------------------------------------|---------|---------|-------------|----------------|--------------|
| | | | Raw Water (pre-NH ₂ Cl) | UF Feed | RO Feed | RO Permeate | RO Concentrate | UVAOP Outlet |
| Gross Beta | EPA 900 | RO Concentrate Monitoring | | | | | 1 | |
| Tributyltin | Krone et al., 1989 | | | | | | 1 | |
| Aldrin | EPA 608 | | | | | | 1 | |
| Benzidine | EPA 625 | | | | | | 1 | |
| Beryllium | EPA 200.8 | | | | | | 1 | |
| Chlordane | EPA 608 | | | | | | 1 | |
| DDT | EPA 608 | | | | | | 1 | |
| 3,3-Dichlorobenzidine | EPA 625 | | | | | | 1 | |
| Dieldrin | EPA 608 | | | | | | 1 | |
| Heptachlor epoxide | EPA 608 | | | | | | 1 | |
| Hexachlorobenzene | EPA 625 | | | | | | 1 | |
| PCBs | EPA 625 | | | | | | 1 | |
| Tetrachlorodibenzo-p-dioxin (TCDD) Equivalentents | EPA 1613B | | | | | | 1 | |
| Toxaphene | EPA 608 | | | | | 1 | | |
| PMMoV | Carollo Water ARC® | Performance Surrogate | | 1 | 3 | 1 | | |
| Total Coliforms | SM 9223B | Pathogen Monitoring | | | | | | 1 |

Table 9 Quarterly Sampling

| Test | Method(s) | Category | Sample Location | | | | | |
|----------------|--|---------------------|------------------------------------|---------|---------|-------------|----------------|--------------|
| | | | Raw Water (pre-NH ₂ Cl) | UF Feed | RO Feed | RO Permeate | RO Concentrate | UVAOP Outlet |
| Primary MCLs | EPA 200.8, 100.2, 218.6, 245.1, 300, 524.2, 504.1, 505, 515.4, 525.2, 531.2, 547, 548.1, 549.2, 1613B, SM4500CN-F, SRL 524M-TCPs | Regulated Chemicals | 1 | | | | | 1 |
| Secondary MCLs | EPA 200.8, 524.2, 525.1, 300, SM5540C, SM2540C, SM210B | | 1 | | | | | 1 |
| NLs | EPA 200.8, 524.2, 525.2, 521, 300, 522m, 556, 524-SIM | | 1 | | | | | 1 |
| CECs and PPCPs | EPA 1694M-APCI, EPA 1694M-ESI-, EPA 1694M-ESI+ | Public Perception | 1 | | | 1 | | 1 |
| DBPs | EPA 552.2, EPA 542.2, EPA 300.1 | Regulated Chemicals | 1 | | | 1 | | 1 |

Table 10 Limited Sampling

| Frequency | Test | Category | Method(s) | Sample Location | | | | | |
|---|--|---------------------------|--|------------------------------------|---------|---------|-------------|----------------|--------------|
| | | | | Raw Water (pre-NH ₂ Cl) | UF Feed | RO Feed | RO Permeate | RO Concentrate | UVAOP Outlet |
| Q1 Only | Total oxidizable perfluorinated assay (TOPA) | Process Monitoring | EPA 537M | 1 | | | | | 1 |
| | PFAS Suite (32 compounds) ¹ | | EPA 537M EPA 600/R95/136 | 1 | | | | | 1 |
| Q1 only, most sensitive to be repeated in Q2, Q3 and Q4 | Topsmelt (<i>Atherinops affinis</i> - survival and growth) | RO Concentrate Monitoring | 1995 | | | | | 1 | |
| | Purple sea urchin (<i>Strongylocentrotus purpuratus</i> - growth and fertilization) | | EPA 600/R95/136 1995 | | | | | 1 | |
| | Sand dollar (<i>Dendraster excentricus</i> - growth and fertilization) | | EPA 600/R95/136 1995 | | | | | 1 | |
| | Red abalone (<i>Haliotis rufescens</i> - shell development) | | EPA 600/R95/136 1995 | | | | | 1 | |
| | Giant kelp (<i>Macrocystis pyrifera</i> - germination and growth) | | EPA 600/R95/136 1995 | | | | | 1 | |
| Q1 Only | Estrogen receptor-α | Regulated Chemicals | Escher et al. (2014) Environ. Sci. Tech. 48, 1940-1956 | | | 1 | 1 | | 1 |
| | Aryl hydrocarbon receptor | | Escher et al. (2014) Environ. Sci. Tech. 48, 1940-1956 | | | 1 | 1 | | 1 |

Note:

(1) Perfluorooctanoic acid (PFOA) and perfluorooctanesulfonic acid (PFOS) are included in the quarterly sampling of NLs. This one-time sample event is to characterize all 32 types of per/polyfluoroalkyl substances (PFAS).

2.4.1 CECs and the State of California

The selection of CECs for analysis requires further discussion here. The State of California has specific CECs that they want to see monitored for full scale potable reuse projects, as shown in Table 11. All but two of these CECs (sulfamethoxazole and sucralose) are already part of different line items in the monitoring program. Commercial laboratories, such as Eurofins, have a standard CEC “suite”, which uses United States Environmental Protection Agency (EPA) Method 1694 and includes sulfamethoxazole and sucralose as well as a broad range of other trace level chemicals. This Test Plan current calls for CEC testing per EPA 1694. The CECs for that method include:

| | | | |
|--------------------------------------|---------------------------------|-----------------------------------|-------------------------------------|
| 2,4-D | Clofibric Acid | Isobutylparaben | Quinoline |
| 1,7-Dimethylxanthine | Cotinine | Isoproturon | Salicylic Acid |
| 4-nonylphenol (semi-quantitative) | Cyanazine | Ketoprofen | Simazine |
| 4-tert-octylphenol | DACT | Ketorolac | Sucralose |
| Acesulfame-K | DEA | Lidocaine | Sulfachloropyridazine |
| Acetaminophen | DEET | Lincomycin | Sulfadiazine |
| Albuterol | Dehydronifedipine | Linuron | Sulfadimethoxine |
| Amoxicillin (semi-quantitative) | DIA | Lopressor | Sulfamerazine |
| Androstenedione | Diazepam | Meclofenamic Acid | Sulfamethazine |
| Atenolol | Diclofenac | Meprobamate | Sulfamethizole |
| Atrazine | Dilantin | Metazachlor | Sulfamethoxazole |
| Bendroflumethiazide | Diltiazem | Metformin | Sulfathiazole |
| Bezafibrate | Diuron | Methylparaben | TCEP |
| BPA | Erythromycin | Metolachlor | T CPP |
| Bromacil | Estradiol | Naproxen | TDCPP |
| Butalbital | Estriol | Nifedipine (semi-quantitative) | Testosterone |
| Butylparben | Estrone | Norethisterone | Theobromine |
| Caffeine | Ethinyl Estradiol - 17 alpha | OUST (Sulfameturon,methyl) | Theophylline (semi-quantitative) |
| Carbadox | Ethylparaben | Oxolinic acid | Thiabendazole |
| Carbamazepine | Flumequine | Pentoxifylline | Triclocarban |
| Carisoprodol | Fluoxetine | Phenazone | Triclosan |
| Chloramphenicol | Gemfibrozil | Primidone | Trimethoprim |
| Chloridazon | Ibuprofen | Progesterone | Warfarin |
| Chlorotoluron | Iohexal | Propazine | |
| Cimetidine (semi-quantitative) | Iopromide | Propylparaben | |

Table 11 Monitoring Requirements for CECs per SWRCB

| Constituent | Relevance | MTL (in µg/L) | Example Removal Percentages (%) |
|---|--------------------------|---------------|---------------------------------|
| 1,4-dioxane | Health | 1 | -- |
| NDMA ⁽¹⁾ | Health and Performance | 0.010 | >25-50, 80 |
| NMOR ⁽²⁾ | Health | 0.012 | -- |
| PFOS | Health | 0.013 | -- |
| PFOA | Health | 0.014 | -- |
| Sulfamethoxazole ⁽²⁾ | Performance | - | >90 |
| Sucralose ⁽²⁾ | Performance | - | >90 |
| Dissolved Organic Carbon ⁽²⁾ | Surrogate ⁽³⁾ | - | >90 |
| UV Absorbance ⁽²⁾ | Surrogate ⁽³⁾ | - | >50 |
| EC ⁽²⁾ | Surrogate ⁽³⁾ | - | >90 |
| Estrogen receptor-alpha bioassay ⁽²⁾ | Bioanalytical Screening | - | -- |
| Aryl hydrocarbon bioassay ⁽²⁾ | Bioanalytical Screening | - | -- |

Notes:

- (1) Health-based CECs and Bioanalytical Screening to be monitored following treatment.
- (2) Performance indicator CECs to be monitored before RO and after treatment.
- (3) Surrogates are provided as examples. Surrogates should be used to demonstrate effectiveness of individual processes for removing CECs.

2.5 Process Challenge Testing (Phase 1)

2.5.1 UF Challenge Testing

UF and MF treatment performance will be documented through a combination of turbidity and PDT results. These tests are supplemented by documenting the removal of Pepper mild mottle virus (PMMoV) across both UF and the single MF membrane. Initial results have been collected, documenting 1.6 log removal value (LRV) of PMMoV by MF and 2.9 LRV of PMMoV by the Toray UF membrane. Additional testing is listed in Table 8.

It has been suggested that to best support the PMMoV testing, inclusion of other indigenous viruses such as MS2 or other pathogenic viruses be included. One of the primary benefits of PMMoV testing is to utilize the large feed concentration and measurable effluent concentration for reliable quantification of removal. MS2 may be sufficiently quantifiable but is a culture-based method that is impacted by chlorine and chloramine disinfection, thus being problematic to confine reduction entirely to membrane filtration. Other pathogenic viruses that can be monitored by quantitative polymerase chain reaction (qPCR), such as adenovirus, are often not at sufficiently high levels in secondary or tertiary effluent to allow for reliable quantification of removal across MF or UF.

2.5.2 RO Challenge Testing

RO challenge testing is intended to identify the optimum parameters for log reduction credits for the RO system, including analysis of MS2 bacteriophage (MS2), PMMoV, EC, TOC, sulfate, sucralose, and strontium. The importance of this item is highlighted by the latest LRV for EC and TOC, at values of ~1.7 and 1.8, respectively. Higher LRVs have been documented at other sites

using strontium (Pure Water San Diego) and sulfate (Perth Australia), documenting up to 3 LRV across RO. Novel testing with PMMoV is another method to increase RO LRV credits, which is included in Table 8. No testing of a fluorescent dye (e.g., Trasar) is planned at this time. Baseline RO performance for various surrogates would be developed over the entire test period, whereas damaged RO challenge testing would occur over a 3-day period. Challenge testing may include seeded MS2 testing, depending upon the ongoing results with PMMoV. Challenge testing will be performed over a 3-day period and will include repeated sampling for sulfate, strontium, sucralose, and TOC sampling. Some PMMoV sampling will be conducted to support the chemical analysis.

The specifics for how to “appropriately” simulate a RO membrane failure condition should be discussed with the JPA’s program management team prior to performing the testing. Options include O-ring failure and free chlorine exposure of the RO membranes as follows:

- Baseline testing (historical data set) - no additional sampling.
- Baseline testing (week of testing):
 - PMMoV, strontium, sucralose, sulfate, TOC, and EC (potentially MS2 seeding).
 - Triplicate.
- Damage Condition #1:
 - PMMoV, strontium, sucralose, sulfate, TOC, and EC (potentially MS2 seeding).
 - Triplicate
- Damage Condition #2:
 - PMMoV, strontium, sucralose, sulfate, TOC, and EC (potentially MS2 seeding).
 - Triplicate.
- Damage Condition #3:
 - PMMoV, strontium, sucralose, sulfate, TOC, and EC (potentially MS2 seeding).
 - Triplicate.

At some point in the future, additional RO performance/challenge testing will be conducted to simulate RO operation during the “shoulder” and summer seasons when the full capacity of the system will not be required due to a lack of water for purification. The details of that testing are TBD and will be greatly informed by the development of supplemental water supplies by the program management team. Example operation may include consecutive days on followed by consecutive days off for the membrane systems.

2.5.3 UV AOP Challenge Testing

Due to the use of RO permeate in the UV reactor, general performance decline is not anticipated due to internal fouling (biological or scaling) within the UV reactor. Loss of UVI due to either UVI sensor drift or reduction in UV lamp output is being tracked through the use of the duty and standby UVI sensors.

General UV efficiency correlates to the feed UVT to the UV reactor, which is impacted by chloramine concentrations. Correlations will be developed between chloramines and UVT based upon the overall 12-month data set.

Regarding challenge testing, UV AOP challenge testing is intended to document 6-log reduction of virus, NDMA and N-nitrosomorpholine (NMOR) destruction to below California state requirements, disinfection byproduct formation (e.g., bromate, bromodichloromethane [BDCM] and dibromochloromethane [DBCM]) and a minimum of 0.5 log reduction of 1,4-dioxane.

Because the finished water will be required to reliably meet an NDMA limit of 0.6g nanograms per liter (ng/L) concentration at the Las Virgenes Reservoir (California Toxics Rule sets this standard below the commonly used detection limit of 2 ng/L), a component of this analysis must go beyond the standard dose/response of the UV reactor and look at NDMA formation ahead of the UV AOP. The Demo has the ability to dose ammonia and hypochlorite in series (with either first) or to dose them at the same location. Thus, the first series of tests under this section will examine NDMA formation as follows:

- Ammonia dosing followed by hypochlorite dosing.
 - Targeting chloramine concentrations in UF filtrate of 2 and 3 milligrams per liter (mg/L).
 - Utilizing excess free ammonia at molar ratios TBD in the field sufficient to protect RO membranes.
 - Sampling for these four test conditions would include NDMA, free chlorine, combined chlorine, ammonia, ORP.
- Hypochlorite dosing followed by ammonia dosing.
 - Targeting chloramine concentrations in UF filtrate of 2 and 3 mg/L.
 - Utilizing excess free ammonia at molar ratios TBD in the field sufficient to protect RO membranes. Sampling for these four test conditions would be NDMA, free chlorine, combined chlorine, ammonia, ORP.

Virus destruction testing will be performed second using the bacterial spore surrogate aspergillus, which has the ability to document UV dose delivery up to ~800 mJ/cm². The surrogate will be seeded into the UV reactor with testing of the following conditions:

- No free chlorine dosing. UV disinfection only.
- UV dose values based upon the WEDECO HMI calculation of 350, 400, 500, 600 and 800 mJ/cm².
- Triplicate sampling.

With the approximate dose delivery known based on reduction equivalent dose determined above using Aspergillus and correlated to the online UV monitoring and HMI UV dose calculations, and with NDMA concentrations known without seeding, subsequent testing of 24 test conditions of different operational test conditions (flow, UV dose, chloramine dose, sodium hypochlorite dose). Testing includes spiking of 1,4-dioxane, spiking of NDMA (if needed), and quenching of samples, as follows:

- Baseline testing (historical data set) - no additional sampling.
- Test Condition #1:
 - UV Dose - 600 mJ/cm² - based on HMI display.
 - RO Feed Combined Chlorine ~2 mg/L.
 - pH of ~5.5.
 - UV Feed Free Chlorine.
 - 2 mg/L.
 - 3.5 mg/L.
 - 5 mg/L.
 - Seeded 1,4 dioxane.
 - Seeded NDMA.

- Samples pre- and post-quenching after UV AOP.
- Single sampling.
- Test Condition #2:
 - UV Dose - 1200 mJ/cm² - based on HMI display.
 - RO Feed Combined Chlorine ~2 mg/L.
 - pH of ~5.5.
 - UV Feed Free Chlorine.
 - 2 mg/L.
 - 3.5 mg/L.
 - 5 mg/L.
 - Seeded 1,4 dioxane.
 - Seeded NDMA.
 - Samples pre- and post-quenching after UV AOP.
 - Single sampling.
- Test Condition #3:
 - UV Dose - 1800 mJ/cm² - based on HMI display.
 - RO Feed Combined Chlorine ~2 mg/L.
 - pH of ~5.5.
 - UV Feed Free Chlorine.
 - 2 mg/L.
 - 3.5 mg/L.
 - 5 mg/L.
 - Seeded 1,4 dioxane.
 - Seeded NDMA.
 - Samples pre- and post-quenching after UV AOP.
 - Single sampling.
- Test Condition #4:
 - UV Dose - 1,200 mJ/cm²- based on HMI display.
 - RO Feed Combined Chlorine.
 - 2 mg/L.
 - 3 mg/L.
 - 4 mg/L.
 - pH of ~5.5.
 - UV Feed Free Chlorine - 0 mg/L.
 - Seeded 1,4 dioxane.
 - Seeded NDMA.
 - Samples pre- and post-quenching after UV AOP.
 - Single sampling.

Note: the tests above are intended to provide an important initial understanding of UV AOP performance. Should results be inconsistent or demonstrate an inability to reliably meet targets, then a more in-depth evaluation of hydroxyl radical scavengers may be required.

2.6 Production Reliability (Phase 1)

For the entirety of the first 9 months of operation, the treatment and monitoring system time off-spec or out of calibration, respectively, will be tabulated. The impact of such events on water

production will be estimated and coupled with the time to repair/replace/calibrate to result in a determination of production reliability.

2.7 RO Concentrate Testing for NPDES Compliance (Phase 1 & Phase 2)

Detailed analysis was conducted to estimate which chemicals in the RO concentrate may pose an NPDES compliance risk, attached as Appendix C. As the JPA's project develops and the RO concentrate permitting issues are refined, this test list may need modification (Phase 2). Based upon the analysis within Appendix C, monthly sampling for specific constituents in RO concentrate is included in Table 8. Much more limited sampling, focused upon toxicity, is shown in Table 10. It should be noted that these tests will be conducted under different RO operational scenarios (number of stages, recovery).

2.8 RO Concentrate Scaling Evaluation (Phase 1 & Phase 2)

Scaling in the future line that would carry RO concentrate (brine) to the Calleguas brine line is a concern to the District. In parallel with this project, Calleguas is looking at the existing line for design features that would encourage scale, which includes a review of the hydraulic profile. Carollo Engineers, Inc. (Carollo) is assisting Calleguas and using a modeling tool called Blue Plan-it® to define hot spots through blending analysis of the different sources (existing and future). Since the pipeline is already installed, there will likely be recommendations for maintenance procedures, options for alternative valves and instruments, and potentially a recommendation to do source control of scale formers, such as softening of brine before it goes into the pipeline.

The initial evaluation will examine RO brine water quality data using water quality modeling tools to determine if it is sufficiently stable to travel from a full scale AWPf to the Calleguas brine line without precipitating scale within the brine line. In addition, water quality data will be sent to Avista for scaling potential analysis. The specific details of this testing will be adjusted after greater discussion with Avista.

However, the general plan is as follows:

1. Ship one or more 250-gallon tote (or 55-gallon drums) of water to the supplier (or lab).
2. Water to have 2 to 5 mg/L of chloramines in it.
3. Develop a matrix of inhibitor doses and recoveries to be tested. For example:
 - a. 0.5 mg/L dose at 75 percent, 80 percent, 85 percent, and 90 percent recovery.
 - b. 1 mg/L dose at 75 percent, 80 percent, 85 percent, and 90 percent recovery.
 - c. 1.5 mg/L dose at 75 percent, 80 percent, 85 percent, and 90 percent recovery.
 - d. 2 mg/L dose at 75 percent, 80 percent, 85 percent, and 90 percent recovery.
 - e. 2.5 mg/L Dose at 75 percent, 80 percent, 85 percent, and 90 percent recovery.
4. Lab doses inhibitor to the water and concentrates the 250 gallons to the correct concentration(s) representing a range of recoveries.
5. Qualitative Test:
 - a. Collect samples in beakers.
 - b. Observe mineral scale formation (by photographs) on the air water surface over time:
 - i. 0, 4, 8, 12, 16, 24, 48, 72 hours.

6. Quantitative:
 - a. Collect samples in beakers:
 - i. Test A: Measure micronic particle counts in the brine over time.
 - ii. Test B: Measure dry weight of beaker before and after testing.
7. Summarize results.

Variations on the testing above may include:

- Performing all tests on site with JPA staff.
- Extended duration testing to determine if residual anti-scalants remain active.
- Aeration of RO concentrate to simulate aeration from an airgap discharge within the RO concentrate transmission line.
- Blending of existing brine in the Salinity Management Pipeline (SMP) with the AWPf RO concentrate after simulation of travel time.
- Pipe loop studies.

The bench testing could be accomplished by placing a fixed volume of brine on the benchtop and monitoring it daily for turbidity, running particle size distribution tests, and monitoring pH. The goal is to determine if crystallization is occurring over time. Furthermore, the pH of samples may be adjusted and additional antiscalant added to determine the impact of chemical addition on brine stability.

The District has expressed concern that the future long brine line will not always run full and may have increased scaling risk on those occasions. It remains TBD if more extensive testing, such as a pipe loop testing using high-density polyethylene (HDPE) piping, which is recommended for full scale brine line, should be performed as part of Phase 2 of this Test Plan.

2.8.1 Product Water Stabilization (Phase 2)

Water quality results from UV/AOP effluent will be analyzed using commonly available water quality models (i.e., MINEQL+, RTW) to determine the level of chemical treatment required to stabilize the water for positive Langelier Saturation Index (LSI) and calcium carbonate precipitation potential (CCPP) in order to decrease the corrosivity of the final product water. It is anticipated that the JPA will decide to test the desktop calculated stabilization doses at the bench and/or with a pilot post-treatment system as part of Phase 2 of testing, with the date TBD.

Quenching of chlorine (or chloramines) and stabilization methods may also impact NDMA reformation in the pipeline from the future full-scale AWPf and the reservoir. In particular, focus should be upon rapid stabilization of the purified water to control dichloramine formation (and thus NDMA reformation), and/or quenching of all chlorine species immediately after UV treatment.

2.8.2 Pathogen Monitoring (Phase 2)

Depending upon the need for additional pathogen reduction credit, the JPA may choose to complete extensive pathogen sampling across the Tapia WRP. This testing should include testing of screened raw wastewater, secondary effluent, and filtered unchlorinated effluent.

Based upon discussions with DDW and Carollo³, DDW has concluded that log reduction credits for the combined primary/secondary treatment process should be based upon the following minimum level of testing:

- Testing to span 12 months of operation, covering the different types of effluent quality on a seasonal basis.
- At each sampling location:
 - 20 samples of Total Cultural Virus, before and after the Primary/Secondary Process.
 - 20 samples of Adenovirus, before and after the Primary/Secondary Process, with a preference for collecting both qPCR and culturable data.
 - 20 samples of *Giardia* and *Cryptosporidium*, before and after the Primary/Secondary Process, with a preference for collecting both qPCR and culturable data.
- Development of a suite of secondary process (e.g., TOC) and tertiary (e.g., turbidity) parameters to be used (ideally) as surrogates for pathogen removal.
- Use of positive and negative controls (e.g., colorseed for protozoa recovery).
- Pathogen surrogates, such as male specific coliphage & somatic coliphage (surrogates for virus), and *Clostridium* (surrogate for protozoa), are encouraged. Reduction of pathogen sampling in lieu of lower cost surrogate sampling may be allowed, pending development of data.

It should be noted that the cost to implement such a testing program will exceed \$100,000 and is not include in Phase 1 of this Test Plan.

2.8.3 Seasonal Operations Simulation (Phase 2)

As shown in Figure 2, the JPA has high demand for non-potable reuse during the summer, but demand drops off during the winter, freeing up tertiary effluent for the future full scale AWWP. The JPA is prohibited from discharging to Malibu Creek from April 15 to November 15 except when creek flows drop below 2.5 cubic feet per second (cfs), at which point Tapia WRF must discharge reclaimed water to increase creek flow back up to 2.5 cfs. However, by May 22, 2022, the JPA will supplement the creek with potable water instead of reclaimed water in order to meet the Total Maximum Daily Load (TMDL) nutrient limits.

³ 7/11/2019 conversation between Andrew Salveson and Brian Bernados of DDW.




Figure 2 Tapia WRF Seasonal Flow Variation

For the 6 months between mid-May and mid-October, the full scale AWPf could be entirely offline, depending upon ongoing efforts to supplement the future AWPf with other flows, such as brackish groundwater or dry weather runoff. Pending upcoming analysis and findings from the JPA's program management team on supplemental flows, there may be a need to examine the on and off cycles that may occur due to a seasonal lack of flow to the AWPf.

2.8.3.1 Dry Season Operation

Under this seasonal flow scenario, the AWPf would not operate from mid-May to mid-October. Before this extended shutdown, operators should perform a CIP on the UF and RO membrane systems and preserve with manufacturer recommended chemicals.

2.8.3.2 Shoulder Season Operation

For the 1.5 months before and after the summer period from mid-May to mid-October (April through mid-May and mid-October through November), the full scale AWPf may treat a fraction of its design capacity, so only a portion of its treatment trains would be in service. During this period, each UF module should operate for one day then go offline for 1 day. Backwashes will take place at the time interval established during the first year of testing (Phase 1). Monitoring trends in operational parameters, such as TMP, will indicate whether a chlorinated MC is required at a shorter interval than previously determined during the first year of testing when all modules were operated continuously.

As an alternative to the approach listed above, or as a supplemental study, the MF/UF systems could be continuously run at a dramatically reduced flux.

In reuse applications, RO membranes should not be out of service for longer than 72 hours without first conducting a CIP (per Toray O&M manual), so the operating strategy should include rotation of each RO train back into service in intervals that maintain offline time without a CIP less than 72 hours. Operators must flush the RO membranes prior to removing them from service.

2.8.3.3 Seasonal Demonstration Approach

The Demonstration Project will simulate full scale seasonal operation in the second year (Phase 2) of testing, after determining the first-year optimal operating conditions. After the first year of operation, Carollo, the JPA, and the JPA's program management team will conduct a desk top analysis of the influent flow variation and number of UF trains and flux rate recommended for full scale at each of the seasonal flow conditions. The information from this analysis will inform the recommended flux rate for the second year of testing. Though the UF system online/offline regime is different from that of the RO system, an adequate number of UF modules need to remain in service to provide continuous flow to the RO system. The required flow to the RO system depends on whether two- or three-stage operation is proven most effective, based on the behavior of normalized RO operational parameters, during the first year of testing.

2.8.4 Supplemental Flow Simulation (Phase 2)

Pertaining to the potential to add supplemental flows to the AWPF during the dry (summer) and shoulder (Spring and Fall) seasons, such testing would be potentially simulated at the Demo during Phase 2 of testing. At this time, there is insufficient information to further develop the testing or the schedule beyond what is listed below.

- Brackish groundwater testing.
 - Fed directly to the Demo.
 - The Demo would need some modifications to house sufficient volumes of brackish groundwater to continuously feed to the AWPF for periods of 30 to 45 days, at a minimum. Tankage could be placed outside of the building and plumbed into the Demo through side rooms, feeding the UF feed tank.
 - Water to be fed into the UF feed tank at levels appropriate to the anticipated blend amount at full scale.
 - Fed into the sewer system.
 - Assuming the only significant chemical constituents within the brackish groundwater is salt, the preferred simulation approach may be the addition of salt to the UF feed tank at a level representative of the brackish groundwater addition amount to Tapia.
- Dry weather runoff testing.
 - Fed into the sewer system.
 - TBD how to simulate this addition in a meaningful way at the Demo.
 - Fed directly to the AWPF.
 - Pretreatment may be required, level TBD.
 - Water to be fed into the UF feed tank at levels appropriate to the anticipated blend amount at full scale.

Table 12 Phase 2 Seasonal Simulation Operating Schedule

| System | S1: January through March | S2: April through Mid-May | S3: Mid-May through Mid-October | S4: Mid-October through November | S5: November through December |
|-------------------------|-------------------------------|--|--|---|-------------------------------|
| UF | Standard operating procedures | Operate MF/UF at low flux setpoint with reduced maintenance clean frequency. Conduct backwash and MCs at time interval determined during Phase 1 and monitor operational parameters to determine if MC frequency needs to be adjusted. | Out of service. Conduct CIP before placing into service and after taking out of service. Place membranes in manufacturer approved preservation chemical. | Operate MF/UF at low flux setpoint with reduced maintenance clean frequency. Conduct backwash and MCs at time interval determined during Year 1 and monitor operational parameters to determine if MC frequency needs to be adjusted. | Standard operating procedures |
| UF - ALT ⁽¹⁾ | Standard operating procedures | Operate all skids at reduced capacity while adjusting backwash interval to maintain target recovery and at reduced MC frequency. | Out of service. Conduct CIP before placing into service and after taking out of service. Place membranes in manufacturer approved preservation chemical. | Operate all skids at reduced capacity while adjusting backwash interval to maintain target recovery and at reduced MC frequency. | Standard operating procedures |
| RO | Standard operating procedures | Cycle placing into service for 3 days and out of service for 3 days. Conduct RO flush before placing into service and after taking out of service. ⁽²⁾ | Offline. Conduct CIP before placing into service and after taking out of service. Place membranes in manufacturer approved preservation chemical. | Cycle placing into service for 3 days and out of service for 3 days. Conduct RO flush before placing into service and after taking out of service. | Standard operating procedures |
| UV AOP | Standard operating procedures | Cycle placing into service for 3 days and out of service for 3 days. Drain and rinse UV system after taking out of service. | Offline. Drain and rinse UV system after taking out of service. | Cycle placing into service for 3 days and out of service for 3 days. Drain and rinse UV system after taking out of service. | Standard operating procedures |

Notes:

(1) The listed alternative to the UF evaluation could be a supplemental study or an alternative. Discussion with the project team is needed after completion of Phase 1 of the Test Plan.

(2) The on/off operation places stress on product water connector O-rings. The RO challenge testing from Phase 1 and the various surrogate work may be sufficient to determine O-ring integrity impacts. TBD if further challenge testing is needed during Phase 2.

-This Page Intentionally Left Blank-

Section 3

DAILY OPERATIONAL DATA

Online data is currently recorded by the H₂O Innovation Intelogx soft water package. Daily run sheets are currently recorded by hand but are anticipated to transition to digital input and recording. The run-sheets are included in Appendix D of this Test Plan.

-This Page Intentionally Left Blank-

Section 4

QUALITY ASSURANCE/QUALITY CONTROL

Quality Assurance and Quality Control (QA/QC) are necessary aspects of any project, and particularly so for this project as it pertains to the protection of public health. The project team will work closely with certified laboratories running accepted standard methods to ensure data precision and accuracy (defined below). Method detection limits (MDLs) will be used to determine the statistical significance of any detectable response. Certified laboratories will be performing the analysis in this project and will be responsible for internal QA/QC for each sampling parameter.

4.1 Sample Replicates

The Demonstration Project will run for 12 months, with online monitoring of a range of parameters, daily inspection of online equipment, and monthly or more frequent sampling for a wide range of offline laboratory parameters.

Sample replicates will be conducted for 5 percent of all samples, with a minimum of one replicate for each MCL, NL, or CEC.

4.2 Precision

The precision of duplicate samples is assessed by calculating the relative percent difference (RPD) according to:

$$RPD = \frac{|S - D|}{\frac{(S + D)}{2}} \times 100\%$$

where,

S = Sample concentration.

D = Duplicate sample concentration.

If calculated from three or more replicates, the precision is determined using the relative standard deviation (RSD):

$$RSD = \frac{SD}{Average} \times 100\%$$

where,

SD = Standard deviation for the replicate samples.

4.3 Accuracy

For measurements where matrix spikes (constituent seeding) are used, accuracy is evaluated by calculating the percent recovery (R):

$$R(\%) = \frac{S - U}{C_{SA}} \times 100\%$$

where,

S = Measured concentration in spiked sample.

U = Measured concentration in unspiked sample.

C_{SA} = Calculated concentration of spike in sample.

When a standard reference material (SRM) is used, the Recovery is determined by:

$$R(\%) = \frac{C_m}{C_{SRM}} \times 100\%$$

where,

C_m = Measured concentration of SRM.

C_{SRM} = Actual concentration of SRM.

4.4 Method Detection Limit

The MDL will be as reported by the contract laboratory.

A typical approach to determine the MDL involves at least seven replicates of a laboratory fortified blank at a concentration of three to five times the estimated instrument detection limit is analyzed through the entire analytical method. The MDL for each constituent tested will be determined by the laboratory in accordance with the standard method listed for each constituent. It is important to show that the detection limit for each chemical parameter is sensitive enough such that it can measure below the regulatory limit and show appropriate removal of each compound in question.

The MDL is calculated using the following equation:

$$MDL = (t) \times (SD)$$

where,

t = t value for 99 percent (t for 7 replicates = 3.14).

SD = Standard deviation for the replicate samples.

4.4.1 Comparability

On-site online monitors and field kits will analyze much of the critical data, and outside laboratory analysis will be used for remaining analyses. It is important to prove consistency between laboratories and have a common practice to ensure QC across various laboratories. Comparability is the degree of consistency between a data set obtained at one laboratory and data sets from another. It is achieved by use of consistent methods and materials (i.e., standards). Comparability of data will be promoted by adherence to the standard and certified analytical methods decided by each outside laboratory.

4.5 Sample Transport

Sampling will be performed by Carollo and JPA staff, depending upon who is on site at the necessary dates of sampling. Operators will package the samples in coolers/shipping boxes and provide shipping information. Samples should be in coolers with fresh ice (or freezer bricks) and

a chain of custody (COC). Due to hold time and preservation concerns, the samples should be shipped FedEx "Priority Overnight" to outside labs. The samples should be shipped only Monday through Wednesday as some of the labs are closed on Friday. The cases should be insured for a minimum of \$700 in case of loss or damages due to shipper error and note no signature needed upon arrival.

Two to 5 weeks is the industry standard for report turnaround times from labs. If the results are needed sooner, surcharges may be applied.

4.5.1 External Laboratory Samples

Lab-prepared sample bottles will be sent from each lab (BioVir, Weck, Eurofins, GAP, Water ARC®, and University of Arizona) to the WRF, who will then take the bottles and coolers to the test site. Before sampling, approximately 1 to 2 liters of water will be flushed from the sample port to minimize potential contamination from sample lines. Each sample bottle will be filled with minimum bubbling, without external agents touching and disturbing the internal integrity of the inside of the bottle. All bottles will be immediately capped post sampling, placed in a cooler with the date and sample ID, and sent to the lab within the allowable holding time provided by the lab for each parameter to be measured. All coolers will contain a COC (log of samples) and will be clearly marked with identification tags before shipment. Samples will be shipped priority overnight unless otherwise directed to respective labs by Carollo and follow up communication and tracking will take place after each shipment to confirm receipt of all samples.

Sample teams will abide by the following sampling protocol for trace organics (CECs):

- Place ice packs into freezer upon arrival and confirm that they are frozen before sampling begins.
- Wear gloves, always, during sampling and avoid touching or even breathing on the samples. Measuring compounds at ng/L levels renders them very prone to contamination.
- Use caution (reference Material Safety Data Sheets) when handling sample bottle, which contains toxic preservative.
- Do not rinse or overfill sample bottle and leave approximately 1-inch headspace.
- Use sampling tap that is free of aerators, strainers, or hose attachments.
- Flush for 3 to 5 minutes to obtain a representative sample (preferably using a tap that is constantly flowing).
- For Field blank, please transfer water provided into Field blank sample bottle.
- Make sure cap is tightly sealed.
- Fill out Sample Information Sheet/COC and include any additional water quality data available.
- Place samples in 1 to 4-degree Celsius refrigerator to cool sample prior to shipping (minimum 2 hours).
- When ready to ship place sample bottles into blue shipping case, add ice packs and Sample Information Sheet/COC in a sealed plastic bag.

-This Page Intentionally Left Blank-

Appendix A

PROCESS FLOW DIAGRAMS

VALVE SYMBOLS

N.OPEN N.CLOSED

- BALL
- V-BALL
- BUTTERFLY
- DIAPHRAGM
- GATE
- GLOBE
- NEEDLE
- PLUG
- SAMPLE/DRAIN
- CHECK
- BACKFLOW PREVENTER
- 3-WAY, 4-WAY
- PRESSURE REGULATING
- BACK PRESSURE REGULATING
- FLOW CONTROL
- 2-WAY SOLENOID
- 3-WAY SOLENOID
- 4-WAY SOLENOID
- AIR RELEASE
- VACUUM BREAKER
- PRESSURE RELEASE
- SLUICE GATE/WEIR

VALVE ACTUATOR SYMBOLS

- PNEUMATIC (FAIL LAST POSITION)
- PNEUMATIC FAIL CLOSE
- PNEUMATIC FAIL OPEN
- ELECTRIC
- DIAPHRAGM
- POSITIONER (ANY ACTUATOR TYPE)
- HAND OVERRIDE (ANY ACTUATOR TYPE)
- TRAVEL STOPS (ANY ACTUATOR TYPE)

FLOWMETER SYMBOLS

INTEGRAL CLOSE COUPLED REMOTE

- MAGNETIC
- PADDLE
- VORTEX
- DP/ORIFICE
- THERMAL
- ROTAMETER

INSTRUMENTATION SYMBOLS

| LOCALLY MOUNTED | IN CONTROL PANEL | DESCRIPTION |
|-----------------|------------------|-------------------------------------|
| | | DISCRETE INSTRUMENT |
| | | PRIMARY PLC OR DCS SHARED CONTROL |
| | | SECONDARY PLC OR DCS SHARED CONTROL |
| | | COMPUTER FUNCTION |

INSTRUMENT FUNCTIONS

- SIGNAL PROCESSING FUNCTION
- AUTO/MANUAL
- ADDITION/SUMMATION
- DIFFERENTIAL
- INTERLOCK LOGIC FUNCTION
- AVERAGING

INSTRUMENT CONNECTIONS

- SOCKETWELD
- WELDED
- THREADED

PIPING SYMBOLS

- FLANGED CONNECTION
- BLIND FLANGE
- QUICK DISCONNECT VICTAULIC
- QUICK DISCONNECT CAMLOK
- CAPPED PIPE END
- UNION
- EXPANSION/FLEXIBLE/ISOLATION JOINT
- THREADED CONNECTION
- DOUBLE CONTAINMENT
- INSULATION
- INSULATION
- HEAT TRACING
- DRAIN OUTLET
- REDUCER
- ECCENTRIC REDUCER

PIPING ABBREVIATIONS

- 316 SS 316 STAINLESS STEEL
- 304 SS 304 STAINLESS STEEL
- 316L SS LOW CARBON 316 STAINLESS STEEL
- 304L SS LOW CARBON 304 STAINLESS STEEL
- CPVC CHLORINATED POLYVINYL CHLORIDE
- CS CARBON STEEL
- DI DUCTILE IRON
- HDPE HIGH-DENSITY POLYETHYLENE
- PE POLYETHYLENE
- PVC POLYVINYL CHLORIDE
- RLCS RUBBER LINED CARBON STEEL
- SCH. SCHEDULE
- SDR STANDARD DIMENSION RATIO

LINE SYMBOLOGY

- MAIN PROCESS LINE
- SECONDARY PROCESS LINE
- PROCESS LINE, BY OTHERS
- COMM LINK (EX. PLC TO HMI)
- COMM LINK (EX. PLC TO DCS)
- ELECTRIC WIRING
- PNEUMATIC LINE
- LINE JUMPER
- PIPE DISCONTINUATION
- FLOW DIRECTION ARROWS
- 4" 316 SS SCH.10 LINES SIZE/MATERIAL IDENTIFIER
- SKID BOUNDARY
- NOT BY H₂O Innovation
- SKID BY H₂O Innovation
- REVISION
- LINES TO/FROM OTHER SHEETS
- DESCRIPTION
- C01-001 SHT 1
- DESTINATION

PUMP SYMBOLS

- CENTRIFUGAL
- CHEMICAL METERING
- DIAPHRAGM
- POSITIVE DISPLACEMENT
- VACUUM
- SUBMERSIBLE OR FLOATING
- VERTICAL TURBINE
- PERISTALTIC/HOSE

MISCELLANEOUS EQUIPMENT SYMBOLS

- CARTRIDGE FILTER HOUSING
- AUTOMATIC STRAINER
- SILENCER
- MIXER
- STATIC MIXER
- RESIN TRAP
- MOTOR
- EDUCTOR OR VENTURI
- Y STRAINER
- CONICAL OR TEMPORARY STRAINER
- PULSATION DAMPENER
- DIAPHRAGM
- FLOW ORIFICE
- AIR COMPRESSOR
- RUPTURE DISK (PRESSURE)
- RUPTURE DISK (VACUUM)
- SPECTACLE BLIND (NORMALLY OPEN, NORMALLY CLOSED)
- INJECTION QUILL
- FILTER
- REFRIGERATED AIR DRYER
- TANK
- MMF TANK
- MMF TANK
- MANWAY
- IMMERSED HEATER
- IN-LINE HEATER
- ULTRASONIC LEVEL TRANSMITTER
- FLOAT-STYLE LEVEL TRANSMITTER
- CHEMICAL CONTAINMENT
- CALIBRATION COLUMN
- MEMBRANE
- UV STERILIZER
- DIFFUSERS: COARSE BUBBLE
- FINE BUBBLE
- POSITIVE DISPLACEMENT BLOWER
- REGENERATIVE BLOWER
- CENTRIFUGAL BLOWER
- TURBOCHARGER
- BIO-WHEEL

FLOW INSTRUMENTS

- FAH FLOW ALARM HIGH
- FAL FLOW ALARM LOW
- FCV FLOW CONTROL VALVE
- FE FLOW ELEMENT
- FI FLOW INDICATOR
- FIC FLOW INDICATING CONTROLLER
- FIT FLOW INDICATING TRANSMITTER
- FR FLOW RECORDING
- FSH FLOW SWITCH HIGH
- FSL FLOW SWITCH LOW
- FV FLOW CONTROL OR ON/OFF VALVE
- FQ FLOW TOTALIZER
- FY FLOW SIGNAL CONVERT, I/P, OR SOLN

PRESSURE INSTRUMENTS

- PAH PRESSURE ALARM HIGH
- PAL PRESSURE ALARM LOW
- PC PRESSURE CONTROLLER
- PCV SELF REG PRESS CONTROL VALVE
- PDH DIFFERENTIAL PRESSURE HIGH
- PDI DIFFERENTIAL PRESSURE INDICATOR
- PDIT DIFF PRESS INDICATING TRANSMITTER
- PDSH DIFFERENTIAL PRESS SWITCH HIGH
- PG PRESSURE GAUGE
- PI PRESSURE INDICATOR
- PIC PRESSURE INDICATING CONTROLLER
- PIT PRESSURE INDICATING TRANSMITTER
- PSH PRESSURE SWITCH HIGH
- PSL PRESSURE SWITCH LOW
- PSV SELF REG PRESS SAFETY VALVE
- PT PRESSURE TRANSMITTER
- PY PRESS SIGNAL CONVERT, I/P, OR SOLN
- PSLH PRESSURE SWITCH LOW HIGH

LEVEL INSTRUMENTS

- LAH LEVEL ALARM HIGH
- LAL LEVEL ALARM LOW
- LCV SELF REG LEVEL CONTROL VALVE
- LE LEVEL ELEMENT
- LG LEVEL GAUGE
- LI LEVEL INDICATOR
- LIC LEVEL INDICATING CONTROLLER
- LIT LEVEL INDICATING TRANSMITTER
- LSH LEVEL SWITCH HIGH
- LSL LEVEL SWITCH LOW
- LT LEVEL TRANSMITTER
- LV LEVEL CONTROL OR ON/OFF VALVE
- LY LEVEL SIGNAL CONVERT, I/P, OR SOLN

TEMPERATURE INSTRUMENTS

- TAH TEMPERATURE ALARM HIGH
- TAL TEMPERATURE ALARM LOW
- TC TEMPERATURE CONTROLLER
- TE TEMPERATURE ELEMENT
- TG TEMPERATURE GAUGE
- TI TEMPERATURE INDICATOR
- TIC TEMP INDICATING CONTROLLER
- TIT TEMP INDICATING TRANSMITTER
- TSH TEMPERATURE SWITCH HIGH
- TSL TEMPERATURE SWITCH LOW
- TT TEMPERATURE TRANSMITTER
- TV TEMP CONTROL OR ON/OFF VALVE
- TY TEMP SIGNAL CONVERT, I/P, OR SOLN

ELECTRICAL ABBREVIATIONS

- JB JUNCTION BOX
- MCP MAIN CONTROL PANEL
- RIO REMOTE I/O PANEL
- PP POWER PANEL
- VFD VARIABLE FREQUENCY DRIVE
- HOA HAND-OFF-AUTO

ANALYTICAL INSTRUMENTS

- AAH ANALYTICAL ALARM HIGH
- AAL ANALYTICAL ALARM LOW
- AE ANALYTICAL ELEMENT
- AI ANALYTICAL INDICATOR
- AIC ANAL INDICATING CONTROLLER
- AIT ANAL INDICATING TRANSMITTER
- ASH ANALYTICAL SWITCH HIGH
- ASL ANALYTICAL SWITCH LOW
- AT ANALYTICAL TRANSMITTER
- AY ANALYTICAL SIGNAL CONVERT, I/P, OR SOLN

MISCELLANEOUS INSTRUMENTS

- HS HAND SWITCH
- HI HAND SWITCH POSITION INDICATOR
- II CURRENT INDICATOR
- QOI TOTALIZER INDICATOR
- SC SPEED CONTROLLER
- SI SPEED INDICATOR
- YA MOTOR ALARM
- YC MOTOR CONTROL
- YI MOTOR ON/OFF INDICATOR
- ZIC SWITCH CLOSE INDICATOR
- ZIO SWITCH OPEN INDICATOR
- ZSC POSITION SWITCH CLOSED
- ZSO POSITION SWITCH OPEN
- ZT POSITION TRANSMITTER
- ZI POSITION INDICATOR

VALVES & EQUIPMENT

- AC AIR COMPRESSOR
- ARV AIR RELEASE VALVE
- AS AIR SUPPLY
- B BLOWER
- BT BULK TOTE
- CBD COARSE BUBBLE DIFFUSER
- CV CHECK VALVE
- ED EDUCTOR
- F FILTER
- FBD FINE BUBBLE DIFFUSER
- FL FAIL LAST (DEFAULT IF NOT SHOWN)
- FC FAIL CLOSED
- FO FAIL OPEN
- FQG CALIBRATION COLUMN
- H HEATER
- HCV HAND CONTROL VALVE
- HTR HEATER
- HV HAND VALVE
- M MOTOR
- MX MIXER
- P PUMP
- RT RESIN TRAP
- ST SPILL TANK
- STR STRAINER
- T TANK
- UV ULTRAVIOLET
- HV HAND VALVE
- MV MULTI FUNCTION VALVE

OTHER ABBREVIATIONS

- CAP CAPACITANCE
- CIP CLEAN-IN-PLACE
- COND CONDUCTIVITY
- DO2 DISSOLVED OXYGEN
- ESP EMERGENCY STOP
- IA INSTRUMENT AIR
- I/P CURRENT TO PNEUMATIC CONVERTER
- ORP OXIDATION REDUCTION POTENTIAL
- pH HYDROGEN ION
- RES RESISTIVITY
- RTD RESISTANCE TEMP DETECTOR
- SOL SOLENOID
- SP SET POINT
- uS MICROSIEMENS

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

DRAWING REVISION

| REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
|-----|------------|--------------------------------|-------|------|------|-------|
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |



UNLESS NOTED OTHERWISE
INTERPRETATION: ANSI Y14.5

TOLERANCES - FRACTIONS: 49/2, 49/300
- DECIMALS: 0.XX, 49/10, 49/5
- ANGLES: 49/5
- HOLE SIZES: 49/2
- HOLE CENTERS: 49/2

DO NOT SCALE PRINTS





UF-RO SYSTEM

LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT

TITLE: **PIPING AND INSTRUMENTATION DIAGRAMS LEGEND**

| | | |
|------------|---------------------------------|--------------|
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-001 | REVISION: 01 |
|------------|---------------------------------|--------------|

SHEET: 1 of 1



REFERENCE DRAWING

- NOTES:
1. MINIMUM FEED PRESSURE IS 25 PSIG FOR STRAINER BACK WASHING.
 2. MAX. HEIGHT OF EACH SKID SECTION IS 88" TO FIT IN STANDARD ISO CONTAINER.
 3. FOR FUTURE OXIDATION TANK CONNECTION INCLUDE SPACE IN POWER PANEL FOR SUBMERSIBLE TRANSFER PUMP FROM OXIDATION TANK.
 4. CHLORINE & AMMONIUM SULFATE TO BE ROUTED APART FROM EACH OTHER ON SKID.

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

| DRAWING REVISION | | | | | | |
|------------------|-------------------|--------------------------------|-------|------|------|-------|
| REV | DATE (MM/DD/YYYY) | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |



UNLESS NOTED OTHERWISE
INTERPRETATION:
ANSI Y14.5


TOLERANCES
FRACTIONS: 1/16" ± 0.005
DECIMALS: 0.125 ± 0.005
0.001 ± 0.001
0.010 ± 0.005
0.015 ± 0.005
0.030 ± 0.005
0.060 ± 0.005
0.125 ± 0.005

ANGLES: 90° ± 0.015
HOLE SIZES: 0.062" ± 0.002
HOLE CENTERS: 0.002"

DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT

| | | |
|---|-------------------------------------|----------------|
| TITLE: RAW WATER PIPING & INSTRUMENTATION DIAGRAM | | |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0110 | REVISION 01 |
| SHEET: 1 of 1 | | |



- NOTES:**
- VACUUM BREAKER SUGGESTED ON DRAIN LINE AFTER SKID.
 - ENSURE THAT THERE IS NO BACKPRESSURE ON BACKWASH GRAVITY DRAIN CONNECTION.
 - TRANSMITTER IS COMMON WITH FEED TURBIDITY METER.
 - MIT AIR IS TO BE RELEASED THROUGH THE BW WASTE DRAIN LINE.
 - UF MODULES NOT BY H₂O INNOVATION.

REFERENCE DRAWING

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

| DRAWING REVISION | | | | | | |
|------------------|------------|--------------------------------|-------|------|------|-------|
| REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |






UNLESS NOTED OTHERWISE
ANSI Y14.5

TOLERANCES
FRACTIONS: 1/16" - 3/16" 1/32"
DECIMALS: 0.00 - 0.05 0.010
ANGLES: 15° - 90° 1/2°
HOLE SIZES: 1/16" - 1/2" 1/64"
HOLE CENTERS: 1/16" - 1/2" 1/64"

DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT

| | |
|--|-------------------------------------|
| TITLE: ULTRA FILTRATION UNIT PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0310 |
| REVISION: 01 | SHEET: 1 of 1 |



REFERENCE DRAWING

- NOTES:
- ALLOW FOR 2 x AI AND 1 x DO IN ELECTRICAL DESIGN FOR ADDITION OF NEUTRALIZATION INSTRUMENTATION. ALLOW SPACE AS WELL.
 - AFTER NEUTRALIZATION CHEMICAL HAS BEEN ADDED, OPERATOR INTERVENTION REQUIRED TO DISCHARGE WASTE TO DRAIN.

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

| DRAWING REVISION | | REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
|------------------|------------|-----|------|--------------------------------|-------|------|------|-------|
| 01 | 26/11/2018 | | | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | | | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |





UNLESS NOTED OTHERWISE
INTERPRETATION:
ANSI Y14.5

TOLERANCES:
FRACTIONS: 48"
DECIMALS: 0.XX: 40/100
0.000: 40/1000
0.015: 40/1000
ANGLES: 40/100
HOLE SIZES: 48"
HOLE CENTERS: 48"

DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER
DEMONSTRATION PROJECT

| | |
|---|-------------------------------------|
| TITLE: UF CIP SYSTEM W/ VFD CONTROLLED PUMP PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0370 |
| REVISION 01 | |
| SHEET: 1 of 1 | |



- NOTES:
1. VALVE TO BE MANUALLY PARTIALLY THROTTLED TO PROVIDED BACK PRESSURE FOR SAMPLING.
 2. CENTERLINE ELEVATION OF LINE BETWEEN UF AND RO MUST REMAIN AT AN ELEVATION EQUAL OR BELOW CENTERLINE ELEVATION OF ITS NOZZLE ON THE FILTRATE/BREAK TANK.

REFERENCE DRAWING

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

| DRAWING REVISION | | | | | | |
|------------------|------------|--------------------------------|-------|------|------|-------|
| REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
INTERPRETATION:
ANSI Y14.5

TOLERANCES:
FRACTIONS: 1/16"
DECIMALS: 0.0005
ANGLES: 10.00°
HOLE SIZES: 0.005"
HOLE CENTERS: 0.005"

DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER
DEMONSTRATION PROJECT

| | | |
|---|-------------------------------------|----------------|
| TITLE: BACK PULSE / FILTRATE PUMP AND TANK PROCESS & INSTRUMENTATION DIAGRAM | | REVISION 01 |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0390 | SHEET: 1 of 1 |



CONTINUES

CONTINUES

NOT BY H₂O Innovation SKID BY H₂O Innovation

NOTE:
1. DRAIN VALVE REQUIRES 120V POWER FEED; NO LOGIC.

REFERENCE DRAWING

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.


| DRAWING REVISION | | | | | | |
|------------------|------------|--------------------------------|-------|------|------|-------|
| REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
INTERPRETATION:
ANSI Y14.5
TOLERANCES:
FRACTIONS: 1/16"
DECIMALS: 0.XX
ANGLES: 10, 15, 30, 45, 60, 90
HOLE SIZES: 1/16", 1/8", 3/16", 1/4", 3/8", 1/2", 5/8", 3/4", 7/8", 1"
HOLE CENTERS: 1/16", 1/8", 3/16", 1/4", 3/8", 1/2", 5/8", 3/4", 7/8", 1"
DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT

| | | |
|--|-------------------------------------|----------------|
| TITLE: AIR COMPRESSOR SYSTEM PROCESS & INSTRUMENTATION DIAGRAM | | |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0950 | REVISION 01 |
| SHEET: 1 of 1 | | |



BY OTHERS SKID BY H₂O Innovation CONTINUED



- NOTES:**
1. RAW WATER TANK SUPPLIED BY OTHERS. LEVEL SWITCH SUPPLIED BY H₂O INNOVATION.
 2. SPARE INJECTION POINT.
 3. DRAIN CONNECTION NOT BY H₂O INNOVATION.

REFERENCE DRAWING

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.



| DRAWING REVISION | | DRAWN | CHKD | ENG | APPVD |
|------------------|------------|--------------------------------|------|-----|-------|
| REV | DATE | REVISION DESCRIPTION | | | |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | | | |
| 00 | 23/10/2018 | INITIAL RELEASE | | | |



UNLESS NOTED OTHERWISE
ANSI Y14.5
TOLERANCES:
FRACTIONS: 1/16", 1/8", 1/4", 3/8", 1/2"
DECIMALS: 0.001, 0.005, 0.010, 0.015, 0.030, 0.060, 0.125, 0.250, 0.500, 1.000
ANGLES: 15°, 30°, 45°, 60°, 90°, 120°, 150°, 180°
HOLE SIZES: 1/16", 1/8", 1/4", 3/8", 1/2"
HOLE CENTERS: 1/16", 1/8", 1/4", 3/8", 1/2"
DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT

| | | |
|--|-------------------------------------|-----------------------|
| TITLE: RO CARTRIDGE FILTERS AND FEED PUMPS PROCESS & INSTRUMENTATION DIAGRAM | | REVISION 01 |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0400 | SHEET: 1 of 1 |



NOTES:
1. DRAIN CONNECTION NOT BY H₂O INNOVATION.

REFERENCE DRAWING

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

| DRAWING REVISION | | | | | | |
|------------------|------------|--------------------------------|-------|------|------|-------|
| REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
INTERPRETATION:
ANSI Y14.5

TOLERANCES:
FRACTIONS: 1/16" - 3/4"
DECIMALS: 0.001 - 0.005
ANGLES: 10° - 90°
HOLE SIZES: 1/16" - 1/2"
HOLE CENTERS: 1/16" - 1/2"

DO NOT SCALE PRINTS


UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT

| | |
|--|-----------------|
| TITLE: RO MODULES - 3 STAGES PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: N/A | REVISION: 01 |
| DRAWING NUMBER: 19U5064-C01-0410 | |
| SHEET: 1 of 1 | |



CONTINUES

CONTINUES



REFERENCE DRAWING

NOTES:
1. CIP AND FLUSH TO BE PERFORMED MANUALLY.

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.


| DRAWING REVISION | | | | | | |
|------------------|------------|--------------------------------|-------|------|------|-------|
| REV | DATE | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
INTERPRETATION: ANSI Y14.5
TOLERANCES: FRACTIONS: $\frac{X}{Y}$ ± 0.005
DECIMALS: 0.XX ± 0.015
ANGLES: 0.XX ± 0.5°
HOLE SIZES: $\frac{X}{Y}$ ± 0.005
HOLE CENTERS: $\frac{X}{Y}$ ± 0.005
DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER
DEMONSTRATION PROJECT


| | | |
|-----------------|--|---------------|
| TITLE: | RO CIP AND FLUSH SYSTEM PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: | N/A | REVISION: 01 |
| DRAWING NUMBER: | 19U5064-C01-0470 | SHEET: 1 of 1 |



**SODIUM HYPOCHLORITE (10.3%)
DOSING SYSTEM**



CITRIC ACID (50%) DOSING SYSTEM



REFERENCE DRAWING

- NOTE:
 1. SECONDARY CONTAINMENT BIN.
 2. PUMP FEED BACK AND ANALOGUE CONTROL MAY NOT BE INCLUDED.
 CHECK PUMP DATASHEETS.

NOTE:
 THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.
 THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.


| DRAWING REVISION | | | | | | |
|------------------|-------------------|--------------------------------|-------|------|------|-------|
| REV | DATE (DD/MM/YYYY) | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
 INTERPRETATION: ANSI Y14.5
 TOLERANCES: FRACTIONS: 1/16" - 3/16" 0.000
 DECIMALS: 0.XX 0.000
 ANGLES: 0.D 0.015
 HOLE SIZES: 0.062" - 0.125" 0.005"
 HOLE CENTERS: 0.062" 0.005"
 DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT


| | |
|---|-------------------------------------|
| TITLE: DOSING SKIDS PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0800 |
| REVISION: 01 | SHEET: 1 of 4 |



AMMONIUM SULFATE, 38% DOSING SYSTEM



MINERAL ACID DOSING SYSTEM



TYPICAL PUMP DETAIL

- NOTE:
1. SECONDARY CONTAINMENT BIN.
 2. PUMP FEED BACK AND ANALOGUE CONTROL MAY NOT BE INCLUDED. CHECK PUMP DATASHEETS.

REFERENCE DRAWING

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.


| DRAWING REVISION | | | | | | |
|------------------|------------------|--------------------------------|-------|------|------|-------|
| REV | DATE (DD/M/YYYY) | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
INTERPRETATION: ANSI Y14.5
TOLERANCES - FRACTIONS: .001" - .005" - .010" - .015" - .030" - .050" - .100" - .150" - .300" - .500" - 1.000" - 1.500" - 2.000" - 3.000" - 4.000" - 5.000" - 6.000" - 8.000" - 10.000" - 12.000" - 15.000" - 20.000" - 25.000" - 30.000" - 40.000" - 50.000" - 60.000" - 70.000" - 80.000" - 90.000" - 100.000"
DECIMALS: 0.001" - 0.005" - 0.010" - 0.015" - 0.030" - 0.050" - 0.100" - 0.150" - 0.300" - 0.500" - 1.000" - 1.500" - 2.000" - 3.000" - 4.000" - 5.000" - 6.000" - 8.000" - 10.000" - 12.000" - 15.000" - 20.000" - 25.000" - 30.000" - 40.000" - 50.000" - 60.000" - 70.000" - 80.000" - 90.000" - 100.000"
ANGLES: 0.001" - 0.005" - 0.010" - 0.015" - 0.030" - 0.050" - 0.100" - 0.150" - 0.300" - 0.500" - 1.000" - 1.500" - 2.000" - 3.000" - 4.000" - 5.000" - 6.000" - 8.000" - 10.000" - 12.000" - 15.000" - 20.000" - 25.000" - 30.000" - 40.000" - 50.000" - 60.000" - 70.000" - 80.000" - 90.000" - 100.000"
HOLE SIZES: .001" - .005" - .010" - .015" - .030" - .050" - .100" - .150" - .300" - .500" - 1.000" - 1.500" - 2.000" - 3.000" - 4.000" - 5.000" - 6.000" - 8.000" - 10.000" - 12.000" - 15.000" - 20.000" - 25.000" - 30.000" - 40.000" - 50.000" - 60.000" - 70.000" - 80.000" - 90.000" - 100.000"
HOLE CENTERS: .001" - .005" - .010" - .015" - .030" - .050" - .100" - .150" - .300" - .500" - 1.000" - 1.500" - 2.000" - 3.000" - 4.000" - 5.000" - 6.000" - 8.000" - 10.000" - 12.000" - 15.000" - 20.000" - 25.000" - 30.000" - 40.000" - 50.000" - 60.000" - 70.000" - 80.000" - 90.000" - 100.000"
DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER
DEMONSTRATION PROJECT


| | | | |
|---------------|-----|---|------------------|
| TITLE: | | DOSING SKIDS PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: | N/A | DRAWING NUMBER: | 19U5064-C01-0800 |
| | | REVISION: | 01 |
| SHEET: 2 of 4 | | | |



SODIUM BISULFITE (38%) DOSING SYSTEM



SODIUM HYDROXIDE (50%) DOSING SYSTEM



TYPICAL PUMP DETAIL

REFERENCE DRAWING

- NOTE:
1. SECONDARY CONTAINMENT BIN.
 2. PUMP FEED BACK AND ANALOGUE CONTROL MAY NOT BE INCLUDED. CHECK PUMP DATASHEETS.

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.


| DRAWING REVISION | | | | | | |
|------------------|-----------------|--------------------------------|-------|------|------|-------|
| REV | DATE (MM/DD/YY) | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |




UNLESS NOTED OTHERWISE
INTERPRETATION: ANS I Y14.5
TOLERANCES - FRACTIONS: ±1/2" OTHERWISE
- DECIMALS: 0.XX ±0.030
- ANGLES: 0.XXX ±0.015
- HOLE SIZES: ±0.005
- HOLE CENTERS: ±0.005
DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER DEMONSTRATION PROJECT


| | |
|---|----------------|
| TITLE: DOSING SKIDS PROCESS & INSTRUMENTATION DIAGRAM | |
| SCALE: N/A | REVISION 01 |
| DRAWING NUMBER: 19U5064-C01-0800 | |
| SHEET: 3 of 4 | |



SODIUM HYPOCHLORITE (10.3%)
DOSING SYSTEM



SODIUM HYPOCHLORITE (10.3%)
DOSING SYSTEM



TYPICAL PUMP DETAIL

REFERENCE DRAWING

- NOTE:
1. SECONDARY CONTAINMENT BIN.
 2. PUMP FEED BACK AND ANALOGUE CONTROL MAY NOT BE INCLUDED. CHECK PUMP DATASHEETS.

NOTE:
THE INFORMATION, SPECIFICATIONS AND DATA SHOWN ON THIS PRINT ARE FURNISHED BY AND ARE TO REMAIN THE PROPERTY OF H₂O INNOVATION.

THE PURPOSE OF THIS DOCUMENT IS TO FACILITATE THE INSTALLATION, MAINTENANCE AND OPERATION OF THE EQUIPMENT REPRESENTED BY SAID PRINT. NO OTHER USE OF THIS DOCUMENT SHALL BE MADE WITHOUT EXPRESS WRITTEN CONSENT FROM H₂O INNOVATION.

| DRAWING REVISION | | | | | | |
|------------------|-----------------|--------------------------------|-------|------|------|-------|
| REV | DATE (MM/DD/YY) | REVISION DESCRIPTION | DRAWN | CHKD | ENG | APPVD |
| 01 | 26/11/2018 | MODIFIED PER ENGINEER COMMENTS | M.P. | N.C. | R.D. | D.D. |
| 00 | 23/10/2018 | INITIAL RELEASE | M.P. | N.C. | R.D. | D.D. |



UNLESS NOTED OTHERWISE
INTERPRETATION: ANSI Y14.5
TOLERANCES: FRACTIONS: ±1/2" OTHERWISE
DECIMALS: 0.XX ±0.030
ANGLES: 0.XXX ±0.015
HOLE SIZES: ±0.005
HOLE CENTERS: ±0.010
DO NOT SCALE PRINTS

UF-RO SYSTEM
LAS VIRGENES-TRIUNFO PURE WATER
DEMONSTRATION PROJECT


| | | |
|---|-------------------------------------|-----------------|
| TITLE: DOSING SKIDS PROCESS & INSTRUMENTATION DIAGRAM | | |
| SCALE: N/A | DRAWING NUMBER: 19U5064-C01-0800 | REVISION: 01 |
| SHEET: 4 of 4 | | |

D

C

B

A



REFERENCE DRAWING

- NOTES:
1. A (*) DENOTES ITEMS NOT SUPPLIED BY XYLEM.
 2. UV VESSEL BOUNDARY SHOWN FOR GENERAL LAYOUT PURPOSES ONLY.
 3. ALL PIPING AND FITTINGS EXTERNAL TO SKID BOUNDARY ARE SUPPLIED BY OTHERS.

| REV | REV # ECN # | SHEET (ZONE) | DESCRIPTION | DATE | APPROVAL |
|-----------|----------------|-----------------|-------------|------|----------|
| REVISIONS | | | | | |

| FOR INFORMATION ONLY | |
|----------------------|----------------------|
| PROJECT | LAS VIRGENES |
| LOCATION | LAS VIRGENES, CA |
| CUSTOMER | LAS VIRGENES |
| CONSULTING ENGINEER | |
| NAVISON NUMBER | JOB NUMBER U18028 |

| | |
|--|-----------|
| UNLESS OTHERWISE SPECIFIED TOLERANCES ARE X/X = ±.1, .X = ±.05, .XX = ±.02, .XXX = ±.005 ANG = ± 1° | |
| THIRD ANGLE PROJECTION | |
| DESIGNER | DATE |
| JDM | 1/29/2019 |
| APPROVED BY | DATE |

WEDECO
a xylem brand

www.xyleminc.com

THIS DRAWING CONTAINS DESIGNS AND OTHER INFORMATION WHICH ARE THE PROPERTY OF XYLEM EXCEPT FOR RIGHTS EXPRESSLY GRANTED BY CONTRACT TO THE UNITED STATES GOVERNMENT. THIS DRAWING MAY NOT, IN WHOLE OR IN PART, BE DUPLICATED OR DISCLOSED OR USED FOR MANUFACTURE OF THE PART DISCLOSED HEREIN, WITHOUT THE PRIOR WRITTEN PERMISSION OF XYLEM. XYLEM ACCEPTS NO RESPONSIBILITY FOR UNDOCUMENTED CUSTOMER-INITIATED DRAWING CHANGES TO ELECTRONICALLY TRANSMITTED DRAWINGS.

| | | | | | |
|-----------|---------------|----------|--------|--------------------------------|--------|
| TITLE | | | | PROCESS DIAGRAM SKID LAYOUT | |
| MODEL NO. | | | | SPEKTRON 30e w/ CONTROL 4 | |
| SIZE | DRAWING NO. | | | REV | |
| B | U18028-PID-02 | | | - | |
| SCALE | WEIGHT | MATERIAL | FINISH | SHEET | 1 OF 1 |

Appendix B

PURE WATER STARTUP TESTING

PURE WATER DEMONSTRATION PROJECT

Date: 8/21/2020
 Project No.: 11019A.10

Las Virgenes-Triunfo JPA

Prepared By: Andy Salveson
Reviewed By: Amos Branch, Lydia Holmes
Subject: Pure Water Results from Startup Testing

Purpose

This project memorandum (PM) summarizes treatment performance and water quality of the Pure Water Demonstration (Demo) based upon a limited amount of initial testing. This PM reviews treatment process surrogates, pathogen reduction, and chemical water quality.

Summary

This PM documents the pathogen and chemical removal ability of the Demo based upon a series of testing and online performance in July and August of 2020. While the provided data are snapshots, continual collection and analysis of online data indicates that the treatment process performance is stable and the collected data is expected to be representative of broader performance.

Bulk treatment performance, as indicated by UF filtrate turbidity and reduction of EC and TOC by RO, is summarized below and followed by a summary of pathogen reduction. The results from this project demonstrate a high level of pathogen removal, as indicated in the summary table below, noting that extensive future testing will be used to validate the preliminary information presented in this PM.

Table 1 [AWPF Online Monitoring Summary](#)

| Water Quality Target | UF | RO | UV/AOP |
|----------------------|--------------|-----------|--------|
| Turbidity | <0.2 NTU | - | - |
| TOC | 5 to 7 mg/L | 0.1 mg/L | - |
| EC | ~1,100 uS/cm | <30 uS/cm | - |

Table 2 [AWPF Pathogen Performance Summary](#)

| Water Quality Target | UF | RO | UV/AOP | Free Chlorination | Total |
|----------------------|----|-----|--------|-------------------|-------|
| Virus LRV | >2 | 1.5 | 6 | 4 | 13.5 |
| Protozoa LRV | >4 | 1.5 | 6 | - | 11.5 |

As detailed within this report, apart from TON and chlorate, all measured chemicals met regulatory standards for potable water reuse. Both TON and chlorate were found to be the result of a low-quality batch

of sodium hypochlorite that has since been remedied (with data provided herein). Detected chemicals along with their regulatory levels, are show in the table below.

Table 3 Summary of Detected Chemicals with Regulatory Limits

| Constituent | Measured Value | Regulated Value |
|------------------------|-------------------------|-----------------|
| Total Trihalomethanes | 41 ug/L | 80 ug/L |
| Chlorate | 1,100 ug/L ¹ | 800 ug/L |
| TON | 12 ² | 3 |
| Chloride | 7.8 mg/L | 250 mg/L |
| Sulfate | 1.5 mg/L | 250 mg/L |
| Total Organic Carbon | <0.3 mg/L | 0.3 mg/L |
| Total Nitrogen | 0.29 mg/L | 10 mg/L |
| Gross Alpha | 0.48 pCi/L | 15 pCi/L |
| Gross Beta | 0.88 pCi/L | 50 pCi/L |
| Conductance | 49 uS/cm | 900 uS/cm |
| Total Dissolved Solids | 19 mg/L | 500 mg/L |

A list of Chemicals of Emerging Concern (CECs) was also sampled, with 19 CECs below detectable levels and 10 CECs detected. No CECs are present at levels near or above health-based screening levels, where those levels have been established

General Process Performance

Ultrafiltration and Microfiltration

The Demo utilizes three different low-pressure membranes, run in parallel, to provide treatment ahead of reverse osmosis (RO). These membranes are, in order, an ultrafilter (UF) from DOW (designated UF1), a microfilter (MF) from Asahi (designated UF2), and a UF from Toray (designated UF3). The ultrafilters utilize a smaller pore size compared to the MF, and UFs have been shown to reliably remove virus, but are not credited with virus removal by the State of California Division of Drinking Water (DDW).

The primary value of MF/UF is *Giardia* and *Cryptosporidium* removal and pretreatment ahead of RO. Performance of the MF and UF systems are broken into turbidity reduction and membrane integrity test (MIT) results, as reviewed below.

Turbidity

Turbidity is an indirect and online method to document membrane integrity. For both potable and non-potable water reuse projects, the State of California Division of Drinking Water (DDW) requires low pressure membrane systems (such as UF) to maintain an effluent turbidity of 0.2 NTU or less 95 percent of the time and to never exceed 0.5 NTU (DDW, 2018).

Example turbidity results, which are generally representative of performance, are shown in Table 4, below. Values are typically well below regulated values. Turbidity challenges seen to date are intermittent and appear to be linked to biofouling and air bubbles. Neither of these represent a public health or water quality concern.

¹ See section on Chlorate, noting that chlorate concentrations were the result of degraded sodium hypochlorite supplies.

² See section on TON, noting that the high TON value was an anomaly and subsequent values were at a TON of 1.

Table 4 Example Turbidity Removal Via UF1, UF2, and UF3

| Date | Time | Tertiary Effluent | UF1 Effluent | UF2 Effluent | UF3 Effluent |
|-----------|------|-------------------|--------------|--------------|--------------|
| 8/16/2020 | 0600 | 0.496 | 0.0145 | 0.0139 | 0.0119 |
| 8/18/2020 | - | 0.564 | 0.0163 | 0.0144 | 0.0121 |
| 8/21/2020 | 0400 | 0.466 | 0.0155 | 0.0140 | 0.0121 |

Pressure Decay Testing

While turbidity removal through membrane processes is a gross indication of process performance, referred to as “continuous indirect integrity monitoring” by the U.S. EPA (2005), pressure decay testing (PDT) is a “direct integrity test” U.S. EPA (2005). The PDTs are designed to measure if there is membrane damage sufficient to pass a 3 µm particle, which is the lower bound of the *Cryptosporidium* size range (U.S. EPA, 2005).

Through size exclusion, the UF membranes remove bacteria, protozoan, and viral pathogens (Cheryan, 1998, USEPA, 2005). The State of California Division of Drinking Water (DDW, formerly the California Department of Public Health (CDPH)) has previously granted virus removal credit for UF (CDPH, 2014), approving “at least 1-log” virus removal while also approving 4-log protozoa removal. However, DDW currently does not grant virus credit due to the lack of a continuous or daily method to verify membrane integrity to the level sufficient to remove virus.

PDT is sometimes referred to as membrane integrity testing (MIT) through which the integrity of the membrane is determined based upon an air pressure test in which the membranes are pressurized with air, then put in a “hold” mode and the air slowly leaks from the membranes. Too fast a leak means that the membrane has been compromised. The air leakage rate, can be converted to a LRV for protozoa (*Giardia* and *Cryptosporidium*) using constants specific to each membrane system. Based upon daily MIT readings for UF1, UF2, and UF3, all three membrane systems remain intact and providing for robust removal of protozoa. All daily PDT results for each of the three low pressure membranes have indicated protozoa LRV > 4 with example protozoan LRV results shown in Table 5 below.

Table 5 Example LRV Results for UF1, UF2, and UF3

| Date | Time | UF1 Effluent | UF2 Effluent | UF3 Effluent |
|-----------|------|--------------|--------------|--------------|
| 8/16/2020 | 0600 | 4.95 | 4.80 | 5.30 |
| 8/18/2020 | - | 4.64 | 5.30 | 5.30 |
| 8/21/2020 | 0400 | 4.53 | 5.30 | 4.82 |

Reverse Osmosis

RO provides a robust barrier to both pathogens and chemical pollutants, as represented below by the removal of total organic carbon (TOC) and electrical conductivity (EC).

For both potable water reuse projects, the State of California DDW requires RO systems to maintain, on average, an RO permeate TOC level of <0.5 mg/L (DDW, 2018). Reducing TOC to this level (or below) is considered an important barrier to reduction of chemical pollutants. Further, DDW allows for the reduction of TOC across RO to be a conservative surrogate for both virus and protozoa removal (Los Angeles, 2018).

Tables 6 and 7, below, show TOC and EC reduction across the RO.

Table 6 Summary of Total Organic Carbon Removal Through Reverse Osmosis

| Date | Time | TOC (mg/L) | | LRV |
|-----------|------|-----------------|-------------|-----|
| | | Sample Location | | |
| | | RO FEED | RO Permeate | |
| 8/16/2020 | 0600 | 4.99 | 0.1 | 1.7 |
| 8/18/2020 | - | 6.00 | 0.19 | 1.5 |
| 8/21/2020 | 0400 | 6.09 | 0.1 | 1.8 |

Table 7 Summary of Conductivity Removal Through Reverse Osmosis

| Date | Time | EC, uS/cm | | LRV |
|-----------|------|-----------------|-------------|-----|
| | | Sample Location | | |
| | | RO FEED | RO Permeate | |
| 8/16/2020 | 0600 | 1144 | 24 | 1.7 |
| 8/18/2020 | - | 1081 | 23 | 1.7 |
| 8/21/2020 | 0400 | 1200 | 26 | 1.4 |

Ultraviolet Light Advanced Oxidation Process

Ultraviolet light advanced oxidation process (UV AOP) technologies are used with potable reuse applications for:

- 6 LRV of pathogens.
- Photolysis of NDMA, reliably below the NL of 10 ng/L.
- Advanced oxidation of 1,4-dioxane. Per 22 CCR, with a minimum LRV of 0.5. The AOP uses an oxidant added upstream of the reactor to generate hydroxyl radicals that oxidize and break down various chemical pollutants, including 1,4-dioxane.

For the Demo, the UV AOP utilizes hypochlorite and a high dose UV reactor, noting that future testing may examine the use of hydrogen peroxide in lieu of hypochlorite.

UV Disinfection

Under UV disinfection, pathogens absorb UV light in the water, which damages the pathogen's DNA or RNA, making it non-infectious. The UV dose is based on adenovirus, since it is shown to resist inactivation with UV light better than other viruses. Adenoviruses comprise a large group of serologically different viruses that can cause a broad spectrum of diseases with varying severity (USEPA, 2010).

Research on the dose-response relationship of Adenoviruses, using Low Pressure (LP) UV radiation on a bench-scale collimated beam setup, is mainly limited to Adenovirus types 2, 40, and 41. The dose response relationship at high UV doses (>200 mJ/cm²) is more widely published for Adenovirus type 2 (Ad2), and shows that 6 LRV of Ad2 may be obtained at a dose of 235 mJ/cm² (Gerba et al., 2002). The dose response relationship of Ad2 as well as other viruses is shown in Figure 1, demonstrating that Ad2 is a conservative surrogate for a wider range of viruses.




Figure 1 LP UV Dose Response Relationship of Ad2

USEPA (2010) published a dose-response equation for Ad2 of:

$$\text{Log Reduction (Ad2)} = 0.0262 * \text{UV Dose} + 0.2774$$

This dose response relationship is based on a dose range between 20 and 160 mJ/cm² (USEPA, 2010). Other studies have shown similar dose responses, consistently indicating that a LP UV dose of up to 235 mJ/cm² results in 6 LRV of Ad2.

The USEPA document entitled "Innovative Approaches for Validation of Ultraviolet Disinfection Reactors for Drinking Water Systems," (Innovative Approaches for Validation) (USEPA 2018) provides UV dose requirements for 6 log inactivation of Cryptosporidium, Giardia, and adenovirus of 85, 84 and 276 mJ/cm², respectively.

No pathogen challenge work has been conducted to date on the installed UV system at the Demo. However, it is being run at a UV dose of ~1600 mJ/cm², well in excess of the minimum UV dose of 276 mJ/cm² for 6 LRV of adenovirus (and thus all pathogens).

NDMA Photolysis

NDMA destruction via photolysis is regulated by DDW (DDW, 2018), with a notification level (NL) of 10 ng/L. However, the Regional Water Quality Control Board (RWQCB) is expected to regulate the discharge to the Las Virgenes Reservoir under the California Toxics Rule (CTR). The CTR would require NDMA levels to be 0.69 ng/L, which is below the detection limit (typically 2 ng/L). As such, robust NDMA destruction will be required from the Demo's UV reactor.

The literature indicates that 1 LRV of NDMA occurs within the UV dose range of 700 mJ/cm² to 1,100 mJ/cm², as shown and referenced in Figure 2 below. Typical NDMA concentrations in tertiary effluents may range from the low ng/L level to the 100s of ng/L. At this time, there is no data on Tapia effluent NDMA,

and thus the dose needed to meet the DDW and CTR requirements is not known. However, the UV system is currently being run at a UV dose of 1,600 mJ/cm², and is resulting in NDMA concentrations of <2 ng/L.




Figure 2 Collimated Beam Bench Testing Results for NDMA Collected in different Studies (San Diego, 2007; Sharpless and Linden, 2003; Swaim et al., 2008; Hokanson et al., 2011). Graphic credit: Trussell Technologies

Advanced Oxidation

The UV AOP at the Demo combined high intensity UV light with sodium hypochlorite to generate the necessary radicals for destruction a broad range of other chemical pollutants. DDW (2018) requires all IPR groundwater recharge and reservoir augmentation projects to provide, at a minimum, 0.5-log removal of 1,4-dioxane after the RO process. Destruction of 1,4-dioxane is a surrogate for broader removal of trace pollutants, as demonstrated by Hokanson et al. (2011) (Figure 3).

The destruction of 1,4-dioxane has been shown to directly correlate with the combined dose of UV and the oxidant (e.g., hypochlorite) (Oxnard (2018), City of Los Angeles (2018)), noting that performance appears to be site specific and the dose must be determined on site. To date, no UV AOP testing has been performed at the Demo, though the UV system is operating at a high UV dose (~1,600 mJ/cm²) and with a free chlorine feed concentration of ~2.5 to ~3.0 mg/L, sufficient to attain the DDW requirements for 0.5-log removal of 1,4-dioxane.




Figure 3 Destruction of Trace Pollutants by UV AOP (Hokanson et al., 2011)

Free Chlorination

The free chlorine dosed ahead of the UV reactor is dual-purpose, providing for advanced oxidation ahead of UV and also providing for a free chlorine residual that provides a measure of disinfection. While USEPA has clear guidance on pathogen credits for free chlorination in water, DDW relies upon regulatory analysis and guidance from Australia (WaterSecure, 2017), as shown in Figure 4 below.

| pH | Log ₁₀ inactivation | ≤0.2 NTU | | | | | ≤2 NTU | | | | | ≤5 NTU | | | | |
|------|--------------------------------|----------|-------|-------|-------|-------|--------|-------|-------|-------|-------|--------|-------|-------|-------|-------|
| | | 5 °C | 10 °C | 15 °C | 20 °C | 25 °C | 5 °C | 10 °C | 15 °C | 20 °C | 25 °C | 5 °C | 10 °C | 15 °C | 20 °C | 25 °C |
| ≤7 | 1 | 4 | 3 | 2 | 2 | 1 | 4 | 3 | 2 | 2 | 1 | 4 | 3 | 2 | 2 | 1 |
| | 2 | 5 | 4 | 3 | 2 | 2 | 5 | 4 | 3 | 2 | 2 | 6 | 4 | 3 | 2 | 2 |
| | 3 | 7 | 5 | 4 | 3 | 2 | 7 | 5 | 4 | 3 | 2 | 7 | 5 | 4 | 3 | 2 |
| | 4 | 8 | 6 | 4 | 3 | 2 | 9 | 6 | 4 | 3 | 2 | 9 | 7 | 5 | 3 | 3 |
| ≤7.5 | 1 | 7 | 5 | 4 | 3 | 2 | 7 | 5 | 4 | 3 | 2 | 8 | 6 | 4 | 3 | 2 |
| | 2 | 10 | 7 | 5 | 4 | 3 | 10 | 7 | 5 | 4 | 3 | 13 | 9 | 6 | 5 | 4 |
| | 3 | 13 | 9 | 7 | 5 | 4 | 13 | 9 | 7 | 5 | 4 | 16 | 12 | 9 | 6 | 5 |
| | 4 | 16 | 11 | 8 | 6 | 4 | 16 | 11 | 8 | 6 | 4 | 21 | 15 | 11 | 7 | 6 |
| ≤8 | 1 | 9 | 7 | 5 | 3 | 3 | 10 | 7 | 5 | 4 | 3 | 12 | 9 | 6 | 4 | 3 |
| | 2 | 14 | 10 | 7 | 5 | 4 | 15 | 10 | 7 | 5 | 4 | 19 | 13 | 9 | 7 | 5 |
| | 3 | 18 | 13 | 9 | 7 | 5 | 19 | 13 | 10 | 7 | 5 | 25 | 18 | 13 | 9 | 7 |
| | 4 | 23 | 16 | 12 | 8 | 6 | 23 | 16 | 12 | 8 | 6 | 32 | 23 | 16 | 11 | 8 |
| ≤8.5 | 1 | 11 | 8 | 6 | 4 | 3 | 12 | 9 | 6 | 5 | 4 | 14 | 10 | 7 | 5 | 4 |
| | 2 | 17 | 12 | 9 | 6 | 5 | 19 | 13 | 9 | 7 | 5 | 21 | 15 | 11 | 8 | 6 |
| | 3 | 23 | 16 | 12 | 9 | 6 | 25 | 17 | 13 | 9 | 7 | 29 | 21 | 15 | 10 | 8 |
| | 4 | 29 | 21 | 15 | 10 | 8 | 31 | 22 | 16 | 11 | 8 | 37 | 26 | 18 | 13 | 9 |
| ≤9 | 1 | 13 | 9 | 6 | 5 | 3 | 14 | 10 | 7 | 5 | 4 | 15 | 10 | 7 | 5 | 4 |
| | 2 | 20 | 14 | 10 | 7 | 5 | 22 | 16 | 11 | 8 | 6 | 23 | 16 | 12 | 8 | 6 |
| | 3 | 28 | 19 | 14 | 10 | 7 | 30 | 21 | 15 | 11 | 8 | 32 | 23 | 16 | 11 | 8 |
| | 4 | 35 | 25 | 17 | 12 | 9 | 38 | 27 | 19 | 13 | 10 | 41 | 29 | 20 | 14 | 10 |

Figure 4 CT Tables per the Australian Protocol (WaterSecure, 2017)

Following the UV is a small storage tank of ~30 gallons. Prior to a tasting event, the finished water will be fed into the container and held to achieve 4 LRV of virus based upon the information below. After holding, the water will go through a flash chilling device and to the tap for tasting.

The CT (free chlorine residual times contact time) required for different virus log reduction credits from WaterSecure (2017) can be calculated using a conservative temperature (20 degrees C in this case, which is well below the current finished water temperature of 23 to 24 degrees C) and pH of <7 (the pH in the finished water is ~5.5). CT values based upon LRV targets are shown below:

- 1 LRV of virus – Minimum CT of 2 mg-min/L.
- 2 LRV of virus – Minimum CT of 2 mg-min/L.
- 3 LRV of virus – Minimum CT of 3 mg-min/L.
- 4 LRV of virus – Minimum CT of 3 mg-min/L.

The operational plan is to provide the CT of >3 mg-min/L by storing the water for sufficient time with sufficient residual (e.g., 3 minutes at 1 mg/L of free chlorine). It should be noted that the Australian data was capped due to local regulations at 4 LRV. In addition, the experiments to produce the chlorination curves were not conducted on RO permeate, but filtered recycled water. On RO permeate, the efficacy of chlorine disinfection would be expected to be higher as there is no chlorine demand. If the curve were extrapolated to a contact time of 5 - 6 mg-min/L (i.e. waiting 6 minutes instead of 3) then arguably over 6 LRV for virus could be achieved. Accordingly, the 4 LRV claimed at a contact time of 3 minutes is conservative.

Pathogen Data

Limited testing of indigenous virus has been completed at the demo. To date, only one sampling event has been completed for indigenous pathogens, focusing only upon pepper mold mottle virus (PMMoV) and SARS-CoV-2 (Covid-19), with data showing robust reduction (~99%) of PMMoV across the low pressure membrane systems (MF and UF), and the lack of detection of SARS-CoV-2 in the tertiary feed water to the Demo as well as in the RO permeate.

Chemical Water Quality

Regulated Chemicals

A broad list of chemicals are regulated for potable water reuse projects, including inorganics, radioactivity, organics, disinfection byproducts, and other chemicals. The regulations utilize "maximum contaminant levels" (MCLs), secondary MCLs (sMCLs), and notification levels (NLs).

Appendix A contains a complete list of the regulated chemicals for a potable reuse project in California. Appendix B contains the raw sample results from the contract laboratory for the June 30th sampling event. Table 8 contains a list of all detected regulated chemicals based upon sampling for the full list of regulated chemicals (Appendix A). Note that all detected chemicals were found below regulated levels, with the exception of TON and chlorate which were subsequently solved through the use of higher quality sodium hypochlorite.

Table 8 Summary of Detected Chemicals with Regulatory Limits

| Constituent | Measured Value | Regulated Value |
|--------------------------------|---------------------------|-----------------|
| Bulk Parameters | | |
| Conductance | 49 umhos/cm | 900 umhos/cm |
| Total Dissolved Solids | 19 mg/L | 500 mg/L |
| Total Organic Carbon | 0.3 mg/L | 0.3 mg/L |
| TON | 12 ³ | 3 |
| Total Trihalomethanes | 41 ug/L | 80 ug/L |
| Total Nitrogen | 0.29 mg/L | 10 mg/L |
| Radioactivity | | |
| Gross Alpha | 0.48 pCi/L | 15 pCi/L |
| Gross Beta | 0.88 pCi/L | 50 pCi/L |
| Combined Radium-(226&228) | 0.508 pCi/L & 0.519 pCi/L | 5 pCi/L |
| Miscellaneous Chemicals | | |
| Chlorate | 1,100 ug/L ⁴ | 800 ug/L |
| Chloride | 7.8 mg/L | 250 mg/L |
| Formaldehyde | 6.8 ug/L | 100 ug/L |
| Sulfate | 1.5 mg/L | 250 mg/L |

Chemicals of Emerging Concern

A list of Chemicals of Emerging Concern (CECs) was also sampled, with all results presented below, including results below detectable levels.

- 19 CECs were not detected: Gimfibrozil (<1 ng/L), Ibuprofen (<1 ng/L), Iopromide (<5 ng/L), Naproxin (<1 ng/L), Acetaminophen (<20 ng/L), Amoxicillin (<400 ng/L), Atenolol (<1 ng/L), Caffeine (<1 ng/L), Carbamazepine (<1 ng/L), Cotinine (<2 ng/L), Diazepam (<1 ng/L), Meprobamate (<1 ng/L), Methadone (<1 ng/L), Phytoin (<65 ng/L), Primidone (<1 ng/L), Sulfamethoxazole (<1 ng/L), TCEP (<5 ng/L), TDCPP (<42 ng/L), and Trimethoprim (<1 ng/L).
- 10 CECs were detected. None are present at levels near or above health-based screening levels, where those levels have been established, as shown in the table below.

³ See section on TON, noting that the high TON value was an anomaly and subsequent values were at a TON of 1.

⁴ See section on Chlorate, noting that chlorate concentrations were the result of degraded sodium hypochlorite supplies.

Table 9 Summary of Detected CECs with Health Based Concentrations

| Detected Chemical | Detected Concentration in Finished Water (ng/L) | Health Screening Level for drinking (ng/L) ⁽¹⁾ |
|-------------------|---|---|
| Bisphenol A | 13 | 35,000 ⁽²⁾ |
| Salicylic Acid | 56 | 110,000 ⁽²⁾ |
| Triclosan | 4.5 | 2,100,000 |
| Atorvastatin | 4.7 | 1,000 ⁽²⁾ |
| Azithromycin | 43 | 120 ⁽²⁾ |
| Ciprofloxacin | 100 | 23,000 ⁽²⁾ |
| DEET | 3 | 200,000 |
| Fluoxetine | 8.3 | 2,000 ⁽²⁾ |
| Sucralose | 270 | 150,000,000 |
| TCCP | 140 | .. ⁽³⁾ |

Notes:

(1) Health screening and concentration data taken from Trussell et al. 2013 unless otherwise specified

(2) Health screening level taken from (Drewes et al. 2018). The lowest (most conservative) health screening value was selected.

(3) No health screening level available, lowest health screening level for a similar flame retardant TCEP from Drewes et al. 2018 is 2,500.

A broad range of Per and Polyfluoroalkyl Substances (PFAS) were included with the CEC analysis, noting that two PFAS chemicals (PFOA and PFOS) are regulated in California. Only PFHpH, which is not regulated, was found in the finished water, at a concentration of 9.9 ng/L⁵.

Chlorate

In initial testing, chlorate was found in the finished water from the Demo exceeding the DDW NL value of 800 $\mu\text{g/L}$. Other work on site suggested that the sodium hypochlorite feed stock provided by the chemical supplier was not “fresh”, meaning that the stock solution was old and had degraded, in some cases substantially. It is known that chlorate is a degradation product of sodium hypochlorite. Subsequent batches of sodium hypochlorite were obtained that were fresh, with a percent by weight over 13%. Those batches did not see the higher (and concerning) concentrations of chlorate. Data from several rounds of testing is shown in Figure 5, below. These data show that, under the important determination of “fresh” hypochlorite, a free chlorine dose of ~3 mg/L will not result in an exceedance of the DDW NL of 800 $\mu\text{g/L}$.

In addition to the chlorate testing, the District operators with assistance from Carollo are now taking the following steps to manage chlorate formation:

- Monitoring the concentration of hypochlorite deliveries upon arrival,
- Investigating alternate suppliers with less variable quality, and
- Continuing monitoring sampling of chlorate to increase water quality confidence.

⁵ See section on QA/QC, this detection was likely either a lab or sampling error.




Figure 5 Chlorate Concentrations at the Demo

Threshold Odor Number

Similar to the chlorate findings, initial TON values exceeded regulatory guidance (this time, exceeding the secondary MCL of 3 with a value of 12). Subsequent TON testing with “fresh” sodium hypochlorite documented TON values all of 1.

QA/QC

Perspective is important in analyzing one set of results for a broad range of contaminants. Often some of these chemicals are found in the low ng/L range. Improper sampling, contamination during transport, contamination in the laboratory, and laboratory error all contribute to a level of uncertainty with the final results. Repeated testing coupled with blanks, duplicates, and other measure of quality control are important for a level understanding of long-term results.

With that said, challenges with data quality are noted below:

- Analytical Recovery:
 - High recoveries, in excess of 150 percent, where seen for PFHpA, salicylic acid, amoxicillin, ciprofloxacin, meprobamate, continine, sucralose, sulfate, and chlorate.
 - Low recoveries, below 50 percent, where seen for diquat, iohexal, and phenytoin.
- Field Blanks:
 - For the finished water sampling on June 30th, all Per and Polyfluoroalkyl Substances (PFAS) were below detection with the exception of PFHpA, detected at 9.9 ng/L. However, the field blank for PFAS showed ND for all PFAS with the exception of PFHpA with a field blank value of 10 mg/L for that same chemical.
- Laboratory Blanks:
 - The following chemicals were found in laboratory blanks: atenolol, azithromycin, caffiene, ciprofloxacin, cotinine, galaxolide, quinoline, and sucralose. For simplicity, the measured concentrations are not listed here but can be found in Appendix B.

References

- California Department of Public Health (CDPH), 2014. *Groundwater Replenishment Reuse FINAL Regulation*, dated June, 2014.
- Cheryan, M., 1998 "Ultrafiltration and Microfiltration Handbook." CRC Press, Boca Raton, FL.
- Division of Drinking Water (DDW), 2018, California Regulations Related to Recycled Water. California Code of Regulation Title 22, Division 4, Chapter 3. California State Water Resources Control Board Division of Drinking Water. Published October 8, 2018.
https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/documents/lawbook/rwregulations_20181001a.pdf.
- Drewes, J E, P Anderson, N Denslow, W Jakubowski, A Olivieri, D Schlenk, and S Snyder (2018). Monitoring Strategies for Constituents of Emerging Concern in Recycled Water. Scientific Advisory Panel Report, Costa Mesa, CA: State Water Resources Control Board, Southern California Coastal Water Research Project.
- Gerba, C.P, Gramos, D.M, and Nwachukwu, N. (2002). Comparative Inactivation of Enteroviruses and Adenovirus 2 by UV Light. *Appl Environ Microbiol.* Oct 2002; 68(10): 5167–5169.
[10.1128/AEM.68.10.5167-5169.2002](https://doi.org/10.1128/AEM.68.10.5167-5169.2002).
- Hokanson, D., R. Trussell, S. Tiwari, G. Stolarik, A. Bazzi, J. Hinds, G. Wetterau, T. Richardson, and S. Dedovic-Hammond (2011). "Pilot Testing to Evaluate Advanced Oxidation Processes for Water Reuse", Proceedings Water Environment Federation Technical Exhibition and Conference, Los Angeles, CA, Oct. 15-19.
- Los Angeles (2018). Demonstration of Water Quality for Potable Reuse Report, Terminal Island Advanced Water Purification Facility Expansion: Dominguez Gap Barrier Project. A report by Carollo Engineers, Inc. and Walsh Construction. March 2018.
- Oxnard (2018). Engineering Report Groundwater Replenishment Reuse Project. A report by Carollo Engineers, Inc. December 2018.
- San Diego (2007) Advanced Water Treatment Research Studies, Final Report, prepared by MWH, August.
- Sharpless, C. and K. Linden (2003). "Experimental and Model Comparisons of Low- and Medium-Pressure Hg Lamps for the Direct and H₂O₂ Assisted UV Photo degradation of N-Nitrosodimethylamine in Simulated Drinking Water." *Environmental Science and Technology*, 37 (9), 1933-1940
- Swaim, P., A. Royce, T. Smith, T. Maloney, D. Ehlen, and B. Carter (2008). Effectiveness of UV advanced oxidation for destruction of micro-pollutants, *Ozone: Science and Engineering*, 30 (1), 34-42.
- Trussell, R.,R., A. Salveson, S., A. Snyder, R., S. Trussell, D. Gerrity, and B. Pecson (2013). Potable Reuse: State of the Science Report and Equivalency Criteria for Treatment Trains, WateReuse Research Foundation Project 11-02 Report. Alexandria, VA: WateReuse Research Foundation.
- USEPA (2005). *Membrane Filtration Guidance Manual*; EPA 815-R-06-009; Office of Water, U.S. Environmental Protection Agency, Cincinnati OH, 2005.
- USEPA (2010). "Water Research Foundation (WRF), Challenge Organisms for Inactivation of Viruses by Ultraviolet Treatment." 2010.
- USEPA (2018). Innovative Approaches to Validation of Ultraviolet (UV) Reactors for Disinfection in Drinking Water Systems. Office of Water, U.S. Environmental Protection Agency, Cincinnati OH, 2018.
- WaterSecure 2017, Chlorine disinfection, WaterVal validation protocol, Australian WaterSecure Innovations Ltd, Brisbane.

Appendix A

WATER QUALITY REQUIREMENTS FOR POTABLE WATER REUSE

Table A1 Inorganics with Primary MCLs or ALs⁽¹⁾

| Constituents | Primary MCL or AL (in mg/L) | Constituents | Primary MCL or AL (in mg/L) |
|-----------------------|--------------------------------|--------------------------|--------------------------------|
| Aluminum | 1.0 | Fluoride ⁽⁵⁾ | 2 |
| Antimony | 0.006 | Lead | 0.015 ^(3,4) |
| Arsenic | 0.010 | Mercury | 0.002 |
| Asbestos | 7 (MFL) ⁽²⁾ | Nickel | 0.1 |
| Barium | 1 | Nitrate (as N) | 10 |
| Beryllium | 0.004 | Nitrite (as N) | 1 |
| Cadmium | 0.005 | Nitrate + Nitrite (as N) | 10 |
| Chromium | 0.05 | Perchlorate | 0.006 |
| Copper ⁽⁵⁾ | 1.3 ⁽³⁾ | Selenium ⁽⁵⁾ | 0.05 |
| Cyanide | 0.15 | Thallium | 0.002 |

Notes:

(1) Based on Table 64431-A and Section 64678.

(2) MFL - Million fibers per liter, with fiber lengths > 10 microns.

(3) Regulatory Action Level; if system exceeds, it must take certain actions such as additional monitoring, corrosion control studies and treatment, and for lead, a public education program; replaces MCL.

(4) The MCL for lead was rescinded with the adoption of the regulatory action level described in footnote '3'.

(5) Central Coast Basin Plan Water Quality Objective is more stringent: copper-0.2 mg/L; fluoride-1 mg/L; selenium 0.02 mg/L.

Table A.2 Radioactivity⁽¹⁾

| Constituents | MCL (in pCi/L) | Constituents | MCL (in pCi/L) |
|----------------------------------|----------------|----------------------|-----------------------|
| Uranium | 20 | Beta/photon emitters | 50 ⁽²⁾ |
| Combined radium 226 & 228 | 5 | Strontium-90 | 8 ⁽²⁾ |
| Gross alpha particle activity | 15 | Tritium | 20,000 ⁽²⁾ |

Notes:

(1) Based on Tables 64442 and 64443.

(2) MCLs are intended to ensure that exposure above 4 millirem/yr does not occur.

Table A.3 Regulated Organics⁽¹⁾

| Constituents | MCL (in mg/L) | Constituents | MCL (in mg/L) |
|-----------------------------------|---------------|---------------------------------------|---------------|
| Volatile Organic Compounds | | | |
| Benzene | 0.001 | Monochlorobenzene | 0.07 |
| Carbon Tetrachloride | 0.0005 | Styrene | 0.1 |
| 1,2-Dichlorobenzene | 0.6 | 1,1,2,2-Tetrachloroethane | 0.001 |
| 1,4-Dichlorobenzene | 0.005 | Tetrachloroethylene | 0.005 |
| 1,1-Dichloroethane | 0.005 | Toluene | 0.15 |
| 1,2-Dichloroethane | 0.0005 | 1,2,4 Trichlorobenzene | 0.005 |
| 1,1-Dichloroethylene | 0.006 | 1,1,1-Trichloroethane | 0.2 |
| cis-1,2-Dichloroethylene | 0.006 | 1,1,2-Trichloroethane | 0.005 |
| trans-1,2-Dichloroethylene | 0.01 | Trichloroethylene | 0.005 |
| Dichloromethane | 0.005 | Trichlorofluoromethane | 0.15 |
| 1,3-Dichloropropene | 0.0005 | 1,1,2-Trichloro-1,2,2-Trifluoroethane | 1.2 |
| 1,2-Dichloropropane | 0.005 | Vinyl chloride | 0.0005 |
| Ethylbenzene | 0.3 | Xylenes | 1.75 |
| MTBE | 0.013 | | |
| SVOCs | | | |
| Alachlor | 0.002 | Heptachlor | 0.00001 |
| Atrazine | 0.001 | Heptachlor Epoxide | 0.00001 |
| Bentazon | 0.018 | Hexachlorobenzene | 0.001 |
| Benzo(a) Pyrene | 0.0002 | Hexachlorocyclopentadiene | 0.05 |
| Carbofuran | 0.018 | Lindane | 0.0002 |
| Chlordane | 0.0001 | Methoxychlor | 0.03 |
| Dalapon | 0.2 | Molinate | 0.02 |
| Dibromochloropropane | 0.0002 | Oxamyl | 0.05 |
| Di(2-ethylhexyl)adipate | 0.4 | Pentachlorophenol | 0.001 |
| Di(2-ethylhexyl)phthalate | 0.004 | Picloram | 0.5 |
| 2,4-D | 0.07 | Polychlorinated Biphenyls | 0.0005 |

| Constituents | MCL (in mg/L) | Constituents | MCL (in mg/L) |
|--------------------|---------------|------------------------|---------------------------|
| Dinoseb | 0.007 | Simazine | 0.004 |
| Diquat | 0.02 | Thiobencarb | 0.07/0.001 ⁽²⁾ |
| Endothall | 0.1 | Toxaphene | 0.003 |
| Endrin | 0.002 | 1,2,3-Trichloropropane | 5x10-6 |
| Ethylene Dibromide | 0.00005 | 2,3,7,8-TCDD (Dioxin) | 3x10-8 |
| Glyphosate | 0.7 | 2,4,5-TP (Silvex) | 0.05 |

Notes:

(1) Based on Table 64444-A.

(2) Second value is listed as a Secondary MCL.

Table A.4 Disinfection By-Products⁽¹⁾

| Constituents | MCL (in mg/L) | Constituents | MCL (in mg/L) |
|------------------------|---------------|--------------|---------------|
| Total Trihalomethanes | 0.080 | Bromate | 0.010 |
| Total haloacetic acids | 0.060 | Chlorite | 1.0 |

Note:

(1) Based on Table 64533-A.

Table A.5 Constituents/Parameters with Secondary MCLs

| Constituents ⁽¹⁾ | sMCL (in mg/L) | Constituents ⁽²⁾ | sMCL (in mg/L) |
|-----------------------------|----------------|-----------------------------|----------------|
| Aluminum | 0.2 | TDS | 500 |
| Color | 15 (units) | Specific Conductance | 900 uS/cm |
| Copper | 1 | Chloride | 250 |
| Foaming Agents (MBAS) | 0.5 | Sulfate | 250 |
| Iron | 0.3 | | |
| Manganese | 0.05 | | |
| MTBE | 0.005 | | |
| Odor Threshold | 3 (units) | | |
| Silver | 0.1 | | |
| Thiobencarb | 0.001 | | |

| Constituents ⁽¹⁾ | sMCL (in mg/L) | Constituents ⁽²⁾ | sMCL (in mg/L) |
|-----------------------------|------------------------|-----------------------------|----------------|
| Turbidity | 5 (NTU) ⁽³⁾ | | |
| Zinc ⁽⁴⁾ | 5 | | |

Notes:

(1) Based on Table 64449-A.

(2) Based on Table 64449-B.

(3) NTU - nephelometric turbidity unit; *uS/cm* - microsiemens per centimeter.

(4) Central Coast Basin Plan Water Quality Objective is more stringent: zinc-2 mg/L.

Table A.6 Constituents with Notification Levels^(1, 2)

| Constituents | NL (in µg/L) | Constituents ⁽³⁾ | NL (in µg/L) |
|------------------------------------|--------------|-------------------------------------|--------------|
| Boron ⁽⁴⁾ | 1,000 | Methyl isobutyl ketone (MIBK) | 120 |
| n-Butylbenzene | 260 | Naphthalene | 17 |
| sec-Butylbenzene | 260 | N-Nitrosodiethylamine (NDEA) | 0.01 |
| tert-Butylbenzene | 260 | N-Nitrosodimethylamine (NDMA) | 0.01 |
| Carbon disulfide | 160 | N-Nitrosodi-n-propylamine (NDPA) | 0.01 |
| Chlorate | 800 | Perfluorooctanoic acid (PFOA) | 0.0051 |
| 2-Chlorotoluene | 140 | Perfluorooctanesulfonic acid (PFOS) | 0.0065 |
| 4-Chlorotoluene | 140 | Propachlor | 90 |
| Diazinon | 1.2 | n-Propylbenzene | 260 |
| Dichlorodifluoromethane (Freon 12) | 1,000 | RDX ⁽³⁾ | 0.3 |
| 1,4-Dioxane | 1 | Tertiary butyl alcohol (TBA) | 12 |
| Ethylene glycol | 14,000 | 1,2,4-Trimethylbenzene | 330 |
| Formaldehyde | 100 | 1,3,5-Trimethylbenzene | 330 |
| HMX | 350 | 2,4,6-Trinitrotoluene (TNT) | 1 |
| Isopropylbenzene | 770 | Vanadium | 50 |
| Manganese | 500(2) | | |

Notes:

(1) Based on https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/documents/notificationlevels/notification_levels_response_levels_overview.pdf, published August 23, 2019

(2) The web link above also contains the levels of the pollutants in this table that must result in a removal of the water source from service.

(3) RDX - Research Department Explosive (O₂NNCH₂)₃.

(4) Central Coast Basin Plan Water Quality Objective is more stringent: boron- 750 ug/L (500 ug/L is the "no problem" water quality guideline); vanadium-

Table A.7 Monitoring Requirements for CECs per SWRCB (2019a)

| Constituent | Relevance | MTL (in µg/L) | Example Removal Percentages (%) |
|---|-------------------------|---------------|---------------------------------|
| 1,4-dioxane | Health | 1 | -- |
| NDMA ⁽¹⁾ | Health and Performance | 0.010 | >25-50, 80 |
| NMOR ⁽²⁾ | Health | 0.012 | -- |
| PFOS | Health | 0.013 | -- |
| PFOA | Health | 0.014 | -- |
| Sulfamethoxazole ⁽²⁾ | Performance | - | >90 |
| Sucralose ⁽²⁾ | Performance | - | >90 |
| Dissolved Organic Carbon ⁽²⁾ | Surrogate (example) | - | >90 |
| UV Absorbance ⁽²⁾ | Surrogate (example) | - | >50 |
| EC ⁽²⁾ | Surrogate (example) | - | >90 |
| Estrogen receptor-alpha bioassay ⁽²⁾ | Bioanalytical Screening | - | -- |
| Aryl hydrocarbon bioassay ⁽²⁾ | Bioanalytical Screening | - | -- |

Notes:

- (1) Health-based CECs and Bioanalytical Screening to be monitored following treatment.
- (2) Performance indicator CECs to be monitored before RO and after treatment.
- (3) Surrogates are provided as examples. Surrogates should be used to demonstrate effectiveness.

Appendix B

LABORATORY REPORT FOR JUNE 30TH, 2020 SAMPLING EVENT

Work Orders: 0F30024

Report Date: 8/21/2020

Project: Pure Water Testing

Received Date: 6/30/2020

Turnaround Time: Normal

Phones: (818) 251-2200

Fax: (818) 251-2109

Attn: Frank Almaguer

P.O. #:

Client: Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Billing Code:

DoD-ISO ANAB # • ELAP-CA #1132 • EPA-UCMR #CA00211 • HW-DOH # • ISO17025 ANAB #L2457.01 • LACSD #10143 •
NELAP-OR #4047 • NJ-DEP #CA015 • SCAQMD #93LA1006

This is a complete final report. The information in this report applies to the samples analyzed in accordance with the chain-of-custody document. Weck Laboratories certifies that the test results meet all requirements of TNI unless noted by qualifiers or written in the Case Narrative. This analytical report must be reproduced in its entirety.

Dear Frank Almaguer,


Enclosed are the results of analyses for samples received 6/30/20 with the Chain-of-Custody document. The samples were received in good condition, at 3.4 °C and on ice. All analyses met the method criteria except as noted in the case narrative or in the report with data qualifiers.

Reviewed by:



Regina M. Giancola
Project Manager





WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Sample Summary

| Sample Name | Sampled By | Lab ID | Matrix | Sampled | Qualifiers |
|----------------|------------|------------|--------|----------------|------------|
| Finished Water | ATS | 0F30024-01 | Water | 06/30/20 10:00 | |
| Field Blank | | 0F30024-02 | Water | 06/30/20 09:30 | |

Analyses Accreditation Summary

| Analyte | CAS # | Not By NELAP | ANAB ISO 17025 |
|------------------------------|-------------|-----------------|-------------------|
| EPA 521 in Water | | | |
| N-Nitrosodimethylamine | 62-75-9 | ✓ | |
| N-Nitrosomethylethylamine | 10595-95-6 | ✓ | |
| N-Nitrosodiethylamine | 55-18-5 | ✓ | |
| N-Nitrosodi-n-propylamine | 621-64-7 | ✓ | |
| N-Nitrosomorpholine | 59-89-2 | ✓ | |
| N-Nitrosopyrrolidine | 930-55-2 | ✓ | |
| N-Nitrosopiperidine | 100-75-4 | ✓ | |
| N-Nitrosodi-n-butylamine | 924-16-3 | ✓ | |
| NDMA-d6 | | ✓ | |
| EPA 556 in Water | | | |
| Formaldehyde | 50-00-0 | ✓ | |
| 2,4,5-TFAP | 129322-83-4 | ✓ | |
| LC/MS/MS in Water | | | |
| Iohexol | 66108-95-0 | ✓ | |
| SM 5910B in Water | | | |
| UV 254 | | ✓ | |
| SRL 524M-TCP in Water | | | |
| 1,2,3-Trichloropropane | 96-18-4 | ✓ | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Project Manager: Frank Almaguer

Certificate of Analysis

FINAL REPORT


Reported:

08/21/2020 15:59

Sample Results

Sample: Finished Water
0F30024-01 (Water) Sampled: 06/30/20 10:00 by ATS

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|--|---------------------------------|--------------------------|--------|--------------|----------|-----------|
| 1,4-Dioxane by SPE/GCMS SIM, EPA Method 522 | | | | | | |
| Method: EPA 522 | | Instr: GCMS20 | | | | |
| Batch ID: W0F1841 | Preparation: EPA 522/SPE | Prepared: 07/01/20 09:00 | | Analyst: mld | | |
| 1,4-Dioxane | ND | 0.070 | ug/l | 1 | 07/02/20 | |
| Surrogate(s) | | | | | | |
| 1,4-Dioxane-d8 | 98% | Conc: 9.84 | 70-130 | | 07/02/20 | |
| Acrylamide low levels by EPA Method 8316 | | | | | | |
| Method: EPA 8316 | | Instr: LCMS02 | | | | |
| Batch ID: W0G0592 | Preparation: _NONE (LC) | Prepared: 07/13/20 11:28 | | Analyst: kan | | |
| Acrylamide | ND | 0.10 | ug/l | 1 | 07/13/20 | |
| Aldehydes and Carbonyl Compounds by GC/ECD | | | | | | |
| Method: EPA 556 | | Instr: GC08 | | | | |
| Batch ID: W0G0132 | Preparation: EPA 556/Micro Ext. | Prepared: 07/06/20 08:35 | | Analyst: amw | | |
| Formaldehyde | 6.8 | 2.0 | ug/l | 1 | 07/10/20 | |
| Surrogate(s) | | | | | | |
| 2,4,5-TFAP | 112% | Conc: 22.4 | 70-130 | | 07/10/20 | |
| Anions by IC, EPA Method 300.0 | | | | | | |
| Method: EPA 300.0 | | Instr: LC04 | | | | |
| Batch ID: W0G0250 | Preparation: _NONE (LC) | Prepared: 07/07/20 12:35 | | Analyst: jna | | |
| Chloride, Total | 7.8 | 1.0 | mg/l | 2 | 07/10/20 | |
| Fluoride, Total | ND | 0.20 | mg/l | 2 | 07/10/20 | |
| Sulfate as SO4 | 1.5 | 1.0 | mg/l | 2 | 07/10/20 | |
| Anions by IC, EPA Method 300.1 | | | | | | |
| Method: EPA 300.1 | | Instr: LC08 | | | | |
| Batch ID: W0G0041 | Preparation: _NONE (LC) | Prepared: 07/01/20 12:47 | | Analyst: jna | | |
| Bromate | ND | 5.0 | ug/l | 1 | 07/02/20 | |
| Chlorite | ND | 10 | ug/l | 1 | 07/02/20 | |
| Surrogate(s) | | | | | | |
| Dichloroacetate | 100% | Conc: 500 | 90-115 | | 07/02/20 | |
| Carbamates and Urea Pesticides | | | | | | |
| Method: EPA 531.2 | | Instr: LC10 | | | | |
| Batch ID: W0G0155 | Preparation: _NONE (LC) | Prepared: 07/06/20 11:34 | | Analyst: jna | | |
| 3-Hydroxycarbofuran | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |
| Aldicarb | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |
| Aldicarb sulfone | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |
| Aldicarb sulfoxide | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |
| Carbaryl | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |
| Carbofuran | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |
| Methiocarb | ND | 10 | ug/l | 5 | 07/07/20 | M-05 |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water)

Sampled: 06/30/20 10:00 by ATS

(Continued)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier

Carbamates and Urea Pesticides (Continued)

Method: EPA 531.2

Instr: LC10

Batch ID: W0G0155

Preparation: _NONE (LC)

Prepared: 07/06/20 11:34

Analyst: jna

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Rows include Methomyl, Oxamyl, Propoxur (Baygon).

Surrogate(s)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Row includes BDMC.

Chlorinated Acids Herbicides by GC/ECD

Method: EPA 515.4

Instr: GC08

Batch ID: W0G0176

Preparation: EPA 515.4/Micro Ext. Drtz

Prepared: 07/07/20 08:15

Analyst: amw

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Rows include 2,4,5-T, 2,4,5-TP (Silvex), 2,4-D, 2,4-DB, 3,5-Dichlorobenzoic acid, Acifluorfen, Bentazon, Dalapon, DCPA, Dicamba, Dichloroprop, Dinoseb, Pentachlorophenol, Picloram.

Surrogate(s)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Row includes 2,4-DCAA.

Chlorinated Pesticides and/or PCBs by GC/ECD

Method: EPA 508

Instr: GC07

Batch ID: W0G0230

Preparation: EPA 508/L-L SF


Prepared: 07/07/20 10:20

Analyst: AMW

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Rows include 4,4'-DDD, 4,4'-DDE, 4,4'-DDT, Aldrin, alpha-BHC, Aroclor 1016, Aroclor 1221, Aroclor 1232, Aroclor 1242.

0F30024

Page 4 of 55



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Project Manager: Frank Almaguer

Certificate of Analysis

FINAL REPORT

Reported: 08/21/2020 15:59

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water)

Sampled: 06/30/20 10:00 by ATS
(Continued)


Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier

Chlorinated Pesticides and/or PCBs by GC/ECD (Continued)

Main table for Chlorinated Pesticides and/or PCBs by GC/ECD. Includes Method: EPA 508, Instr: GC07, and various analyte results like Aroclor 1248, beta-BHC, etc.

Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods

Table for Conventional Chemistry/Physical Parameters. Includes Method: _Various, Instr: [CALC], and results for Total Anions, Total Cations, Total Hardness as CaCO3.



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water)
Sampled: 06/30/20 10:00 by ATS
(Continued)

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|--|---------------------------------------|-------|-------------|---------------------------------|----------------|---------------------|
| Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods (Continued) | | | | | | |
| Method: EPA 180.1 | | | | Instr: TURB01 | | |
| Batch ID: W0G0068 | Preparation: _NONE (WETCHEM) | | | Prepared: 07/01/20 17:18 | | Analyst: SBN |
| Turbidity | ND | 0.10 | NTU | 1 | 07/01/20 17:35 | |
| Method: EPA 335.4 | | | | Instr: AA01 | | |
| Batch ID: W0G0140 | Preparation: MIDI-Distillation | | | Prepared: 07/06/20 09:28 | | Analyst: SAR |
| Cyanide, Total | ND | 5.0 | ug/l | 1 | 07/08/20 | |
| Method: EPA 353.2 | | | | Instr: AA01 | | |
| Batch ID: W0F1837 | Preparation: _NONE (WETCHEM) | | | Prepared: 06/30/20 17:39 | | Analyst: ymt |
| Nitrate as N | 0.29 | 0.20 | mg/l | 1 | 07/01/20 17:12 | |
| Nitrite as N | ND | 100 | ug/l | 1 | 07/01/20 17:12 | |
| NO2+NO3 as N | 290 | 200 | ug/l | 1 | 07/01/20 | |
| Method: SM 2120B | | | | Instr: _ANALYST | | |
| Batch ID: W0F1838 | Preparation: _NONE (WETCHEM) | | | Prepared: 06/30/20 17:45 | | Analyst: ism |
| Color | ND | 3.0 | Color Units | 1 | 07/01/20 13:32 | |
| Method: SM 2320B | | | | Instr: AA02 | | |
| Batch ID: W0G0013 | Preparation: _NONE (WETCHEM) | | | Prepared: 07/01/20 09:41 | | Analyst: sbn |
| Alkalinity as CaCO3 | 8.7 | 5.0 | mg/l | 1 | 07/01/20 | |
| Bicarbonate Alkalinity as HCO3 | 11 | 6.1 | mg/l | 1 | 07/01/20 | |
| Carbonate Alkalinity as CaCO3 | ND | 5.0 | mg/l | 1 | 07/01/20 | |
| Hydroxide Alkalinity as CaCO3 | ND | 5.0 | mg/l | 1 | 07/01/20 | |
| Method: SM 2510B | | | | Instr: AA02 | | |
| Batch ID: W0G0099 | Preparation: _NONE (WETCHEM) | | | Prepared: 07/02/20 11:31 | | Analyst: sbn |
| Specific Conductance (EC) | 49 | 2.0 | umhos/cm | 1 | 07/02/20 | |
| Method: SM 2540C | | | | Instr: OVEN01 | | |
| Batch ID: W0F1765 | Preparation: _NONE (WETCHEM) | | | Prepared: 07/01/20 11:15 | | Analyst: ism |
| Total Dissolved Solids | 19 | 10 | mg/l | 1 | 07/01/20 | |
| Method: SM 4500H+-B | | | | Instr: AA02 | | |
| Batch ID: W0F1828 | Preparation: _NONE (WETCHEM) | | | Prepared: 06/30/20 16:31 | | Analyst: sbn |
| pH | 6.09 | 0.10 | Units | 1 | 06/30/20 17:26 | * |
| Method: SM 5310B | | | | Instr: TOC02 | | |
| Batch ID: W0G0163 | Preparation: SM 5310B_comb | | | Prepared: 07/06/20 13:18 | | Analyst: jlp |
| Dissolved Organic Carbon | 0.30 | 0.30 | mg/l | 1 | 07/06/20 | A-01 |
| Method: SM 5540C | | | | Instr: UVVIS04 | | |
| Batch ID: W0G0004 | Preparation: _NONE (WETCHEM) | | | Prepared: 07/01/20 09:06 | | Analyst: mfh |
| MBAS | ND | 0.050 | mg/l | 1 | 07/01/20 17:26 | |
| Method: SM 5910B | | | | Instr: UVVIS04 | | |
| Batch ID: W0G0009 | Preparation: _NONE (WETCHEM) | | | Prepared: 07/01/20 09:22 | | Analyst: ssi |
| UV 254 | ND | 0.009 | 1/cm | 1 | 07/01/20 10:15 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water) Sampled: 06/30/20 10:00 by ATS
(Continued)

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|---------|--------|-----|-------|-----|----------|-----------|
|---------|--------|-----|-------|-----|----------|-----------|

Diquat and Paraquat by EPA 549.2

| | | | | | | |
|--------------------------|-----------------------------------|---------------------------------|------|---------------------|----------|--|
| Method: EPA 549.2 | | Instr: LC11 | | | | |
| Batch ID: W0G0142 | Preparation: EPA 549.2/SPE | Prepared: 07/06/20 09:29 | | Analyst: jna | | |
| Diquat | ND | 4.0 | ug/l | 1 | 07/09/20 | |

Endothall By EPA 548.1

| | | | | | | |
|--------------------------|-----------------------------------|---------------------------------|------|---------------------|----------|--|
| Method: EPA 548.1 | | Instr: GCMS06 | | | | |
| Batch ID: W0G0141 | Preparation: EPA 548.1/SPE | Prepared: 07/06/20 09:28 | | Analyst: rmr | | |
| Endothall | ND | 45 | ug/l | 1 | 07/08/20 | |

Explosives by EPA Method 8330

| | | | | | | |
|----------------------------|----------------------------------|---------------------------------|------|---------------------|----------|--|
| Method: EPA 8330A | | Instr: LC11 | | | | |
| Batch ID: W0G0131 | Preparation: EPA 8330/SPE | Prepared: 07/06/20 08:04 | | Analyst: jna | | |
| 1,3,5-Trinitrobenzene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 1,3-Dinitrobenzene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 2,4,6-Trinitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 2,4-Dinitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 2,6-Dinitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 2-Amino-4,6-Dinitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 2-Nitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 3-Nitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 4-Amino-2,6-Dinitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| 4-Nitrotoluene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| HMX | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| Nitrobenzene | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| RDX | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| Tetryl | ND | 1.0 | ug/l | 1 | 07/08/20 | |

Glycols by GC/FID

| | | | | | | |
|--------------------------|----------------------------------|---------------------------------|------|---------------------|----------|--|
| Method: EPA 8015B | | Instr: GC09 | | | | |
| Batch ID: W0F1735 | Preparation: _NONE (SVOC) | Prepared: 06/30/20 15:30 | | Analyst: rjg | | |
| Ethylene glycol | ND | 10 | mg/l | 1 | 06/30/20 | |

Glyphosate by EPA 547


| | | | | | | |
|--------------------------|--------------------------------|---------------------------------|------|---------------------|----------|--|
| Method: EPA 547 | | Instr: LC10 | | | | |
| Batch ID: W0F1710 | Preparation: _NONE (LC) | Prepared: 06/30/20 14:57 | | Analyst: jna | | |
| Glyphosate | ND | 5.0 | ug/l | 1 | 06/30/20 | |

Haloacetic Acids (HAAs) by GC/ECD

| | | | | | | |
|----------------------------|---|---------------------------------|------|---------------------|----------|--|
| Method: EPA 552.3 | | Instr: GC05 | | | | |
| Batch ID: W0G0076 | Preparation: EPA 552.3/Micro Ext. Drtz | Prepared: 07/02/20 08:41 | | Analyst: rjg | | |
| Dibromoacetic acid (dbaa) | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| Dichloroacetic acid (dcaa) | ND | 1.0 | ug/l | 1 | 07/08/20 | |
| HAA5, Total | ND | 1.0 | ug/l | 1 | 07/08/20 | |

0F30024

Page 7 of 55



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)


Sample: Finished Water
0F30024-01 (Water)
Sampled: 06/30/20 10:00 by ATS
(Continued)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Haloacetic Acids (HAAs) by GC/ECD (Continued). Includes method EPA 552.3, batch W0G0076, and analytes like Monobromoacetic acid (mbaa), Monochloroacetic acid (mcaa), Trichloroacetic acid (tcaa), and 2-Bromobutyric acid.

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Low Level 1,2,3-TCP by SRL Method, P&T, GC/MS SIM. Includes method SRL 524M-TCP, batch W0G0002, and analyte 1,2,3-Trichloropropane.

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Metals by EPA 200 Series Methods. Includes method EPA 200.7, batch W0G0033, and analytes like Boron, Calcium, Iron, Magnesium, Potassium, Sodium.

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Metals by EPA 200 Series Methods. Includes method EPA 200.8, batch W0G0423, and analytes like Aluminum, Antimony, Arsenic, Barium, Beryllium, Cadmium, Chromium, Copper, Lead, Manganese, Nickel, Selenium, Silver, Thallium, Vanadium, Zinc.



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Project Manager: Frank Almaguer

Certificate of Analysis

FINAL REPORT

Reported: 08/21/2020 15:59

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water)
Sampled: 06/30/20 10:00 by ATS
(Continued)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Metals by EPA 200 Series Methods (Continued). Includes rows for Mercury, Total with ND result and 0.050 MRL.

Nitrosamines by CI GC/MS/MS, EPA 521

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Nitrosamines by CI GC/MS/MS, EPA 521. Includes rows for various nitrosamines (N-Nitrosodiethylamine, etc.) and NDMA-d6 with 85% result.

Organic Compounds by Tandem LC/MS/MS


Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Organic Compounds by Tandem LC/MS/MS. Includes row for Iohexol with ND result and 5.0 MRL.

Per- and Polyfluorinated Alkyl Substances (PFAS) by SPE/LCMSMS

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Section: Per- and Polyfluorinated Alkyl Substances (PFAS) by SPE/LCMSMS. Includes rows for various PFAS compounds like 11CI-PF3OUdS, ADONA, etc., with ND results and 1.8 MRL.

0F30024

Page 9 of 55



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water)

Sampled: 06/30/20 10:00 by ATS

(Continued)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier

Per- and Polyfluorinated Alkyl Substances (PFAS) by SPE/LCMSMS (Continued)

Table containing PFAS results including PFOA, PFOS, PFTeDA, PFTrDA, PFUnA, and surrogate compounds like 13C2-PFDA, 13C2-PFHxA, d5-EtFOSAA, HFPO-DA-13C3.

Perchlorate by EPA 314.0

Table for Perchlorate results showing Method: EPA 314.0, Batch ID: W0F1821, and result ND.

PPCPs - Pharmaceuticals by LC/MSMS-ESI-

Table for PPCPs - Pharmaceuticals by LC/MSMS-ESI- including Bisphenol A, Diclofenac, Gemfibrozil, Ibuprofen, Iopromide, Naproxen, Salicylic Acid, and Triclosan.

PPCPs - Pharmaceuticals by LC/MSMS-ESI+

Table for PPCPs - Pharmaceuticals by LC/MSMS-ESI+ including Acetaminophen, Amoxicillin, Atenolol, Atorvastatin, Azithromycin, Caffeine, Carbamazepine, and Ciprofloxacin.

0F30024

Las Virgenes Municipal Water District
 4232 Las Virgenes Road
 Calabasas, CA 91302

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Finished Water
 0F30024-01 (Water)

Sampled: 06/30/20 10:00 by ATS

(Continued)


| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|--|----------------------------------|---------------------------------|-------|---------------------|----------|------------------|
| PPCPs - Pharmaceuticals by LC/MSMS-ESI+ (Continued) | | | | | | |
| Method: EPA 1694M-ESI+ | | Instr: LCMS03 | | | | |
| Batch ID: W0G1399 | Preparation: EPA 3535/SPE | Prepared: 07/28/20 08:00 | | Analyst: kan | | |
| Cotinine | ND | 2.0 | ng/l | 1 | 08/10/20 | |
| DEET | 3.0 | 1.0 | ng/l | 1 | 08/10/20 | |
| Diazepam | ND | 1.0 | ng/l | 1 | 08/10/20 | |
| Fluoxetine | 8.3 | 1.0 | ng/l | 1 | 08/10/20 | |
| Meprobamate | ND | 1.0 | ng/l | 1 | 08/10/20 | |
| Methadone | ND | 1.0 | ng/l | 1 | 08/10/20 | |
| Phenytoin (Dilantin) | ND | 65 | ng/l | 1 | 08/10/20 | BS-L, I-05, R-01 |
| Primidone | ND | 1.0 | ng/l | 1 | 08/10/20 | |
| Sucralose | 270 | 5.0 | ng/l | 1 | 08/10/20 | B, BS-04 |
| Sulfamethoxazole | ND | 1.0 | ng/l | 1 | 08/10/20 | |
| TCEP | ND | 5.0 | ng/l | 1 | 08/10/20 | R-01 |
| TCP | 140 | 1.0 | ng/l | 1 | 08/10/20 | E-01 |
| TDCPP | ND | 42 | ng/l | 1 | 08/10/20 | R-01 |
| Trimethoprim | ND | 1.0 | ng/l | 1 | 08/10/20 | |

Radiological Parameters by APHA/EPA Methods

| | | | | | | |
|--------------------------|---------------------------------------|---------------------------------|-------|---------------------|----------|--|
| Method: EPA 200.8 | | Instr: ICPMS04 | | | | |
| Batch ID: W0G0675 | Preparation: EPA 200.2 | Prepared: 07/09/20 11:55 | | Analyst: mtt | | |
| Uranium Rad | ND | 0.13 | pCi/L | 1 | 07/13/20 | |
| Method: EPA 900.0 | | Instr: RAD02 | | | | |
| Batch ID: W0G0146 | Preparation: _NONE (RADIOCHEM) | Prepared: 07/06/20 10:01 | | Analyst: mem | | |
| Gross Alpha | 0.48 | | pCi/L | 1 | 07/07/20 | |
| Uncertainty: 0.259 | MDA: 0.392 | | | | | |
| Gross Beta | 0.88 | | pCi/L | 1 | 07/07/20 | |
| Uncertainty: 0.539 | MDA: 0.878 | | | | | |

Semivolatile Organic Compounds by GC/MS

| | | | | | | |
|----------------------------|-----------------------------------|---------------------------------|------|---------------------|----------|--|
| Method: EPA 525.2 | | Instr: GCMS16 | | | | |
| Batch ID: W0G0136 | Preparation: EPA 525.2/SPE | Prepared: 07/06/20 09:10 | | Analyst: rmr | | |
| Alachlor | ND | 0.10 | ug/l | 1 | 07/22/20 | |
| Atrazine | ND | 0.10 | ug/l | 1 | 07/22/20 | |
| Benzo (a) pyrene | ND | 0.10 | ug/l | 1 | 07/22/20 | |
| Bis(2-ethylhexyl)adipate | ND | 5.0 | ug/l | 1 | 07/22/20 | |
| Bis(2-ethylhexyl)phthalate | ND | 3.0 | ug/l | 1 | 07/22/20 | |
| Bromacil | ND | 0.50 | ug/l | 1 | 07/22/20 | |
| Butachlor | ND | 0.10 | ug/l | 1 | 07/22/20 | |
| Captan | ND | 1.0 | ug/l | 1 | 07/22/20 | |
| Chlorpropham | ND | 0.10 | ug/l | 1 | 07/22/20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water)

Sampled: 06/30/20 10:00 by ATS
(Continued)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier

Semivolatile Organic Compounds by GC/MS (Continued)

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Includes Method: EPA 525.2, Instr: GCMS16, and various pesticides like Cyanazine, Diazinon, etc.

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Includes Surrogate(s) like 1,3-Dimethyl-2-nitrobenzene, Perylene-d12, Triphenyl phosphate.

Semivolatile Organics - Low Level by Tandem GC/MS/MS

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Includes Method: EPA 1613B, Instr: GCMS19, and 2,3,7,8-TCDD (Dioxin).

Volatile Organic Compounds by P&T and GC/MS


Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Includes Method: EPA 524.2, Instr: GCMS14, and Epichlorohydrin, Tert-butyl alcohol.

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Includes Surrogate(s) like 1,2-Dichlorobenzene-d4, 4-Bromofluorobenzene.

Volatile Organics by P&T and GC/MS

Table with 7 columns: Analyte, Result, MRL, Units, Dil, Analyzed, Qualifier. Includes Method: EPA 524.3, Instr: GCMS04, and 1,2-Dibromo-3-chloropropane, 1,2-Dibromoethane (EDB).

0F30024



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer



Sample Results

(Continued)

Sample: Finished Water
0F30024-01 (Water) Sampled: 06/30/20 10:00 by ATS
(Continued)

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|---------|--------|-----|-------|-----|----------|-----------|
|---------|--------|-----|-------|-----|----------|-----------|

Volatile Organics by P&T and GC/MS (Continued)

Method: EPA 524.3 **Instr:** GCMS04
Batch ID: W0G0107 **Preparation:** EPA 524.2 P&T
Prepared: 07/02/20 13:16 **Analyst:** adm


Sample: Finished Water
0F30024-01RE1 (Water) Sampled: 06/30/20 10:00 by ATS

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|---------|--------|-----|-------|-----|----------|-----------|
|---------|--------|-----|-------|-----|----------|-----------|

Anions by IC, EPA Method 300.1

Method: EPA 300.1 **Instr:** LC08
Batch ID: W0G0041 **Preparation:** _NONE (LC)
Prepared: 07/01/20 12:47 **Analyst:** jna

| | | | | | | |
|---------------------|------|-----------|--------|---|----------|--|
| Chlorate | 1100 | 50 | ug/l | 5 | 07/02/20 | |
| <i>Surrogate(s)</i> | | | | | | |
| Dichloroacetate | 100% | Conc: 501 | 90-115 | | 07/02/20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Sample Results

(Continued)

Sample: Field Blank

Sampled: 06/30/20 9:30 by

0F30024-02 (Water)

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|---------|--------|-----|-------|-----|----------|-----------|
|---------|--------|-----|-------|-----|----------|-----------|

Per- and Polyfluorinated Alkyl Substances (PFAS) by SPE/LCMSMS

Method: EPA 537.1

Instr: LCMS06

Batch ID: W0G0516

Preparation: EPA 537/SPE

Prepared: 07/10/20 15:31

Analyst: jam

| | | | | | | |
|--------------|----|-----|------|---|----------|---|
| 11CI-PF3OUdS | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| 9CI-PF3ONS | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| ADONA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| EtFOSAA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| HFPO-DA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| MeFOSAA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFBS | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFDA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFDoA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFHpA | 10 | 1.7 | ng/l | 1 | 07/14/20 | B |
| PFHxA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFHxS | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFNA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFOA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFOS | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFTeDA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFTTrDA | ND | 1.7 | ng/l | 1 | 07/14/20 | |
| PFUnA | ND | 1.7 | ng/l | 1 | 07/14/20 | |

Surrogate(s)

| | | | | |
|--------------|------|------------|--------|----------|
| 13C2-PFDA | 120% | Conc: 40.4 | 70-130 | 07/14/20 |
| 13C2-PFHxA | 125% | Conc: 42.0 | 70-130 | 07/14/20 |
| d5-EtFOSAA | 107% | Conc: 35.9 | 70-130 | 07/14/20 |
| HFPO-DA-13C3 | 112% | Conc: 37.9 | 70-130 | 07/14/20 |

Volatile Organics by P&T and GC/MS

Method: EPA 524.3

Instr: GCMS04


Batch ID: W0G0107

Preparation: EPA 524.2 P&T

Prepared: 07/02/20 13:16

Analyst: adm

| | | | | | | |
|-----------------------------|----|-------|------|---|----------|--|
| 1,2-Dibromo-3-chloropropane | ND | 0.010 | ug/l | 1 | 07/03/20 | |
| 1,2-Dibromoethane (EDB) | ND | 0.020 | ug/l | 1 | 07/03/20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Project Manager: Frank Almaguer

FINAL REPORT


Reported:
08/21/2020 15:59



Sample Results LA Testing - EMSL Analytical, Inc. CA-ELAP #2283, Non-NELAP

Sample: Finished Water
0F30024-01 (Water) Sampled: 06/30/20 10:00 by ATS

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|--------------------------|----------------------------|---------------------------------|-------|-----|----------|----------------------|
| EPA 100.2 | | | | | | |
| Method: EPA 100.2 | Batch ID: 322011638 | Prepared: 07/01/20 11:45 | | | | Analyst: _SUB |
| Asbestos | ND | 0.20 | MFL | 1 | 07/10/20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer




Sample Results Pace Analytical Services, Inc.

(Continued)

Sample: Finished Water
0F30024-01 (Water) Sampled: 06/30/20 10:00 by ATS

| Analyte | Result | MRL | Units | Dil | Analyzed | Qualifier |
|---------------------------|-------------------------|---------------------------------|-----------|-----|----------|---------------------|
| EPA 903.1 | | | | | | |
| Method: EPA 903.1 | Batch ID: 404026 | Prepared: 07/10/20 00:00 | | | | Analyst: MK1 |
| Radium-226 | 0.508 | | pCi/L dry | 1 | 07/17/20 | |
| Uncertainty: 0.431 | MDA: 0.590 | | | | | |
| EPA 904.0 | | | | | | |
| Method: EPA 904.0 | Batch ID: 404025 | Prepared: 07/10/20 00:00 | | | | Analyst: VAL |
| Radium-228 | 0.519 | | pCi/L dry | 1 | 07/16/20 | |
| Uncertainty: 0.438 | MDA: 0.903 | | | | | |
| EPA 905.0 | | | | | | |
| Method: EPA 905.0 | Batch ID: 405208 | Prepared: 07/15/20 00:00 | | | | Analyst: JJY |
| Strontium-90 | -0.203 | | pCi/L dry | 1 | 07/20/20 | |
| Uncertainty: 0.377 | MDA: 0.769 | | | | | |
| EPA 906.0 | | | | | | |
| Method: EPA 906.0 | Batch ID: 404450 | Prepared: 07/10/20 00:00 | | | | Analyst: CLA |
| Tritium | -77.3 | | pCi/L dry | 1 | 07/11/20 | |
| Uncertainty: 127 | MDA: 232 | | | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

EPA 903.1

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|---|--------|------------|-----------|-------------|---------------|------|-----------|-----|-------|-----------|
| Batch: 404026 - EPA 903.1 | | | | | | | | | | |
| DUP (30370902001DUP) Prepared: 07/10/20 Analyzed: 07/17/20 | | | | | | | | | | |
| Radium-226 | 39.6 | | pCi/L dry | | | | | 29 | 0.32 | |
| Uncertainty: 3.01 | | MDA: 0.437 | | | | | | | | |
| MS (30370941001MS) Source: 30370941001 Prepared: 07/10/20 Analyzed: 07/17/20 | | | | | | | | | | |
| Radium-226 | 10.1 | | pCi/L dry | 9.56 | 0.341 | 102 | 0.71-1.36 | | | |
| Uncertainty: 1.5 | | MDA: 0.879 | | | | | | | | |
| LCS (LCS54959) Prepared: 07/10/20 Analyzed: 07/17/20 | | | | | | | | | | |
| Radium-226 | 3.99 | | pCi/L dry | 4.77 | | 84 | 0.73-1.35 | | | |
| Uncertainty: 0.892 | | MDA: 0.609 | | | | | | | | |

Quality Control Results


EPA 904.0

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|---|--------|------------|-----------|-------------|---------------|------|--------|-----|-------|-----------|
| Batch: 404025 - EPA 904.0 | | | | | | | | | | |
| DUP (30370902001DUP) Prepared: 07/10/20 Analyzed: 07/16/20 | | | | | | | | | | |
| Radium-228 | 35.2 | | pCi/L dry | | | | | 9 | 36 | |
| Uncertainty: 1.84 | | MDA: 0.996 | | | | | | | | |
| MS (30370958001MS) Source: 30370958001 Prepared: 07/10/20 Analyzed: 07/16/20 | | | | | | | | | | |
| Radium-228 | 9.37 | | pCi/L dry | 9.7 | 0.0757 | 96 | 60-135 | | | |
| Uncertainty: 0.888 | | MDA: 0.815 | | | | | | | | |
| LCS (LCS54958) Prepared: 07/10/20 Analyzed: 07/16/20 | | | | | | | | | | |
| Radium-228 | 5.39 | | pCi/L dry | 4.87 | | 111 | 60-135 | | | |
| Uncertainty: 0.744 | | MDA: 0.907 | | | | | | | | |

Quality Control Results

EPA 905.0

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|---|--------|------------|-----------|-------------|---------------|------|--------|-----|-------|-----------|
| Batch: 405208 - EPA 905.0 | | | | | | | | | | |
| MS (30371686001MS) Source: 30371686001 Prepared: 07/15/20 Analyzed: 07/20/20 | | | | | | | | | | |
| Strontium-90 | 71.5 | | pCi/L dry | 12.7 | 61 | 83 | 65-130 | | | |
| Uncertainty: 0.93 | | MDA: 0.222 | | | | | | | | |
| MS (30372512001MS) Source: 30372512001 Prepared: 07/15/20 Analyzed: 07/21/20 | | | | | | | | | | |
| Strontium-90 | 20.2 | | pCi/L dry | 25.9 | -0.084 | 78 | 65-130 | | | |
| Uncertainty: 1.66 | | MDA: 1.06 | | | | | | | | |
| LCS (LCS55071) Prepared: 07/15/20 Analyzed: 07/21/20 | | | | | | | | | | |
| Strontium-90 | 4.93 | | pCi/L dry | 6.45 | | 77 | 65-130 | | | |
| Uncertainty: 0.578 | | MDA: 0.463 | | | | | | | | |
| LCS Dup (LCS55071) Prepared: 07/15/20 Analyzed: 07/21/20 | | | | | | | | | | |
| Strontium-90 | 4.91 | | pCi/L dry | 6.48 | | 76 | 65-130 | 1 | 25 | |
| Uncertainty: 0.588 | | MDA: 0.509 | | | | | | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

EPA 906.0


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|----------|-----|-----------|-------------|---------------|------|--------|-----|-----------|-----------|
| Batch: 404450 - EPA 906.0 | | | | | | | | | | |
| MS (30370818001MS) Source: 30370818001 Prepared: 07/10/20 Analyzed: 07/11/20 | | | | | | | | | | |
| Tritium | 3570 | | pCi/L dry | 3610 | -39.6 | 100 | 75-125 | | | |
| Uncertainty: 273 | MDA: 233 | | | | | | | | | |
| MS (30370824001MS) Source: 30370824001 Prepared: 07/10/20 Analyzed: 07/11/20 | | | | | | | | | | |
| Tritium | 3500 | | pCi/L dry | 4030 | 59.9 | 86 | 75-125 | | | |
| Uncertainty: 270 | MDA: 232 | | | | | | | | | |
| LCS (LCS55010) Prepared: 07/10/20 Analyzed: 07/11/20 | | | | | | | | | | |
| Tritium | 1710 | | pCi/L dry | 2020 | | 85 | 75-125 | | | |
| Uncertainty: 211 | MDA: 231 | | | | | | | | | |
| LCS Dup (LCS55010) Prepared: 07/10/20 Analyzed: 07/11/20 | | | | | | | | | | |
| Tritium | 1860 | | pCi/L dry | 2010 | | 93 | 75-125 | 9 | 25 | |
| Uncertainty: 217 | MDA: 232 | | | | | | | | | |

Quality Control Results

(Continued)

1,4-Dioxane by SPE/GCMS SIM, EPA Method 522

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-------|-------|-------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0F1841 - EPA 522 | | | | | | | | | | |
| Blank (W0F1841-BLK1) Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | | | | | |
| 1,4-Dioxane | ND | 0.070 | ug/l | | | | | | | |
| Surrogate(s) | | | | | | | | | | |
| 1,4-Dioxane-d8 | 8.71 | | ug/l | 10.0 | | 87 | 70-130 | | | |
| LCS (W0F1841-BS1) Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | | | | | |
| 1,4-Dioxane | 0.0690 | 0.070 | ug/l | 0.0600 | | 115 | 50-150 | | | |
| Surrogate(s) | | | | | | | | | | |
| 1,4-Dioxane-d8 | 10.3 | | ug/l | 10.0 | | 103 | 70-130 | | | |
| LCS Dup (W0F1841-BSD1) Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | | | | | |
| 1,4-Dioxane | 0.0646 | 0.070 | ug/l | 0.0600 | | 108 | 50-150 | 7 | 30 | |
| Surrogate(s) | | | | | | | | | | |
| 1,4-Dioxane-d8 | 9.66 | | ug/l | 10.0 | | 97 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Acrylamide low levels by EPA Method 8316


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|---------------------------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0592 - EPA 8316 | | | | | | | | | | |
| Blank (W0G0592-BLK1) | | | | Prepared & Analyzed: 07/13/20 | | | | | | |
| Acrylamide | ND | 0.10 | ug/l | | | | | | | |
| LCS (W0G0592-BS1) | | | | Prepared & Analyzed: 07/13/20 | | | | | | |
| Acrylamide | 1.06 | 0.10 | ug/l | 1.00 | | 106 | 80-120 | | | |
| Matrix Spike (W0G0592-MS1) | | | | Prepared & Analyzed: 07/13/20 | | | | | | |
| | | Source: 0F30024-01 | | | | | | | | |
| Acrylamide | 0.925 | 0.10 | ug/l | 1.00 | ND | 92 | 80-120 | | | |
| Matrix Spike Dup (W0G0592-MSD1) | | | | Prepared & Analyzed: 07/13/20 | | | | | | |
| | | Source: 0F30024-01 | | | | | | | | |
| Acrylamide | 1.13 | 0.10 | ug/l | 1.00 | ND | 113 | 80-120 | 20 | 20 | |

Quality Control Results

(Continued)

Aldehydes and Carbonyl Compounds by GC/ECD

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---------------------------------|--------|-----|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0132 - EPA 556 | | | | | | | | | | |
| Blank (W0G0132-BLK1) | | | | Prepared: 07/06/20 Analyzed: 07/10/20 | | | | | | |
| Formaldehyde | ND | 2.0 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4,5-TFAP | 20.3 | | ug/l | 20.0 | | 101 | 70-130 | | | |
| LCS (W0G0132-BS1) | | | | Prepared: 07/06/20 Analyzed: 07/10/20 | | | | | | |
| Formaldehyde | 19.8 | 2.0 | ug/l | 20.0 | | 99 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4,5-TFAP | 20.1 | | ug/l | 20.0 | | 100 | 70-130 | | | |
| LCS Dup (W0G0132-BSD1) | | | | Prepared: 07/06/20 Analyzed: 07/10/20 | | | | | | |
| Formaldehyde | 19.6 | 2.0 | ug/l | 20.0 | | 98 | 70-130 | 0.7 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4,5-TFAP | 20.6 | | ug/l | 20.0 | | 103 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Anions by IC, EPA Method 300.0

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|---------------------------|-------|--|---------------|------|--------|-------|-----------|-----------|
| Batch: W0G0250 - EPA 300.0 | | | | | | | | | | |
| Blank (W0G0250-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/07/20 Analyzed: 07/10/20 | | | | | | |
| Chloride, Total | ND | 0.50 | mg/l | | | | | | | |
| Fluoride, Total | ND | 0.10 | mg/l | | | | | | | |
| Sulfate as SO4 | ND | 0.50 | mg/l | | | | | | | |
| LCS (W0G0250-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/07/20 Analyzed: 07/10/20 | | | | | | |
| Chloride, Total | 5.21 | 0.50 | mg/l | 5.00 | | 104 | 90-110 | | | |
| Fluoride, Total | 0.962 | 0.10 | mg/l | 1.00 | | 96 | 90-110 | | | |
| Sulfate as SO4 | 5.07 | 0.50 | mg/l | 5.00 | | 101 | 90-110 | | | |
| Matrix Spike (W0G0250-MS1) | | | | | | | | | | |
| | | Source: 0F30027-04 | | Prepared: 07/07/20 Analyzed: 07/10/20 | | | | | | |
| Chloride, Total | 146 | 5.0 | mg/l | 50.0 | 90.2 | 112 | 76-118 | | | |
| Fluoride, Total | 11.0 | 1.0 | mg/l | 10.0 | 0.809 | 102 | 86-107 | | | |
| Sulfate as SO4 | 239 | 5.0 | mg/l | 50.0 | 173 | 132 | 78-111 | | | MS-01 |
| Matrix Spike (W0G0250-MS2) | | | | | | | | | | |
| | | Source: 0G01049-02 | | Prepared: 07/07/20 Analyzed: 07/10/20 | | | | | | |
| Chloride, Total | 9.91 | 0.50 | mg/l | 5.00 | 2.43 | 150 | 76-118 | | | MS-01 |
| Fluoride, Total | 1.20 | 0.10 | mg/l | 1.00 | 0.153 | 105 | 86-107 | | | |
| Sulfate as SO4 | 39.2 | 0.50 | mg/l | 5.00 | 19.5 | 396 | 78-111 | | | MS-01 |
| Matrix Spike Dup (W0G0250-MSD1) | | | | | | | | | | |
| | | Source: 0F30027-04 | | Prepared: 07/07/20 Analyzed: 07/10/20 | | | | | | |
| Chloride, Total | 145 | 5.0 | mg/l | 50.0 | 90.2 | 109 | 76-118 | 1 | 20 | |
| Fluoride, Total | 10.4 | 1.0 | mg/l | 10.0 | 0.809 | 96 | 86-107 | 6 | 20 | |
| Sulfate as SO4 | 228 | 5.0 | mg/l | 50.0 | 173 | 109 | 78-111 | 5 | 20 | |
| Matrix Spike Dup (W0G0250-MSD2) | | | | | | | | | | |
| | | Source: 0G01049-02 | | Prepared: 07/07/20 Analyzed: 07/10/20 | | | | | | |
| Chloride, Total | 9.92 | 0.50 | mg/l | 5.00 | 2.43 | 150 | 76-118 | 0.007 | 20 | MS-01 |
| Fluoride, Total | 1.11 | 0.10 | mg/l | 1.00 | 0.153 | 96 | 86-107 | 8 | 20 | |
| Sulfate as SO4 | 36.2 | 0.50 | mg/l | 5.00 | 19.5 | 334 | 78-111 | 8 | 20 | MS-01 |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Anions by IC, EPA Method 300.1

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|--|---------------|------|--|-----|-----------|-----------|
| Batch: W0G0041 - EPA 300.1 | | | | | | | | | | |
| Blank (W0G0041-BLK1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| Bromate | ND | 5.0 | ug/l | | | | | | | |
| Chlorate | ND | 10 | ug/l | | | | | | | |
| Chlorite | ND | 10 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Dichloroacetate | 552 | | ug/l | 500 | | 110 | 90-115 | | | |
| Dichloroacetate | 552 | | ug/l | 500 | | 110 | 90-115 | | | |
| Dichloroacetate | 552 | | ug/l | 500 | | 110 | 90-115 | | | |
| LCS (W0G0041-BS1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| Bromate | 101 | 5.0 | ug/l | 100 | | 101 | 85-115 | | | |
| Chlorate | 106 | 10 | ug/l | 100 | | 106 | 85-115 | | | |
| Chlorite | 85.4 | 10 | ug/l | 100 | | 85 | 85-115 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Dichloroacetate | 550 | | ug/l | 500 | | 110 | 90-115 | | | |
| Dichloroacetate | 550 | | ug/l | 500 | | 110 | 90-115 | | | |
| Dichloroacetate | 550 | | ug/l | 500 | | 110 | 90-115 | | | |
| Matrix Spike (W0G0041-MS1) | | | | Source: 0F08086-04 | | | Prepared & Analyzed: 07/01/20 | | | |
| Bromate | 76.3 | 5.0 | ug/l | 100 | ND | 76 | 64-133 | | | |
| Chlorate | 176 | 10 | ug/l | 100 | 443 | NR | 76-120 | | | MS-01 |
| Chlorite | 95.9 | 10 | ug/l | 100 | ND | 96 | 78-129 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Dichloroacetate | 519 | | ug/l | 500 | | 104 | 90-115 | | | |
| Dichloroacetate | 519 | | ug/l | 500 | | 104 | 90-115 | | | |
| Dichloroacetate | 519 | | ug/l | 500 | | 104 | 90-115 | | | |
| Matrix Spike (W0G0041-MS2) | | | | Source: 0F08072-14 | | | Prepared & Analyzed: 07/01/20 | | | |
| Bromate | 74.5 | 5.0 | ug/l | 100 | ND | 74 | 64-133 | | | |
| Chlorate | 493 | 10 | ug/l | 100 | 101 | 392 | 76-120 | | | MS-01 |
| Chlorite | 71.9 | 10 | ug/l | 100 | ND | 72 | 78-129 | | | MS-01 |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Dichloroacetate | 516 | | ug/l | 500 | | 103 | 90-115 | | | |
| Dichloroacetate | 516 | | ug/l | 500 | | 103 | 90-115 | | | |
| Dichloroacetate | 516 | | ug/l | 500 | | 103 | 90-115 | | | |
| Matrix Spike Dup (W0G0041-MSD1) | | | | Source: 0F08086-04 | | | Prepared & Analyzed: 07/01/20 | | | |
| Bromate | 74.0 | 5.0 | ug/l | 100 | ND | 74 | 64-133 | 3 | 20 | |
| Chlorate | 182 | 10 | ug/l | 100 | 443 | NR | 76-120 | 3 | 20 | MS-01 |
| Chlorite | 86.5 | 10 | ug/l | 100 | ND | 87 | 78-129 | 10 | 20 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Dichloroacetate | 499 | | ug/l | 500 | | 100 | 90-115 | | | |
| Dichloroacetate | 499 | | ug/l | 500 | | 100 | 90-115 | | | |
| Dichloroacetate | 499 | | ug/l | 500 | | 100 | 90-115 | | | |
| Matrix Spike Dup (W0G0041-MSD2) | | | | Source: 0F08072-14 | | | Prepared: 07/01/20 Analyzed: 07/02/20 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Project Manager: Frank Almaguer

Certificate of Analysis

FINAL REPORT

Reported:


08/21/2020 15:59

Quality Control Results

(Continued)

Anions by IC, EPA Method 300.1 (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-----|---------------------------|-------------|---------------|--|--------|-----|-----------|-----------|
| Batch: W0G0041 - EPA 300.1 (Continued) | | | | | | | | | | |
| Matrix Spike Dup (W0G0041-MSD2) | | | Source: 0F08072-14 | | | Prepared: 07/01/20 Analyzed: 07/02/20 | | | | |
| Bromate | 69.4 | 5.0 | ug/l | 100 | ND | 69 | 64-133 | 7 | 20 | |
| Chlorate | 473 | 10 | ug/l | 100 | 101 | 372 | 76-120 | 4 | 20 | MS-01 |
| Chlorite | 73.8 | 10 | ug/l | 100 | ND | 74 | 78-129 | 3 | 20 | MS-01 |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Dichloroacetate | 496 | | ug/l | 500 | | 99 | 90-115 | | | |
| Dichloroacetate | 496 | | ug/l | 500 | | 99 | 90-115 | | | |
| Dichloroacetate | 496 | | ug/l | 500 | | 99 | 90-115 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Carbamates and Urea Pesticides

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|--|---------------|------|--|-----|-----------|-----------|
| Batch: W0G0155 - EPA 531.2 | | | | | | | | | | |
| Blank (W0G0155-BLK1) | | | | Prepared & Analyzed: 07/06/20 | | | | | | |
| 3-Hydroxycarbofuran | ND | 2.0 | ug/l | | | | | | | |
| Aldicarb | ND | 2.0 | ug/l | | | | | | | |
| Aldicarb sulfone | ND | 2.0 | ug/l | | | | | | | |
| Aldicarb sulfoxide | ND | 2.0 | ug/l | | | | | | | |
| Carbaryl | ND | 2.0 | ug/l | | | | | | | |
| Carbofuran | ND | 2.0 | ug/l | | | | | | | |
| Methiocarb | ND | 2.0 | ug/l | | | | | | | |
| Methomyl | ND | 2.0 | ug/l | | | | | | | |
| Oxamyl | ND | 2.0 | ug/l | | | | | | | |
| Propoxur (Baygon) | ND | 2.0 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| BDMC | 12.8 | | ug/l | 10.0 | | 128 | 70-130 | | | |
| LCS (W0G0155-BS1) | | | | Prepared & Analyzed: 07/06/20 | | | | | | |
| 3-Hydroxycarbofuran | 8.57 | 2.0 | ug/l | 10.0 | | 86 | 70-130 | | | |
| Aldicarb | 9.63 | 2.0 | ug/l | 10.0 | | 96 | 70-130 | | | |
| Aldicarb sulfone | 9.24 | 2.0 | ug/l | 10.0 | | 92 | 70-130 | | | |
| Aldicarb sulfoxide | 10.2 | 2.0 | ug/l | 10.0 | | 102 | 70-130 | | | |
| Carbaryl | 10.3 | 2.0 | ug/l | 10.0 | | 103 | 70-130 | | | |
| Carbofuran | 9.83 | 2.0 | ug/l | 10.0 | | 98 | 70-130 | | | |
| Methiocarb | 9.48 | 2.0 | ug/l | 10.0 | | 95 | 70-130 | | | |
| Methomyl | 9.50 | 2.0 | ug/l | 10.0 | | 95 | 70-130 | | | |
| Oxamyl | 9.72 | 2.0 | ug/l | 10.0 | | 97 | 70-130 | | | |
| Propoxur (Baygon) | 9.98 | 2.0 | ug/l | 10.0 | | 100 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| BDMC | 12.3 | | ug/l | 10.0 | | 123 | 70-130 | | | |
| Matrix Spike (W0G0155-MS1) | | | | Source: 0F26060-01 | | | Prepared & Analyzed: 07/06/20 | | | |
| 3-Hydroxycarbofuran | 9.15 | 2.0 | ug/l | 10.0 | ND | 92 | 70-130 | | | |
| Aldicarb | 10.2 | 2.0 | ug/l | 10.0 | ND | 102 | 70-130 | | | |
| Aldicarb sulfone | 9.98 | 2.0 | ug/l | 10.0 | ND | 100 | 70-130 | | | |
| Aldicarb sulfoxide | 10.1 | 2.0 | ug/l | 10.0 | ND | 101 | 70-130 | | | |
| Carbaryl | 10.2 | 2.0 | ug/l | 10.0 | ND | 102 | 70-130 | | | |
| Carbofuran | 10.4 | 2.0 | ug/l | 10.0 | ND | 104 | 70-130 | | | |
| Methiocarb | 9.22 | 2.0 | ug/l | 10.0 | ND | 92 | 70-130 | | | |
| Methomyl | 10.3 | 2.0 | ug/l | 10.0 | ND | 103 | 70-130 | | | |
| Oxamyl | 10.1 | 2.0 | ug/l | 10.0 | ND | 101 | 70-130 | | | |
| Propoxur (Baygon) | 9.87 | 2.0 | ug/l | 10.0 | ND | 99 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| BDMC | 12.4 | | ug/l | 10.0 | | 124 | 70-130 | | | |
| Matrix Spike Dup (W0G0155-MSD1) | | | | Source: 0F26060-01 | | | Prepared & Analyzed: 07/06/20 | | | |
| 3-Hydroxycarbofuran | 9.71 | 2.0 | ug/l | 10.0 | ND | 97 | 70-130 | 6 | 30 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Project Manager: Frank Almaguer

Certificate of Analysis

FINAL REPORT

Reported:


08/21/2020 15:59

Quality Control Results

(Continued)

Carbamates and Urea Pesticides (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-----|---------------------------|-------------|---------------|--|--------|-----|-----------|-----------|
| Batch: W0G0155 - EPA 531.2 (Continued) | | | | | | | | | | |
| Matrix Spike Dup (W0G0155-MSD1) | | | Source: 0F26060-01 | | | Prepared & Analyzed: 07/06/20 | | | | |
| Aldicarb | 10.3 | 2.0 | ug/l | 10.0 | ND | 103 | 70-130 | 0.7 | 30 | |
| Aldicarb sulfone | 10.8 | 2.0 | ug/l | 10.0 | ND | 108 | 70-130 | 8 | 30 | |
| Aldicarb sulfoxide | 10.5 | 2.0 | ug/l | 10.0 | ND | 105 | 70-130 | 3 | 30 | |
| Carbaryl | 10.6 | 2.0 | ug/l | 10.0 | ND | 106 | 70-130 | 4 | 30 | |
| Carbofuran | 10.5 | 2.0 | ug/l | 10.0 | ND | 105 | 70-130 | 0.3 | 30 | |
| Methiocarb | 10.5 | 2.0 | ug/l | 10.0 | ND | 105 | 70-130 | 13 | 30 | |
| Methomyl | 10.5 | 2.0 | ug/l | 10.0 | ND | 105 | 70-130 | 2 | 30 | |
| Oxamyl | 9.74 | 2.0 | ug/l | 10.0 | ND | 97 | 70-130 | 4 | 30 | |
| Propoxur (Baygon) | 9.86 | 2.0 | ug/l | 10.0 | ND | 99 | 70-130 | 0.2 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| BDMC | 12.3 | | ug/l | 10.0 | | 123 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Chlorinated Acids Herbicides by GC/ECD

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|------|-------|-------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0176 - EPA 515.4 | | | | | | | | | | |
| Blank (W0G0176-BLK1) | | | | | | | | | | |
| Prepared: 07/07/20 Analyzed: 07/13/20 | | | | | | | | | | |
| 2,4,5-T | ND | 0.20 | ug/l | | | | | | | |
| 2,4,5-TP (Silvex) | ND | 0.20 | ug/l | | | | | | | |
| 2,4-D | ND | 0.40 | ug/l | | | | | | | |
| 2,4-DB | ND | 2.0 | ug/l | | | | | | | |
| 3,5-Dichlorobenzoic acid | ND | 1.0 | ug/l | | | | | | | |
| Acifluorfen | ND | 0.40 | ug/l | | | | | | | |
| Bentazon | ND | 2.0 | ug/l | | | | | | | |
| Dalapon | ND | 0.40 | ug/l | | | | | | | |
| DCPA | ND | 0.10 | ug/l | | | | | | | |
| Dicamba | ND | 0.60 | ug/l | | | | | | | |
| Dichloroprop | ND | 0.30 | ug/l | | | | | | | |
| Dinoseb | ND | 0.40 | ug/l | | | | | | | |
| Pentachlorophenol | ND | 0.20 | ug/l | | | | | | | |
| Picloram | ND | 0.60 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4-DCAA | 9.49 | | ug/l | 10.0 | | 95 | 70-130 | | | |
| LCS (W0G0176-BS1) | | | | | | | | | | |
| Prepared: 07/07/20 Analyzed: 07/13/20 | | | | | | | | | | |
| 2,4,5-T | 3.67 | 0.20 | ug/l | 4.00 | | 92 | 70-130 | | | |
| 2,4,5-TP (Silvex) | 3.79 | 0.20 | ug/l | 4.00 | | 95 | 70-130 | | | |
| 2,4-D | 7.41 | 0.40 | ug/l | 8.00 | | 93 | 70-130 | | | |
| 2,4-DB | 16.1 | 2.0 | ug/l | 16.0 | | 100 | 70-130 | | | |
| 3,5-Dichlorobenzoic acid | 8.20 | 1.0 | ug/l | 8.00 | | 102 | 70-130 | | | |
| Acifluorfen | 4.09 | 0.40 | ug/l | 4.00 | | 102 | 70-130 | | | |
| Bentazon | 15.1 | 2.0 | ug/l | 16.0 | | 94 | 70-130 | | | |
| Dalapon | 9.11 | 0.40 | ug/l | 8.00 | | 114 | 70-130 | | | |
| DCPA | 4.04 | 0.10 | ug/l | 4.00 | | 101 | 70-130 | | | |
| Dicamba | 7.32 | 0.60 | ug/l | 8.00 | | 92 | 70-130 | | | |
| Dichloroprop | 7.86 | 0.30 | ug/l | 8.00 | | 98 | 70-130 | | | |
| Dinoseb | 3.79 | 0.40 | ug/l | 4.00 | | 95 | 70-130 | | | |
| Pentachlorophenol | 4.05 | 0.20 | ug/l | 4.00 | | 101 | 70-130 | | | |
| Picloram | 4.13 | 0.60 | ug/l | 4.00 | | 103 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4-DCAA | 10.1 | | ug/l | 10.0 | | 101 | 70-130 | | | |
| Matrix Spike (W0G0176-MS1) | | | | | | | | | | |
| Source: 0F26060-01 Prepared: 07/07/20 Analyzed: 07/13/20 | | | | | | | | | | |
| 2,4,5-T | 3.69 | 0.20 | ug/l | 4.00 | ND | 92 | 70-130 | | | |
| 2,4,5-TP (Silvex) | 3.78 | 0.20 | ug/l | 4.00 | ND | 94 | 70-130 | | | |
| 2,4-D | 7.42 | 0.40 | ug/l | 8.00 | ND | 93 | 70-130 | | | |
| 2,4-DB | 15.9 | 2.0 | ug/l | 16.0 | ND | 99 | 70-130 | | | |
| 3,5-Dichlorobenzoic acid | 8.34 | 1.0 | ug/l | 8.00 | ND | 104 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Chlorinated Acids Herbicides by GC/ECD (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|------|---------------------------|-------------|---------------|--|--------|-----|-----------|-----------|
| Batch: W0G0176 - EPA 515.4 (Continued) | | | | | | | | | | |
| Matrix Spike (W0G0176-MS1) | | | Source: 0F26060-01 | | | Prepared: 07/07/20 Analyzed: 07/13/20 | | | | |
| Acifluorfen | 4.06 | 0.40 | ug/l | 4.00 | ND | 101 | 70-130 | | | |
| Bentazon | 14.7 | 2.0 | ug/l | 16.0 | ND | 92 | 70-130 | | | |
| Dalapon | 8.94 | 0.40 | ug/l | 8.00 | ND | 112 | 70-130 | | | |
| DCPA | 4.01 | 0.10 | ug/l | 4.00 | ND | 100 | 70-130 | | | |
| Dicamba | 7.36 | 0.60 | ug/l | 8.00 | ND | 92 | 70-130 | | | |
| Dichloroprop | 7.84 | 0.30 | ug/l | 8.00 | ND | 98 | 70-130 | | | |
| Dinoseb | 3.77 | 0.40 | ug/l | 4.00 | ND | 94 | 70-130 | | | |
| Pentachlorophenol | 4.05 | 0.20 | ug/l | 4.00 | ND | 101 | 70-130 | | | |
| Picloram | 4.16 | 0.60 | ug/l | 4.00 | ND | 104 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4-DCAA | 10.3 | | ug/l | 10.0 | | 103 | 70-130 | | | |
| Matrix Spike Dup (W0G0176-MSD1) | | | Source: 0F26060-01 | | | Prepared: 07/07/20 Analyzed: 07/13/20 | | | | |
| 2,4,5-T | 3.85 | 0.20 | ug/l | 4.00 | ND | 96 | 70-130 | 4 | 30 | |
| 2,4,5-TP (Silvex) | 3.77 | 0.20 | ug/l | 4.00 | ND | 94 | 70-130 | 0.3 | 30 | |
| 2,4-D | 7.46 | 0.40 | ug/l | 8.00 | ND | 93 | 70-130 | 0.6 | 30 | |
| 2,4-DB | 16.0 | 2.0 | ug/l | 16.0 | ND | 100 | 70-130 | 0.7 | 30 | |
| 3,5-Dichlorobenzoic acid | 8.64 | 1.0 | ug/l | 8.00 | ND | 108 | 70-130 | 3 | 30 | |
| Acifluorfen | 4.22 | 0.40 | ug/l | 4.00 | ND | 106 | 70-130 | 4 | 30 | |
| Bentazon | 14.4 | 2.0 | ug/l | 16.0 | ND | 90 | 70-130 | 2 | 30 | |
| Dalapon | 8.80 | 0.40 | ug/l | 8.00 | ND | 110 | 70-130 | 2 | 30 | |
| DCPA | 4.04 | 0.10 | ug/l | 4.00 | ND | 101 | 70-130 | 0.6 | 30 | |
| Dicamba | 7.29 | 0.60 | ug/l | 8.00 | ND | 91 | 70-130 | 1 | 30 | |
| Dichloroprop | 7.80 | 0.30 | ug/l | 8.00 | ND | 97 | 70-130 | 0.6 | 30 | |
| Dinoseb | 3.77 | 0.40 | ug/l | 4.00 | ND | 94 | 70-130 | 0.2 | 30 | |
| Pentachlorophenol | 4.02 | 0.20 | ug/l | 4.00 | ND | 100 | 70-130 | 0.7 | 30 | |
| Picloram | 4.23 | 0.60 | ug/l | 4.00 | ND | 106 | 70-130 | 2 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2,4-DCAA | 10.0 | | ug/l | 10.0 | | 100 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Chlorinated Pesticides and/or PCBs by GC/ECD

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---------------------------------|--------|-------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0230 - EPA 508 | | | | | | | | | | |
| Blank (W0G0230-BLK1) | | | | Prepared: 07/07/20 Analyzed: 07/18/20 | | | | | | |
| 4,4'-DDD | ND | 0.010 | ug/l | | | | | | | |
| 4,4'-DDE | ND | 0.010 | ug/l | | | | | | | |
| 4,4'-DDT | ND | 0.010 | ug/l | | | | | | | |
| Aldrin | ND | 0.010 | ug/l | | | | | | | |
| alpha-BHC | ND | 0.010 | ug/l | | | | | | | |
| Aroclor 1016 | ND | 0.10 | ug/l | | | | | | | |
| Aroclor 1221 | ND | 0.10 | ug/l | | | | | | | |
| Aroclor 1232 | ND | 0.10 | ug/l | | | | | | | |
| Aroclor 1242 | ND | 0.10 | ug/l | | | | | | | |
| Aroclor 1248 | ND | 0.10 | ug/l | | | | | | | |
| Aroclor 1254 | ND | 0.10 | ug/l | | | | | | | |
| Aroclor 1260 | ND | 0.10 | ug/l | | | | | | | |
| beta-BHC | ND | 0.010 | ug/l | | | | | | | |
| Chlordane (tech) | ND | 0.10 | ug/l | | | | | | | |
| Chlorothalonil | ND | 0.050 | ug/l | | | | | | | |
| delta-BHC | ND | 0.010 | ug/l | | | | | | | |
| Dieldrin | ND | 0.010 | ug/l | | | | | | | |
| Endosulfan I | ND | 0.010 | ug/l | | | | | | | |
| Endosulfan II | ND | 0.010 | ug/l | | | | | | | |
| Endosulfan sulfate | ND | 0.010 | ug/l | | | | | | | |
| Endrin | ND | 0.010 | ug/l | | | | | | | |
| Endrin aldehyde | ND | 0.010 | ug/l | | | | | | | |
| gamma-BHC (Lindane) | ND | 0.010 | ug/l | | | | | | | |
| Heptachlor | ND | 0.010 | ug/l | | | | | | | |
| Heptachlor epoxide | ND | 0.010 | ug/l | | | | | | | |
| Hexachlorobenzene | ND | 0.050 | ug/l | | | | | | | |
| Hexachlorocyclopentadiene | ND | 0.050 | ug/l | | | | | | | |
| Methoxychlor | ND | 0.010 | ug/l | | | | | | | |
| PCBs, Total | ND | 0.50 | ug/l | | | | | | | |
| Propachlor | ND | 0.050 | ug/l | | | | | | | |
| Toxaphene | ND | 1.0 | ug/l | | | | | | | |
| Trifluralin | ND | 0.010 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Decachlorobiphenyl | 0.102 | | ug/l | 0.100 | | 102 | 70-130 | | | |
| Tetrachloro-meta-xylene | 0.0880 | | ug/l | 0.100 | | 88 | 70-130 | | | |
| Blank (W0G0230-BLK2) | | | | Prepared: 07/07/20 Analyzed: 07/21/20 | | | | | | |
| 4,4'-DDD | ND | 0.010 | ug/l | | | | | | | QC-2 |
| 4,4'-DDE | ND | 0.010 | ug/l | | | | | | | QC-2 |
| 4,4'-DDT | ND | 0.010 | ug/l | | | | | | | QC-2 |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Chlorinated Pesticides and/or PCBs by GC/ECD (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0230 - EPA 508 (Continued) | | | | | | | | | | |
| Blank (W0G0230-BLK2) | | | | Prepared: 07/07/20 Analyzed: 07/21/20 | | | | | | |
| Aldrin | ND | 0.010 | ug/l | | | | | | | QC-2 |
| alpha-BHC | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Aroclor 1016 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Aroclor 1221 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Aroclor 1232 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Aroclor 1242 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Aroclor 1248 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Aroclor 1254 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Aroclor 1260 | ND | 0.10 | ug/l | | | | | | | QC-2 |
| beta-BHC | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Chlordane (tech) | ND | 0.10 | ug/l | | | | | | | QC-2 |
| Chlorothalonil | ND | 0.050 | ug/l | | | | | | | QC-2 |
| delta-BHC | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Dieldrin | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Endosulfan I | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Endosulfan II | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Endosulfan sulfate | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Endrin | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Endrin aldehyde | ND | 0.010 | ug/l | | | | | | | QC-2 |
| gamma-BHC (Lindane) | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Heptachlor | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Heptachlor epoxide | ND | 0.010 | ug/l | | | | | | | QC-2 |
| Hexachlorobenzene | ND | 0.050 | ug/l | | | | | | | QC-2 |
| Hexachlorocyclopentadiene | ND | 0.050 | ug/l | | | | | | | QC-2 |
| Methoxychlor | ND | 0.010 | ug/l | | | | | | | QC-2 |
| PCBs, Total | ND | 0.50 | ug/l | | | | | | | QC-2 |
| Propachlor | ND | 0.050 | ug/l | | | | | | | QC-2 |
| Toxaphene | ND | 1.0 | ug/l | | | | | | | QC-2 |
| Trifluralin | ND | 0.010 | ug/l | | | | | | | QC-2 |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Decachlorobiphenyl | 0.109 | | ug/l | 0.100 | | 109 | 70-130 | | | QC-2 |
| Tetrachloro-meta-xylene | 0.0872 | | ug/l | 0.100 | | 87 | 70-130 | | | QC-2 |
| LCS (W0G0230-BS1) | | | | Prepared: 07/07/20 Analyzed: 07/18/20 | | | | | | |
| 4,4'-DDD | 0.0828 | 0.010 | ug/l | 0.100 | | 83 | 77-137 | | | |
| 4,4'-DDE | 0.0851 | 0.010 | ug/l | 0.100 | | 85 | 69-129 | | | |
| 4,4'-DDT | 0.0913 | 0.010 | ug/l | 0.100 | | 91 | 82-142 | | | |
| Aldrin | 0.0820 | 0.010 | ug/l | 0.100 | | 82 | 56-116 | | | |
| alpha-BHC | 0.0823 | 0.010 | ug/l | 0.100 | | 82 | 62-122 | | | |
| beta-BHC | 0.0892 | 0.010 | ug/l | 0.100 | | 89 | 65-125 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Chlorinated Pesticides and/or PCBs by GC/ECD (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC Limits | RPD | RPD Limit | Qualifier |
|---|--------|-------|-------|-------------|--|-------------|-----|-----------|-----------|
| Batch: W0G0230 - EPA 508 (Continued) | | | | | | | | | |
| LCS (W0G0230-BS1) | | | | | Prepared: 07/07/20 Analyzed: 07/18/20 | | | | |
| delta-BHC | 0.0937 | 0.010 | ug/l | 0.100 | | 94 72-132 | | | |
| Dieldrin | 0.0803 | 0.010 | ug/l | 0.100 | | 80 57-117 | | | |
| Endosulfan I | 0.0718 | 0.010 | ug/l | 0.100 | | 72 57-117 | | | |
| Endosulfan II | 0.0781 | 0.010 | ug/l | 0.100 | | 78 62-122 | | | |
| Endosulfan sulfate | 0.0869 | 0.010 | ug/l | 0.100 | | 87 72-132 | | | |
| Endrin | 0.0909 | 0.010 | ug/l | 0.100 | | 91 58-118 | | | |
| Endrin aldehyde | 0.101 | 0.010 | ug/l | 0.100 | | 101 58-118 | | | |
| gamma-BHC (Lindane) | 0.0830 | 0.010 | ug/l | 0.100 | | 83 59-119 | | | |
| Heptachlor | 0.0879 | 0.010 | ug/l | 0.100 | | 88 68-128 | | | |
| Heptachlor epoxide | 0.0845 | 0.010 | ug/l | 0.100 | | 84 57-117 | | | |
| Methoxychlor | 0.0914 | 0.010 | ug/l | 0.100 | | 91 75-135 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | |
| Decachlorobiphenyl | 0.0967 | | ug/l | 0.100 | | 97 70-130 | | | |
| Tetrachloro-meta-xylene | 0.0726 | | ug/l | 0.100 | | 73 70-130 | | | |
| LCS (W0G0230-BS2) | | | | | Prepared: 07/07/20 Analyzed: 07/21/20 | | | | |
| 4,4'-DDD | 0.0889 | 0.010 | ug/l | 0.100 | | 89 77-137 | | | QC-2 |
| 4,4'-DDE | 0.0905 | 0.010 | ug/l | 0.100 | | 90 69-129 | | | QC-2 |
| 4,4'-DDT | 0.0978 | 0.010 | ug/l | 0.100 | | 98 82-142 | | | QC-2 |
| Aldrin | 0.0875 | 0.010 | ug/l | 0.100 | | 87 56-116 | | | QC-2 |
| alpha-BHC | 0.0956 | 0.010 | ug/l | 0.100 | | 96 62-122 | | | QC-2 |
| beta-BHC | 0.0959 | 0.010 | ug/l | 0.100 | | 96 65-125 | | | QC-2 |
| delta-BHC | 0.101 | 0.010 | ug/l | 0.100 | | 101 72-132 | | | QC-2 |
| Dieldrin | 0.0854 | 0.010 | ug/l | 0.100 | | 85 57-117 | | | QC-2 |
| Endosulfan I | 0.0764 | 0.010 | ug/l | 0.100 | | 76 57-117 | | | QC-2 |
| Endosulfan II | 0.0829 | 0.010 | ug/l | 0.100 | | 83 62-122 | | | QC-2 |
| Endosulfan sulfate | 0.0832 | 0.010 | ug/l | 0.100 | | 83 72-132 | | | QC-2 |
| Endrin | 0.102 | 0.010 | ug/l | 0.100 | | 102 58-118 | | | QC-2 |
| Endrin aldehyde | 0.104 | 0.010 | ug/l | 0.100 | | 104 58-118 | | | QC-2 |
| gamma-BHC (Lindane) | 0.0956 | 0.010 | ug/l | 0.100 | | 96 59-119 | | | QC-2 |
| Heptachlor | 0.0933 | 0.010 | ug/l | 0.100 | | 93 68-128 | | | QC-2 |
| Heptachlor epoxide | 0.0896 | 0.010 | ug/l | 0.100 | | 90 57-117 | | | QC-2 |
| Methoxychlor | 0.0922 | 0.010 | ug/l | 0.100 | | 92 75-135 | | | QC-2 |
| <i>Surrogate(s)</i> | | | | | | | | | |
| Decachlorobiphenyl | 0.106 | | ug/l | 0.100 | | 106 70-130 | | | QC-2 |
| Tetrachloro-meta-xylene | 0.0763 | | ug/l | 0.100 | | 76 70-130 | | | QC-2 |
| LCS Dup (W0G0230-BSD1) | | | | | Prepared: 07/07/20 Analyzed: 07/18/20 | | | | |
| 4,4'-DDD | 0.0965 | 0.010 | ug/l | 0.100 | | 97 77-137 | 15 | 20 | |
| 4,4'-DDE | 0.0943 | 0.010 | ug/l | 0.100 | | 94 69-129 | 10 | 20 | |
| 4,4'-DDT | 0.104 | 0.010 | ug/l | 0.100 | | 104 82-142 | 13 | 20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Chlorinated Pesticides and/or PCBs by GC/ECD (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0230 - EPA 508 (Continued) | | | | | | | | | | |
| LCS Dup (W0G0230-BSD1) | | | | Prepared: 07/07/20 Analyzed: 07/18/20 | | | | | | |
| Aldrin | 0.0903 | 0.010 | ug/l | 0.100 | | 90 | 56-116 | 10 | 20 | |
| alpha-BHC | 0.0965 | 0.010 | ug/l | 0.100 | | 96 | 62-122 | 16 | 20 | |
| beta-BHC | 0.0971 | 0.010 | ug/l | 0.100 | | 97 | 65-125 | 8 | 20 | |
| delta-BHC | 0.103 | 0.010 | ug/l | 0.100 | | 103 | 72-132 | 9 | 20 | |
| Dieldrin | 0.0888 | 0.010 | ug/l | 0.100 | | 89 | 57-117 | 10 | 20 | |
| Endosulfan I | 0.0788 | 0.010 | ug/l | 0.100 | | 79 | 57-117 | 9 | 20 | |
| Endosulfan II | 0.0889 | 0.010 | ug/l | 0.100 | | 89 | 62-122 | 13 | 20 | |
| Endosulfan sulfate | 0.103 | 0.010 | ug/l | 0.100 | | 103 | 72-132 | 17 | 20 | |
| Endrin | 0.101 | 0.010 | ug/l | 0.100 | | 101 | 58-118 | 10 | 20 | |
| Endrin aldehyde | 0.123 | 0.010 | ug/l | 0.100 | | 123 | 58-118 | 20 | 20 | Q-08 |
| gamma-BHC (Lindane) | 0.0967 | 0.010 | ug/l | 0.100 | | 97 | 59-119 | 15 | 20 | |
| Heptachlor | 0.0966 | 0.010 | ug/l | 0.100 | | 97 | 68-128 | 9 | 20 | |
| Heptachlor epoxide | 0.0924 | 0.010 | ug/l | 0.100 | | 92 | 57-117 | 9 | 20 | |
| Methoxychlor | 0.111 | 0.010 | ug/l | 0.100 | | 111 | 75-135 | 19 | 20 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Decachlorobiphenyl | 0.103 | | ug/l | 0.100 | | 103 | 70-130 | | | |
| Tetrachloro-meta-xylene | 0.0741 | | ug/l | 0.100 | | 74 | 70-130 | | | |
| LCS Dup (W0G0230-BSD2) | | | | Prepared: 07/07/20 Analyzed: 07/21/20 | | | | | | |
| 4,4'-DDD | 0.0932 | 0.010 | ug/l | 0.100 | | 93 | 77-137 | 5 | 20 | QC-2 |
| 4,4'-DDE | 0.0908 | 0.010 | ug/l | 0.100 | | 91 | 69-129 | 0.3 | 20 | QC-2 |
| 4,4'-DDT | 0.0997 | 0.010 | ug/l | 0.100 | | 100 | 82-142 | 2 | 20 | QC-2 |
| Aldrin | 0.0876 | 0.010 | ug/l | 0.100 | | 88 | 56-116 | 0.1 | 20 | QC-2 |
| alpha-BHC | 0.0942 | 0.010 | ug/l | 0.100 | | 94 | 62-122 | 1 | 20 | QC-2 |
| beta-BHC | 0.0947 | 0.010 | ug/l | 0.100 | | 95 | 65-125 | 1 | 20 | QC-2 |
| delta-BHC | 0.0997 | 0.010 | ug/l | 0.100 | | 100 | 72-132 | 1 | 20 | QC-2 |
| Dieldrin | 0.0855 | 0.010 | ug/l | 0.100 | | 86 | 57-117 | 0.1 | 20 | QC-2 |
| Endosulfan I | 0.0762 | 0.010 | ug/l | 0.100 | | 76 | 57-117 | 0.2 | 20 | QC-2 |
| Endosulfan II | 0.0854 | 0.010 | ug/l | 0.100 | | 85 | 62-122 | 3 | 20 | QC-2 |
| Endosulfan sulfate | 0.0889 | 0.010 | ug/l | 0.100 | | 89 | 72-132 | 7 | 20 | QC-2 |
| Endrin | 0.102 | 0.010 | ug/l | 0.100 | | 102 | 58-118 | 0.1 | 20 | QC-2 |
| Endrin aldehyde | 0.113 | 0.010 | ug/l | 0.100 | | 113 | 58-118 | 8 | 20 | QC-2 |
| gamma-BHC (Lindane) | 0.0944 | 0.010 | ug/l | 0.100 | | 94 | 59-119 | 1 | 20 | QC-2 |
| Heptachlor | 0.0918 | 0.010 | ug/l | 0.100 | | 92 | 68-128 | 2 | 20 | QC-2 |
| Heptachlor epoxide | 0.0891 | 0.010 | ug/l | 0.100 | | 89 | 57-117 | 0.6 | 20 | QC-2 |
| Methoxychlor | 0.0990 | 0.010 | ug/l | 0.100 | | 99 | 75-135 | 7 | 20 | QC-2 |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| Decachlorobiphenyl | 0.0993 | | ug/l | 0.100 | | 99 | 70-130 | | | QC-2 |
| Tetrachloro-meta-xylene | 0.0704 | | ug/l | 0.100 | | 70 | 70-130 | | | QC-2 |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|------|--------|-------------|---------------|------|----------|-----|-----------|-----------|
| Batch: W0F1765 - SM 2540C | | | | | | | | | | |
| Blank (W0F1765-BLK1) Prepared: 06/29/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Total Dissolved Solids | ND | 10 | mg/l | | | | | | | |
| LCS (W0F1765-BS1) Prepared: 06/29/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Total Dissolved Solids | 816 | 10 | mg/l | 824 | | 99 | 96-102 | | | |
| Duplicate (W0F1765-DUP1) Source: 0F26058-01 Prepared: 06/29/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Total Dissolved Solids | 1310 | 10 | mg/l | | 1330 | | | 2 | 10 | |
| Duplicate (W0F1765-DUP2) Source: 0F29059-01 Prepared: 06/29/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Total Dissolved Solids | 34800 | 50 | mg/l | | 34000 | | | 2 | 10 | |
| Batch: W0F1828 - SM 4500H+-B | | | | | | | | | | |
| LCS (W0F1828-BS1) Prepared & Analyzed: 06/30/20 | | | | | | | | | | |
| pH | 9.09 | 0.10 | Units | 9.18 | | 99 | 98.8-101 | | | |
| Duplicate (W0F1828-DUP1) Source: 0F22022-01 Prepared & Analyzed: 06/30/20 | | | | | | | | | | |
| pH | 7.03 | 0.10 | Units | | 6.93 | | | 1 | 3.1 | |
| Batch: W0F1836 - EPA 140.1 | | | | | | | | | | |
| Blank (W0F1836-BLK1) Prepared & Analyzed: 06/30/20 | | | | | | | | | | |
| Threshold Odor Number | ND | 1.0 | T.O.N. | | | | | | | |
| Duplicate (W0F1836-DUP1) Source: 0F22012-03 Prepared & Analyzed: 06/30/20 | | | | | | | | | | |
| Threshold Odor Number | 1.0 | 1.0 | T.O.N. | | 1.0 | | | 0 | 20 | |
| Batch: W0F1837 - EPA 353.2 | | | | | | | | | | |
| Blank (W0F1837-BLK1) Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Nitrate as N | ND | 0.20 | mg/l | | | | | | | |
| Nitrite as N | ND | 100 | ug/l | | | | | | | |
| NO2+NO3 as N | ND | 200 | ug/l | | | | | | | |
| LCS (W0F1837-BS1) Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Nitrate as N | 0.996 | 0.20 | mg/l | 1.00 | | 100 | 90-110 | | | |
| Nitrite as N | 1010 | 100 | ug/l | 1000 | | 101 | 90-110 | | | |
| NO2+NO3 as N | 996 | 200 | ug/l | 1000 | | 100 | 90-110 | | | |
| Matrix Spike (W0F1837-MS1) Source: 0F22003-07 Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Nitrate as N | 6.19 | 0.20 | mg/l | 2.00 | 4.22 | 99 | 90-110 | | | |
| Nitrite as N | 1010 | 100 | ug/l | 1000 | ND | 101 | 90-110 | | | |
| NO2+NO3 as N | 6190 | 200 | ug/l | 2000 | 4220 | 98 | 90-110 | | | |
| Matrix Spike (W0F1837-MS2) Source: 0F30041-01 Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Nitrate as N | 6.77 | 0.20 | mg/l | 2.00 | 4.81 | 98 | 90-110 | | | |
| Nitrite as N | 1010 | 100 | ug/l | 1000 | ND | 101 | 90-110 | | | |
| NO2+NO3 as N | 6770 | 200 | ug/l | 2000 | 4810 | 98 | 90-110 | | | |
| Matrix Spike Dup (W0F1837-MSD1) Source: 0F22003-07 Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | | | | | |
| Nitrate as N | 6.19 | 0.20 | mg/l | 2.00 | 4.22 | 99 | 90-110 | 0 | 20 | |
| Nitrite as N | 1010 | 100 | ug/l | 1000 | ND | 101 | 90-110 | 0 | 20 | |
| NO2+NO3 as N | 6190 | 200 | ug/l | 2000 | 4220 | 98 | 90-110 | 0 | 20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|---------------------------|-------|-------------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0F1837 - EPA 353.2 (Continued) | | | | | | | | | | |
| Matrix Spike Dup (W0F1837-MSD1) | Source: 0F22003-07 | | | Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | |
| Matrix Spike Dup (W0F1837-MSD2) | Source: 0F30041-01 | | | Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | |
| Nitrate as N | 6.79 | 0.20 | mg/l | 2.00 | 4.81 | 99 | 90-110 | 0.3 | 20 | |
| Nitrite as N | 1000 | 100 | ug/l | 1000 | ND | 100 | 90-110 | 1 | 20 | |
| NO2+NO3 as N | 6790 | 200 | ug/l | 2000 | 4810 | 99 | 90-110 | 0.3 | 20 | |
| Batch: W0F1838 - SM 2120B | | | | | | | | | | |
| LCS (W0F1838-BS1) | | | | Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | |
| Color | 10.0 | 3.0 | Color Units | 10.0 | | 100 | 95-105 | | | |
| Duplicate (W0F1838-DUP1) | Source: 0F30035-08 | | | Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | |
| Color | ND | 3.0 | Color Units | | ND | | | | 10 | |
| Duplicate (W0F1838-DUP2) | Source: 0F30035-10 | | | Prepared: 06/30/20 Analyzed: 07/01/20 | | | | | | |
| Color | ND | 3.0 | Color Units | | ND | | | | 10 | |
| Batch: W0G0004 - SM 5540C | | | | | | | | | | |
| Blank (W0G0004-BLK1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| MBAS | ND | 0.050 | mg/l | | | | | | | |
| LCS (W0G0004-BS1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| MBAS | 0.191 | 0.050 | mg/l | 0.200 | | 95 | 82-115 | | | |
| Matrix Spike (W0G0004-MS1) | Source: 0F30045-01 | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| MBAS | 0.204 | 0.050 | mg/l | 0.200 | ND | 102 | 74-123 | | | |
| Matrix Spike Dup (W0G0004-MSD1) | Source: 0F30045-01 | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| MBAS | 0.200 | 0.050 | mg/l | 0.200 | ND | 100 | 74-123 | 2 | 20 | |
| Batch: W0G0009 - SM 5910B | | | | | | | | | | |
| Blank (W0G0009-BLK1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| UV 254 | ND | 0.009 | 1/cm | | | | | | | |
| LCS (W0G0009-BS1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| UV 254 | 0.088 | 0.009 | 1/cm | 0.0880 | | 100 | 90-110 | | | |
| Duplicate (W0G0009-DUP1) | Source: 0F30024-01 | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| UV 254 | ND | 0.009 | 1/cm | | ND | | | | 10 | |
| Batch: W0G0013 - SM 2320B | | | | | | | | | | |
| Blank (W0G0013-BLK1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| Alkalinity as CaCO3 | ND | 5.0 | mg/l | | | | | | | |
| Bicarbonate Alkalinity as HCO3 | ND | 6.1 | mg/l | | | | | | | |
| Carbonate Alkalinity as CaCO3 | ND | 5.0 | mg/l | | | | | | | |
| Hydroxide Alkalinity as CaCO3 | ND | 5.0 | mg/l | | | | | | | |
| LCS (W0G0013-BS1) | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| Alkalinity as CaCO3 | 252 | 5.0 | mg/l | 250 | | 101 | 94-108 | | | |
| Duplicate (W0G0013-DUP1) | Source: 0F26062-01 | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| Alkalinity as CaCO3 | 317 | 5.0 | mg/l | | 315 | | | 0.7 | 15 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|------|---------------------------|-------------|---------------|--|--------|-----|-----------|-----------|
| Batch: W0G0013 - SM 2320B (Continued) | | | | | | | | | | |
| Duplicate (W0G0013-DUP1) | | | Source: 0F26062-01 | | | Prepared & Analyzed: 07/01/20 | | | | |
| Bicarbonate Alkalinity as HCO3 | 387 | 6.1 | mg/l | | 384 | | | 0.7 | 15 | |
| Carbonate Alkalinity as CaCO3 | ND | 5.0 | mg/l | | ND | | | | 15 | |
| Hydroxide Alkalinity as CaCO3 | ND | 5.0 | mg/l | | ND | | | | 15 | |
| Batch: W0G0068 - EPA 180.1 | | | | | | | | | | |
| Blank (W0G0068-BLK1) | | | | | | Prepared & Analyzed: 07/01/20 | | | | |
| Turbidity | ND | 0.10 | NTU | | | | | | | |
| LCS (W0G0068-BS1) | | | | | | Prepared & Analyzed: 07/01/20 | | | | |
| Turbidity | 10.2 | 0.10 | NTU | 10.0 | | 102 | 90-110 | | | |
| LCS (W0G0068-BS2) | | | | | | Prepared & Analyzed: 07/01/20 | | | | |
| Turbidity | 1.98 | 0.10 | NTU | 2.00 | | 99 | 90-110 | | | |
| Duplicate (W0G0068-DUP1) | | | Source: 0F12003-01 | | | Prepared & Analyzed: 07/01/20 | | | | |
| Turbidity | 0.100 | 0.10 | NTU | | 0.100 | | | 0 | 10 | |
| Batch: W0G0099 - SM 2510B | | | | | | | | | | |
| Blank (W0G0099-BLK1) | | | | | | Prepared & Analyzed: 07/02/20 | | | | |
| Specific Conductance (EC) | ND | 2.0 | umhos/cm | | | | | | | |
| LCS (W0G0099-BS1) | | | | | | Prepared & Analyzed: 07/02/20 | | | | |
| Specific Conductance (EC) | 441 | 2.0 | umhos/cm | 445 | | 99 | 95-105 | | | |
| Duplicate (W0G0099-DUP1) | | | Source: 0F12004-01 | | | Prepared & Analyzed: 07/02/20 | | | | |
| Specific Conductance (EC) | 650 | 2.0 | umhos/cm | | 647 | | | 0.5 | 5 | |
| Batch: W0G0140 - EPA 335.4 | | | | | | | | | | |
| Blank (W0G0140-BLK1) | | | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | |
| Cyanide, Total | ND | 5.0 | ug/l | | | | | | | |
| LCS (W0G0140-BS1) | | | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | |
| Cyanide, Total | 94.7 | 5.0 | ug/l | 100 | | 95 | 90-110 | | | |
| Matrix Spike (W0G0140-MS1) | | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | |
| Cyanide, Total | 190 | 5.0 | ug/l | 200 | ND | 95 | 90-110 | | | |
| Matrix Spike Dup (W0G0140-MSD1) | | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | |
| Cyanide, Total | 195 | 5.0 | ug/l | 200 | ND | 98 | 90-110 | 3 | 20 | |
| Batch: W0G0163 - SM 5310B | | | | | | | | | | |
| Blank (W0G0163-BLK1) | | | | | | Prepared & Analyzed: 07/06/20 | | | | |
| Dissolved Organic Carbon | ND | 0.30 | mg/l | | | | | | | |
| LCS (W0G0163-BS1) | | | | | | Prepared & Analyzed: 07/06/20 | | | | |
| Dissolved Organic Carbon | 1.07 | 0.30 | mg/l | 1.00 | | 107 | 85-115 | | | |
| Matrix Spike (W0G0163-MS1) | | | Source: 0F24064-02 | | | Prepared & Analyzed: 07/06/20 | | | | |
| Dissolved Organic Carbon | 6.66 | 0.30 | mg/l | 5.00 | 2.57 | 82 | 74-120 | | | |
| Matrix Spike Dup (W0G0163-MSD1) | | | Source: 0F24064-02 | | | Prepared & Analyzed: 07/06/20 | | | | |
| Dissolved Organic Carbon | 6.64 | 0.30 | mg/l | 5.00 | 2.57 | 81 | 74-120 | 0.2 | 20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Diquat and Paraquat by EPA 549.2


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|---|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0142 - EPA 549.2 | | | | | | | | | | |
| Blank (W0G0142-BLK1) | | | | Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| Diquat | ND | 4.0 | ug/l | | | | | | | |
| LCS (W0G0142-BS1) | | | | Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| Diquat | 18.2 | 4.0 | ug/l | 20.0 | | 91 | 70-130 | | | |
| Matrix Spike (W0G0142-MS1) | | | | Source: 0F30024-01 Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| Diquat | 18.3 | 4.0 | ug/l | 20.0 | ND | 91 | 46-122 | | | |
| Matrix Spike (W0G0142-MS2) | | | | Source: 0G06111-01 Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| Diquat | 2.58 | 4.0 | ug/l | 20.0 | ND | 13 | 46-122 | | | MS-01 |
| Matrix Spike Dup (W0G0142-MSD1) | | | | Source: 0F30024-01 Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| Diquat | 17.0 | 4.0 | ug/l | 20.0 | ND | 85 | 46-122 | 7 | 30 | |
| Matrix Spike Dup (W0G0142-MSD2) | | | | Source: 0G06111-01 Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| Diquat | 2.17 | 4.0 | ug/l | 20.0 | ND | 11 | 46-122 | 17 | 30 | MS-01 |

Quality Control Results

(Continued)

Endothall By EPA 548.1

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|---|---------------|------|---------|-----|-----------|-----------|
| Batch: W0G0141 - EPA 548.1 | | | | | | | | | | |
| Blank (W0G0141-BLK1) | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| Endothall | ND | 45 | ug/l | | | | | | | |
| LCS (W0G0141-BS1) | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| Endothall | 75.5 | 45 | ug/l | 100 | | 76 | 31-117 | | | |
| Matrix Spike (W0G0141-MS1) | | | | Source: 0F30024-01 Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| Endothall | 111 | 90 | ug/l | 200 | ND | 56 | 0.1-109 | | | |
| Matrix Spike Dup (W0G0141-MSD1) | | | | Source: 0F30024-01 Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| Endothall | 97.1 | 90 | ug/l | 200 | ND | 49 | 0.1-109 | 14 | 30 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Explosives by EPA Method 8330

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|-----------------------------------|--------|-----|-------|---------------------------------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0131 - EPA 8330A | | | | | | | | | | |
| Blank (W0G0131-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| 1,3,5-Trinitrobenzene | ND | 1.0 | ug/l | | | | | | | |
| 1,3-Dinitrobenzene | ND | 1.0 | ug/l | | | | | | | |
| 2,4,6-Trinitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 2,4-Dinitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 2,6-Dinitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 2-Amino-4,6-Dinitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 2-Nitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 3-Nitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 4-Amino-2,6-Dinitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| 4-Nitrotoluene | ND | 1.0 | ug/l | | | | | | | |
| HMX | ND | 1.0 | ug/l | | | | | | | |
| Nitrobenzene | ND | 1.0 | ug/l | | | | | | | |
| RDX | ND | 1.0 | ug/l | | | | | | | |
| Tetryl | ND | 1.0 | ug/l | | | | | | | |
| LCS (W0G0131-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| 1,3,5-Trinitrobenzene | 2.79 | 1.0 | ug/l | 3.25 | | 86 | 70-130 | | | |
| 1,3-Dinitrobenzene | 2.57 | 1.0 | ug/l | 3.25 | | 79 | 70-130 | | | |
| 2,4,6-Trinitrotoluene | 2.53 | 1.0 | ug/l | 3.25 | | 78 | 70-130 | | | |
| 2,4-Dinitrotoluene | 2.36 | 1.0 | ug/l | 3.25 | | 73 | 70-130 | | | |
| 2,6-Dinitrotoluene | 2.66 | 1.0 | ug/l | 3.25 | | 82 | 70-130 | | | |
| 2-Amino-4,6-Dinitrotoluene | 3.01 | 1.0 | ug/l | 3.25 | | 93 | 70-130 | | | |
| 2-Nitrotoluene | 2.39 | 1.0 | ug/l | 3.25 | | 73 | 70-130 | | | |
| 3-Nitrotoluene | 2.79 | 1.0 | ug/l | 3.25 | | 86 | 70-130 | | | |
| 4-Amino-2,6-Dinitrotoluene | 2.64 | 1.0 | ug/l | 3.25 | | 81 | 70-130 | | | |
| 4-Nitrotoluene | 2.32 | 1.0 | ug/l | 3.25 | | 71 | 70-130 | | | |
| HMX | 2.94 | 1.0 | ug/l | 3.25 | | 91 | 70-130 | | | |
| Nitrobenzene | 2.41 | 1.0 | ug/l | 3.25 | | 74 | 70-130 | | | |
| RDX | 3.01 | 1.0 | ug/l | 3.25 | | 93 | 70-130 | | | |
| Tetryl | 2.46 | 1.0 | ug/l | 3.25 | | 76 | 70-130 | | | |
| LCS Dup (W0G0131-BSD1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| 1,3,5-Trinitrobenzene | 3.02 | 1.0 | ug/l | 3.25 | | 93 | 70-130 | 8 | 25 | |
| 1,3-Dinitrobenzene | 2.59 | 1.0 | ug/l | 3.25 | | 80 | 70-130 | 0.9 | 25 | |
| 2,4,6-Trinitrotoluene | 2.72 | 1.0 | ug/l | 3.25 | | 84 | 70-130 | 7 | 25 | |
| 2,4-Dinitrotoluene | 2.60 | 1.0 | ug/l | 3.25 | | 80 | 70-130 | 9 | 25 | |
| 2,6-Dinitrotoluene | 2.75 | 1.0 | ug/l | 3.25 | | 85 | 70-130 | 3 | 25 | |
| 2-Amino-4,6-Dinitrotoluene | 3.08 | 1.0 | ug/l | 3.25 | | 95 | 70-130 | 2 | 25 | |
| 2-Nitrotoluene | 2.46 | 1.0 | ug/l | 3.25 | | 76 | 70-130 | 3 | 25 | |
| 3-Nitrotoluene | 2.78 | 1.0 | ug/l | 3.25 | | 86 | 70-130 | 0.5 | 25 | |
| 4-Amino-2,6-Dinitrotoluene | 3.07 | 1.0 | ug/l | 3.25 | | 95 | 70-130 | 15 | 25 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Explosives by EPA Method 8330 (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|---|--------|-----|-------|--|---------------|--------|--------|-----|-------|-----------|
| Batch: W0G0131 - EPA 8330A (Continued) | | | | | | | | | | |
| LCS Dup (W0G0131-BSD1) | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| 4-Nitrotoluene | 2.36 | 1.0 | ug/l | 3.25 | 73 | 70-130 | 2 | 25 | | |
| HMX | 2.98 | 1.0 | ug/l | 3.25 | 92 | 70-130 | 1 | 25 | | |
| Nitrobenzene | 2.36 | 1.0 | ug/l | 3.25 | 73 | 70-130 | 2 | 25 | | |
| RDX | 3.10 | 1.0 | ug/l | 3.25 | 95 | 70-130 | 3 | 25 | | |
| Tetryl | 2.61 | 1.0 | ug/l | 3.25 | 80 | 70-130 | 6 | 25 | | |

Quality Control Results

(Continued)

Glycols by GC/FID


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|--|--------|-----|-------|--|---------------|--|--------|-----|-------|-----------|
| Batch: W0F1735 - EPA 8015B | | | | | | | | | | |
| Blank (W0F1735-BLK1) | | | | Prepared & Analyzed: 06/30/20 | | | | | | |
| Ethylene glycol | ND | 10 | mg/l | | | | | | | |
| LCS (W0F1735-BS1) | | | | Prepared & Analyzed: 06/30/20 | | | | | | |
| Ethylene glycol | 76.6 | 10 | mg/l | 100 | 77 | 70-130 | | | | |
| Matrix Spike (W0F1735-MS1) | | | | Source: 0F26019-01 | | Prepared & Analyzed: 06/30/20 | | | | |
| Ethylene glycol | 75.0 | 10 | mg/l | 100 | ND | 75 | 57-127 | | | |
| Matrix Spike Dup (W0F1735-MSD1) | | | | Source: 0F26019-01 | | Prepared & Analyzed: 06/30/20 | | | | |
| Ethylene glycol | 92.5 | 10 | mg/l | 100 | ND | 92 | 57-127 | 21 | 25 | |

Quality Control Results

(Continued)

Glyphosate by EPA 547

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|--|--------|-----|-------|--|---------------|--|--------|-----|-------|-----------|
| Batch: W0F1710 - EPA 547 | | | | | | | | | | |
| Blank (W0F1710-BLK1) | | | | Prepared & Analyzed: 06/30/20 | | | | | | |
| Glyphosate | ND | 5.0 | ug/l | | | | | | | |
| LCS (W0F1710-BS1) | | | | Prepared & Analyzed: 06/30/20 | | | | | | |
| Glyphosate | 25.3 | 5.0 | ug/l | 25.0 | 101 | 70-130 | | | | |
| Matrix Spike (W0F1710-MS1) | | | | Source: 0F26060-01 | | Prepared & Analyzed: 06/30/20 | | | | |
| Glyphosate | 23.5 | 5.0 | ug/l | 25.0 | ND | 94 | 41-149 | | | |
| Matrix Spike Dup (W0F1710-MSD1) | | | | Source: 0F26060-01 | | Prepared & Analyzed: 06/30/20 | | | | |
| Glyphosate | 24.8 | 5.0 | ug/l | 25.0 | ND | 99 | 41-149 | 5 | 30 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Haloacetic Acids (HAAs) by GC/ECD

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|--------------------|-------|---------------------------------------|---------------------------------------|------|--------|-----|-----------|-----------|
| Batch: W0G0076 - EPA 552.3 | | | | | | | | | | |
| Blank (W0G0076-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/02/20 Analyzed: 07/07/20 | | | | | | |
| Dibromoacetic acid (dbaa) | ND | 1.0 | ug/l | | | | | | | |
| Dichloroacetic acid (dcaa) | ND | 1.0 | ug/l | | | | | | | |
| HAA5, Total | ND | 1.0 | ug/l | | | | | | | |
| Monobromoacetic acid (mbaa) | ND | 1.0 | ug/l | | | | | | | |
| Monochloroacetic acid (mcaa) | ND | 2.0 | ug/l | | | | | | | |
| Trichloroacetic acid (tcaa) | ND | 1.0 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2-Bromobutyric acid | 10.4 | | ug/l | 10.0 | | 104 | 70-130 | | | |
| LCS (W0G0076-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/02/20 Analyzed: 07/07/20 | | | | | | |
| Dibromoacetic acid (dbaa) | 10.9 | 1.0 | ug/l | 10.0 | | 109 | 70-130 | | | |
| Dichloroacetic acid (dcaa) | 10.9 | 1.0 | ug/l | 10.0 | | 109 | 70-130 | | | |
| Monobromoacetic acid (mbaa) | 10.8 | 1.0 | ug/l | 10.0 | | 108 | 70-130 | | | |
| Monochloroacetic acid (mcaa) | 10.7 | 2.0 | ug/l | 10.0 | | 107 | 70-130 | | | |
| Trichloroacetic acid (tcaa) | 11.0 | 1.0 | ug/l | 10.0 | | 110 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2-Bromobutyric acid | 10.5 | | ug/l | 10.0 | | 105 | 70-130 | | | |
| Matrix Spike (W0G0076-MS1) | | | | | | | | | | |
| | | Source: 0G01035-01 | | | Prepared: 07/02/20 Analyzed: 07/08/20 | | | | | |
| Dibromoacetic acid (dbaa) | 13.6 | 1.0 | ug/l | 10.0 | 2.11 | 115 | 70-130 | | | |
| Dichloroacetic acid (dcaa) | 13.8 | 1.0 | ug/l | 10.0 | 1.55 | 122 | 70-130 | | | |
| Monobromoacetic acid (mbaa) | 9.67 | 1.0 | ug/l | 10.0 | ND | 97 | 70-130 | | | |
| Monochloroacetic acid (mcaa) | 10.4 | 2.0 | ug/l | 10.0 | ND | 104 | 70-130 | | | |
| Trichloroacetic acid (tcaa) | 13.0 | 1.0 | ug/l | 10.0 | 1.27 | 118 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2-Bromobutyric acid | 10.5 | | ug/l | 10.0 | | 105 | 70-130 | | | |
| Matrix Spike Dup (W0G0076-MSD1) | | | | | | | | | | |
| | | Source: 0G01035-01 | | | Prepared: 07/02/20 Analyzed: 07/08/20 | | | | | |
| Dibromoacetic acid (dbaa) | 13.8 | 1.0 | ug/l | 10.0 | 2.11 | 116 | 70-130 | 1 | 30 | |
| Dichloroacetic acid (dcaa) | 14.3 | 1.0 | ug/l | 10.0 | 1.55 | 127 | 70-130 | 3 | 30 | |
| Monobromoacetic acid (mbaa) | 11.2 | 1.0 | ug/l | 10.0 | ND | 112 | 70-130 | 14 | 30 | |
| Monochloroacetic acid (mcaa) | 10.5 | 2.0 | ug/l | 10.0 | ND | 105 | 70-130 | 2 | 30 | |
| Trichloroacetic acid (tcaa) | 13.5 | 1.0 | ug/l | 10.0 | 1.27 | 122 | 70-130 | 3 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 2-Bromobutyric acid | 10.2 | | ug/l | 10.0 | | 102 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Low Level 1,2,3-TCP by SRL Method, P&T, GC/MS SIM

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--------------------------------------|---------|--------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0002 - SRL 524M-TCP | | | | | | | | | | |
| Blank (W0G0002-BLK1) | | | | | | | | | | |
| 1,2,3-Trichloropropane | ND | 0.0050 | ug/l | | | | | | | |
| | | | | Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | |
| LCS (W0G0002-BS1) | | | | | | | | | | |
| 1,2,3-Trichloropropane | 0.00578 | 0.0050 | ug/l | 0.00500 | | 116 | 80-120 | | | |
| | | | | Prepared & Analyzed: 07/01/20 | | | | | | |
| LCS Dup (W0G0002-BSD1) | | | | | | | | | | |
| 1,2,3-Trichloropropane | 0.00541 | 0.0050 | ug/l | 0.00500 | | 108 | 80-120 | 7 | 20 | |
| | | | | Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | |
| Duplicate (W0G0002-DUP1) | | | | | | | | | | |
| 1,2,3-Trichloropropane | 0.00478 | 0.0050 | ug/l | | 0.00480 | | | 0.4 | 20 | |
| | | | | Source: 0F22101-02 | | | | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Metals by EPA 200 Series Methods

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | Limit | Qualifier |
|--|--------|-------|-------|--|---------------|------|--------|-----|-------|-----------|
| Batch: W0G0033 - EPA 200.7 | | | | | | | | | | |
| Blank (W0G0033-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | |
| Boron, Total | ND | 10 | ug/l | | | | | | | |
| Calcium, Total | ND | 0.100 | mg/l | | | | | | | |
| Iron, Total | ND | 10 | ug/l | | | | | | | |
| Magnesium, Total | ND | 0.100 | mg/l | | | | | | | |
| Potassium, Total | ND | 0.10 | mg/l | | | | | | | |
| Sodium, Total | ND | 0.50 | mg/l | | | | | | | |
| LCS (W0G0033-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | |
| Boron, Total | 203 | 10 | ug/l | 200 | | 101 | 85-115 | | | |
| Calcium, Total | 49.8 | 0.100 | mg/l | 50.2 | | 99 | 85-115 | | | |
| Iron, Total | 196 | 10 | ug/l | 200 | | 98 | 85-115 | | | |
| Magnesium, Total | 49.6 | 0.100 | mg/l | 50.2 | | 99 | 85-115 | | | |
| Potassium, Total | 51.7 | 0.10 | mg/l | 50.2 | | 103 | 85-115 | | | |
| Sodium, Total | 49.6 | 0.50 | mg/l | 50.2 | | 99 | 85-115 | | | |
| Matrix Spike (W0G0033-MS1) | | | | | | | | | | |
| | | | | Source: 0F22022-01 Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | |
| Boron, Total | 332 | 10 | ug/l | 200 | 127 | 102 | 70-130 | | | |
| Calcium, Total | 137 | 0.100 | mg/l | 50.2 | 92.4 | 89 | 70-130 | | | |
| Iron, Total | 198 | 10 | ug/l | 200 | ND | 99 | 70-130 | | | |
| Magnesium, Total | 67.6 | 0.100 | mg/l | 50.2 | 18.2 | 98 | 70-130 | | | |
| Potassium, Total | 60.3 | 0.10 | mg/l | 50.2 | 5.39 | 109 | 70-130 | | | |
| Sodium, Total | 80.2 | 0.50 | mg/l | 50.2 | 29.3 | 101 | 70-130 | | | |
| Matrix Spike Dup (W0G0033-MSD1) | | | | | | | | | | |
| | | | | Source: 0F22022-01 Prepared: 07/01/20 Analyzed: 07/02/20 | | | | | | |
| Boron, Total | 336 | 10 | ug/l | 200 | 127 | 105 | 70-130 | 1 | 30 | |
| Calcium, Total | 139 | 0.100 | mg/l | 50.2 | 92.4 | 92 | 70-130 | 1 | 30 | |
| Iron, Total | 202 | 10 | ug/l | 200 | ND | 101 | 70-130 | 2 | 30 | |
| Magnesium, Total | 68.9 | 0.100 | mg/l | 50.2 | 18.2 | 101 | 70-130 | 2 | 30 | |
| Potassium, Total | 61.6 | 0.10 | mg/l | 50.2 | 5.39 | 112 | 70-130 | 2 | 30 | |
| Sodium, Total | 81.5 | 0.50 | mg/l | 50.2 | 29.3 | 104 | 70-130 | 2 | 30 | |
| Batch: W0G0175 - EPA 245.1 | | | | | | | | | | |
| Blank (W0G0175-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/08/20 Analyzed: 07/09/20 | | | | | | |
| Mercury, Total | ND | 0.050 | ug/l | | | | | | | B-07 |
| LCS (W0G0175-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/08/20 Analyzed: 07/09/20 | | | | | | |
| Mercury, Total | 1.04 | 0.050 | ug/l | 1.00 | | 104 | 85-115 | | | |
| Matrix Spike (W0G0175-MS1) | | | | | | | | | | |
| | | | | Source: 0F30024-01 Prepared: 07/08/20 Analyzed: 07/09/20 | | | | | | |
| Mercury, Total | 1.05 | 0.050 | ug/l | 1.00 | ND | 105 | 70-130 | | | |
| Matrix Spike (W0G0175-MS2) | | | | | | | | | | |
| | | | | Source: 0G01049-01 Prepared: 07/08/20 Analyzed: 07/09/20 | | | | | | |
| Mercury, Total | 1.04 | 0.050 | ug/l | 1.00 | ND | 104 | 70-130 | | | |
| Matrix Spike Dup (W0G0175-MSD1) | | | | | | | | | | |
| | | | | Source: 0F30024-01 Prepared: 07/08/20 Analyzed: 07/09/20 | | | | | | |
| Mercury, Total | 1.06 | 0.050 | ug/l | 1.00 | ND | 106 | 70-130 | 1 | 20 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Metals by EPA 200 Series Methods (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-------|--|-------------|---------------|--|--------|-----|-----------|-----------|
| Batch: W0G0175 - EPA 245.1 (Continued) | | | | | | | | | | |
| Matrix Spike Dup (W0G0175-MSD2) | | | Source: 0G01049-01 | | | Prepared: 07/08/20 Analyzed: 07/09/20 | | | | |
| Mercury, Total | 1.05 | 0.050 | ug/l | 1.00 | ND | 105 | 70-130 | 2 | 20 | |
| Batch: W0G0423 - EPA 200.8 | | | | | | | | | | |
| Blank (W0G0423-BLK1) | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | | | | | |
| Aluminum, Total | ND | 5.0 | ug/l | | | | | | | |
| Antimony, Total | ND | 0.50 | ug/l | | | | | | | |
| Arsenic, Total | ND | 0.40 | ug/l | | | | | | | |
| Barium, Total | ND | 0.50 | ug/l | | | | | | | |
| Beryllium, Total | ND | 0.10 | ug/l | | | | | | | |
| Cadmium, Total | ND | 0.10 | ug/l | | | | | | | |
| Chromium, Total | ND | 0.20 | ug/l | | | | | | | |
| Copper, Total | ND | 0.50 | ug/l | | | | | | | |
| Lead, Total | ND | 0.20 | ug/l | | | | | | | |
| Manganese, Total | ND | 0.20 | ug/l | | | | | | | |
| Nickel, Total | ND | 0.80 | ug/l | | | | | | | |
| Selenium, Total | ND | 0.40 | ug/l | | | | | | | |
| Silver, Total | ND | 0.20 | ug/l | | | | | | | |
| Thallium, Total | ND | 0.20 | ug/l | | | | | | | |
| Vanadium, Total | ND | 0.50 | ug/l | | | | | | | |
| Zinc, Total | ND | 5.0 | ug/l | | | | | | | |
| LCS (W0G0423-BS1) | | | | | | | | | | |
| Prepared: 07/09/20 Analyzed: 07/13/20 | | | | | | | | | | |
| Aluminum, Total | 53.6 | 5.0 | ug/l | 50.0 | | 107 | 85-115 | | | |
| Antimony, Total | 48.2 | 0.50 | ug/l | 50.0 | | 96 | 85-115 | | | |
| Arsenic, Total | 51.6 | 0.40 | ug/l | 50.0 | | 103 | 85-115 | | | |
| Barium, Total | 49.1 | 0.50 | ug/l | 50.0 | | 98 | 85-115 | | | |
| Beryllium, Total | 47.3 | 0.10 | ug/l | 50.0 | | 95 | 85-115 | | | |
| Cadmium, Total | 50.3 | 0.10 | ug/l | 50.0 | | 101 | 85-115 | | | |
| Chromium, Total | 50.6 | 0.20 | ug/l | 50.0 | | 101 | 85-115 | | | |
| Copper, Total | 51.5 | 0.50 | ug/l | 50.0 | | 103 | 85-115 | | | |
| Lead, Total | 49.1 | 0.20 | ug/l | 50.0 | | 98 | 85-115 | | | |
| Manganese, Total | 50.9 | 0.20 | ug/l | 50.0 | | 102 | 85-115 | | | |
| Nickel, Total | 50.2 | 0.80 | ug/l | 50.0 | | 100 | 85-115 | | | |
| Selenium, Total | 50.8 | 0.40 | ug/l | 50.0 | | 102 | 85-115 | | | |
| Silver, Total | 51.1 | 0.20 | ug/l | 50.0 | | 102 | 85-115 | | | |
| Thallium, Total | 49.2 | 0.20 | ug/l | 50.0 | | 98 | 85-115 | | | |
| Vanadium, Total | 49.7 | 0.50 | ug/l | 50.0 | | 99 | 85-115 | | | |
| Zinc, Total | 50.6 | 5.0 | ug/l | 50.0 | | 101 | 85-115 | | | |
| Matrix Spike (W0G0423-MS1) | | | | | | | | | | |
| Source: 0G08072-03 | | | | | | | | | | |
| Prepared: 07/09/20 Analyzed: 07/13/20 | | | | | | | | | | |
| Aluminum, Total | 93.2 | 5.0 | ug/l | 50.0 | 53.0 | 80 | 70-130 | | | |
| Antimony, Total | 47.1 | 0.50 | ug/l | 50.0 | 0.0482 | 94 | 70-130 | | | |

0F30024

Page 40 of 55



Certificate of Analysis

FINAL REPORT

Las Virgenes Municipal Water District
 4232 Las Virgenes Road
 Calabasas, CA 91302

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Metals by EPA 200 Series Methods (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|------|---------------------------|-------------|---------------|--|--------|------|-----------|-----------|
| Batch: W0G0423 - EPA 200.8 (Continued) | | | | | | | | | | |
| Matrix Spike (W0G0423-MS1) | | | Source: 0G08072-03 | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | | |
| Arsenic, Total | 50.4 | 0.40 | ug/l | 50.0 | 0.289 | 100 | 70-130 | | | |
| Barium, Total | 135 | 0.50 | ug/l | 50.0 | 87.3 | 96 | 70-130 | | | |
| Beryllium, Total | 46.6 | 0.10 | ug/l | 50.0 | ND | 93 | 70-130 | | | |
| Cadmium, Total | 48.0 | 0.10 | ug/l | 50.0 | ND | 96 | 70-130 | | | |
| Chromium, Total | 60.3 | 0.20 | ug/l | 50.0 | 12.2 | 96 | 70-130 | | | |
| Copper, Total | 113 | 0.50 | ug/l | 50.0 | 68.7 | 88 | 70-130 | | | |
| Lead, Total | 46.1 | 0.20 | ug/l | 50.0 | 0.187 | 92 | 70-130 | | | |
| Manganese, Total | 56.8 | 0.20 | ug/l | 50.0 | 10.3 | 93 | 70-130 | | | |
| Nickel, Total | 51.4 | 0.80 | ug/l | 50.0 | 6.95 | 89 | 70-130 | | | |
| Selenium, Total | 48.5 | 0.40 | ug/l | 50.0 | 0.877 | 95 | 70-130 | | | |
| Silver, Total | 46.6 | 0.20 | ug/l | 50.0 | ND | 93 | 70-130 | | | |
| Thallium, Total | 46.5 | 0.20 | ug/l | 50.0 | ND | 93 | 70-130 | | | |
| Vanadium, Total | 75.6 | 0.50 | ug/l | 50.0 | 29.2 | 93 | 70-130 | | | |
| Zinc, Total | 49.2 | 5.0 | ug/l | 50.0 | 2.83 | 93 | 70-130 | | | |
| Matrix Spike Dup (W0G0423-MSD1) | | | Source: 0G08072-03 | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | | |
| Aluminum, Total | 90.1 | 5.0 | ug/l | 50.0 | 53.0 | 74 | 70-130 | 3 | 30 | |
| Antimony, Total | 47.7 | 0.50 | ug/l | 50.0 | 0.0482 | 95 | 70-130 | 1 | 30 | |
| Arsenic, Total | 50.8 | 0.40 | ug/l | 50.0 | 0.289 | 101 | 70-130 | 0.8 | 30 | |
| Barium, Total | 134 | 0.50 | ug/l | 50.0 | 87.3 | 93 | 70-130 | 1 | 30 | |
| Beryllium, Total | 46.9 | 0.10 | ug/l | 50.0 | ND | 94 | 70-130 | 0.7 | 30 | |
| Cadmium, Total | 48.4 | 0.10 | ug/l | 50.0 | ND | 97 | 70-130 | 0.9 | 30 | |
| Chromium, Total | 59.4 | 0.20 | ug/l | 50.0 | 12.2 | 95 | 70-130 | 1 | 30 | |
| Copper, Total | 113 | 0.50 | ug/l | 50.0 | 68.7 | 89 | 70-130 | 0.6 | 30 | |
| Lead, Total | 46.1 | 0.20 | ug/l | 50.0 | 0.187 | 92 | 70-130 | 0.07 | 30 | |
| Manganese, Total | 56.9 | 0.20 | ug/l | 50.0 | 10.3 | 93 | 70-130 | 0.1 | 30 | |
| Nickel, Total | 52.0 | 0.80 | ug/l | 50.0 | 6.95 | 90 | 70-130 | 1 | 30 | |
| Selenium, Total | 49.7 | 0.40 | ug/l | 50.0 | 0.877 | 98 | 70-130 | 2 | 30 | |
| Silver, Total | 47.2 | 0.20 | ug/l | 50.0 | ND | 94 | 70-130 | 1 | 30 | |
| Thallium, Total | 46.1 | 0.20 | ug/l | 50.0 | ND | 92 | 70-130 | 0.8 | 30 | |
| Vanadium, Total | 74.1 | 0.50 | ug/l | 50.0 | 29.2 | 90 | 70-130 | 2 | 30 | |
| Zinc, Total | 49.0 | 5.0 | ug/l | 50.0 | 2.83 | 92 | 70-130 | 0.4 | 30 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Nitrosamines by CI GC/MS/MS, EPA 521

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---------------------------------|--------|-----|-------|---------------------------------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0130 - EPA 521 | | | | | | | | | | |
| Blank (W0G0130-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| N-Nitrosodiethylamine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosodimethylamine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosodi-n-butylamine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosodi-n-propylamine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosomethylethylamine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosomorpholine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosopiperidine | ND | 2.0 | ng/l | | | | | | | |
| N-Nitrosopyrrolidine | ND | 2.0 | ng/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| NDMA-d6 | 24.0 | | ng/l | 25.0 | | 96 | 70-130 | | | |
| LCS (W0G0130-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/09/20 | | | | | | |
| N-Nitrosodiethylamine | 2.97 | 2.0 | ng/l | 4.00 | | 74 | 70-130 | | | |
| N-Nitrosodimethylamine | 3.24 | 2.0 | ng/l | 4.00 | | 81 | 70-130 | | | |
| N-Nitrosodi-n-butylamine | 2.91 | 2.0 | ng/l | 4.00 | | 73 | 70-130 | | | |
| N-Nitrosodi-n-propylamine | 2.86 | 2.0 | ng/l | 4.00 | | 71 | 70-130 | | | |
| N-Nitrosomethylethylamine | 3.08 | 2.0 | ng/l | 4.00 | | 77 | 70-130 | | | |
| N-Nitrosomorpholine | 3.14 | 2.0 | ng/l | 4.00 | | 78 | 70-130 | | | |
| N-Nitrosopiperidine | 3.26 | 2.0 | ng/l | 4.00 | | 81 | 70-130 | | | |
| N-Nitrosopyrrolidine | 3.73 | 2.0 | ng/l | 4.00 | | 93 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| NDMA-d6 | 26.7 | | ng/l | 25.0 | | 107 | 70-130 | | | |
| LCS Dup (W0G0130-BSD1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/08/20 | | | | | | |
| N-Nitrosodiethylamine | 3.19 | 2.0 | ng/l | 4.00 | | 80 | 70-130 | 7 | 30 | |
| N-Nitrosodimethylamine | 3.57 | 2.0 | ng/l | 4.00 | | 89 | 70-130 | 10 | 30 | |
| N-Nitrosodi-n-butylamine | 3.04 | 2.0 | ng/l | 4.00 | | 76 | 70-130 | 5 | 30 | |
| N-Nitrosodi-n-propylamine | 3.30 | 2.0 | ng/l | 4.00 | | 83 | 70-130 | 14 | 30 | |
| N-Nitrosomethylethylamine | 3.27 | 2.0 | ng/l | 4.00 | | 82 | 70-130 | 6 | 30 | |
| N-Nitrosomorpholine | 3.64 | 2.0 | ng/l | 4.00 | | 91 | 70-130 | 15 | 30 | |
| N-Nitrosopiperidine | 3.31 | 2.0 | ng/l | 4.00 | | 83 | 70-130 | 2 | 30 | |
| N-Nitrosopyrrolidine | 3.80 | 2.0 | ng/l | 4.00 | | 95 | 70-130 | 2 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| NDMA-d6 | 26.7 | | ng/l | 25.0 | | 107 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Organic Compounds by Tandem LC/MS/MS

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|----------------------------------|--------|-----|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0H0124 - LC/MS/MS | | | | | | | | | | |
| Blank (W0H0124-BLK1) | | | | | | | | | | |
| lohexol | ND | 5.0 | ng/l | | | | | | | |
| | | | | Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | |
| LCS (W0H0124-BS1) | | | | | | | | | | |
| lohexol | 10.4 | 5.0 | ng/l | 50.0 | | 21 | 50-150 | | | BS-L |
| | | | | Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | |
| LCS Dup (W0H0124-BSD1) | | | | | | | | | | |
| lohexol | 19.3 | 5.0 | ng/l | 50.0 | | 39 | 50-150 | 60 | 30 | BS-L |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Per- and Polyfluorinated Alkyl Substances (PFAS) by SPE/LCMSMS

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---------------------------------------|--------|-----|-------|-------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0516 - EPA 537.1 | | | | | | | | | | |
| Blank (W0G0516-BLK1) | | | | | | | | | | |
| Prepared: 07/10/20 Analyzed: 07/14/20 | | | | | | | | | | |
| 11CI-PF3OUdS | ND | 2.0 | ng/l | | | | | | | |
| 9CI-PF3ONS | ND | 2.0 | ng/l | | | | | | | |
| ADONA | ND | 2.0 | ng/l | | | | | | | |
| EtFOSAA | ND | 2.0 | ng/l | | | | | | | |
| HFPO-DA | ND | 2.0 | ng/l | | | | | | | |
| MeFOSAA | ND | 2.0 | ng/l | | | | | | | |
| PFBS | ND | 2.0 | ng/l | | | | | | | |
| PFDA | ND | 2.0 | ng/l | | | | | | | |
| PFDoA | ND | 2.0 | ng/l | | | | | | | |
| PFHpA | 52.9 | 2.0 | ng/l | | | | | | | B |
| PFHxA | 3.97 | 2.0 | ng/l | | | | | | | B |
| PFHxS | ND | 2.0 | ng/l | | | | | | | |
| PFNA | ND | 2.0 | ng/l | | | | | | | |
| PFOA | ND | 2.0 | ng/l | | | | | | | |
| PFOS | ND | 2.0 | ng/l | | | | | | | |
| PFTeDA | ND | 2.0 | ng/l | | | | | | | |
| PFTrDA | ND | 2.0 | ng/l | | | | | | | |
| PFUnA | ND | 2.0 | ng/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 13C2-PFDA | 31.7 | | ng/l | 40.0 | | 79 | 70-130 | | | |
| 13C2-PFHxA | 43.9 | | ng/l | 40.0 | | 110 | 70-130 | | | |
| d5-EtFOSAA | 26.4 | | ng/l | 40.0 | | 66 | 70-130 | | | S-11 |
| HFPO-DA-13C3 | 44.0 | | ng/l | 40.0 | | 110 | 70-130 | | | |
| LCS (W0G0516-BS1) | | | | | | | | | | |
| Prepared: 07/10/20 Analyzed: 07/14/20 | | | | | | | | | | |
| 11CI-PF3OUdS | 1.84 | 2.0 | ng/l | 2.00 | | 92 | 50-150 | | | |
| 9CI-PF3ONS | 2.17 | 2.0 | ng/l | 2.00 | | 108 | 50-150 | | | |
| ADONA | 2.32 | 2.0 | ng/l | 2.00 | | 116 | 50-150 | | | |
| EtFOSAA | 2.22 | 2.0 | ng/l | 2.00 | | 111 | 50-150 | | | |
| HFPO-DA | 2.62 | 2.0 | ng/l | 2.00 | | 131 | 50-150 | | | |
| MeFOSAA | 2.21 | 2.0 | ng/l | 2.00 | | 111 | 50-150 | | | |
| PFBS | 2.64 | 2.0 | ng/l | 2.00 | | 132 | 50-150 | | | |
| PFDA | 2.32 | 2.0 | ng/l | 2.00 | | 116 | 50-150 | | | |
| PFDoA | 2.19 | 2.0 | ng/l | 2.00 | | 109 | 50-150 | | | |
| PFHpA | 17.8 | 2.0 | ng/l | 2.00 | | 888 | 50-150 | | | BS-H |
| PFHxA | 3.50 | 2.0 | ng/l | 2.00 | | 175 | 50-150 | | | BS-H |
| PFHxS | 2.43 | 2.0 | ng/l | 2.00 | | 121 | 50-150 | | | |
| PFNA | 2.57 | 2.0 | ng/l | 2.00 | | 128 | 50-150 | | | |
| PFOA | 2.67 | 2.0 | ng/l | 2.00 | | 134 | 50-150 | | | |
| PFOS | 2.53 | 2.0 | ng/l | 2.00 | | 126 | 50-150 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Per- and Polyfluorinated Alkyl Substances (PFAS) by SPE/LCMSMS (Continued)


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|-----|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0516 - EPA 537.1 (Continued) | | | | | | | | | | |
| LCS (W0G0516-BS1) | | | | Prepared: 07/10/20 Analyzed: 07/14/20 | | | | | | |
| PFTeDA | 1.43 | 2.0 | ng/l | 2.00 | | 72 | 50-150 | | | |
| PFTrDA | 1.55 | 2.0 | ng/l | 2.00 | | 77 | 50-150 | | | |
| PFUnA | 1.99 | 2.0 | ng/l | 2.00 | | 100 | 50-150 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 13C2-PFDA | 42.7 | | ng/l | 40.0 | | 107 | 70-130 | | | |
| 13C2-PFHxA | 46.4 | | ng/l | 40.0 | | 116 | 70-130 | | | |
| d5-EtFOSAA | 40.4 | | ng/l | 40.0 | | 101 | 70-130 | | | |
| HFPO-DA-13C3 | 45.9 | | ng/l | 40.0 | | 115 | 70-130 | | | |

Quality Control Results

(Continued)

Perchlorate by EPA 314.0

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|--|---------------|------|--|-----|-----------|-----------|
| Batch: W0F1821 - EPA 314.0 | | | | | | | | | | |
| Blank (W0F1821-BLK1) | | | | Prepared & Analyzed: 06/30/20 | | | | | | |
| Perchlorate | ND | 2.0 | ug/l | | | | | | | |
| LCS (W0F1821-BS1) | | | | Prepared & Analyzed: 06/30/20 | | | | | | |
| Perchlorate | 8.83 | 2.0 | ug/l | 10.0 | | 88 | 85-115 | | | |
| Matrix Spike (W0F1821-MS1) | | | | Source: 0F22022-01 | | | Prepared & Analyzed: 06/30/20 | | | |
| Perchlorate | 8.89 | 2.0 | ug/l | 10.0 | ND | 89 | 80-120 | | | |
| Matrix Spike Dup (W0F1821-MSD1) | | | | Source: 0F22022-01 | | | Prepared & Analyzed: 06/30/20 | | | |
| Perchlorate | 8.75 | 2.0 | ug/l | 10.0 | ND | 87 | 80-120 | 2 | 15 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

PPCPs - Pharmaceuticals by LC/MSMS-ESI-

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|--|---------------|------|---------|------|-----------|-----------|
| Batch: W0G1397 - EPA 1694M-ESI- | | | | | | | | | | |
| Blank (W0G1397-BLK1) | | | | | | | | | | |
| | | | | Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | |
| Bisphenol A | ND | 1.0 | ng/l | | | | | | | |
| Diclofenac | ND | 1.0 | ng/l | | | | | | | |
| Gemfibrozil | ND | 1.0 | ng/l | | | | | | | |
| Ibuprofen | ND | 1.0 | ng/l | | | | | | | |
| Iopromide | ND | 5.0 | ng/l | | | | | | | |
| Naproxen | ND | 1.0 | ng/l | | | | | | | |
| Salicylic Acid | 168 | 50 | ng/l | | | | | | | B |
| Triclosan | ND | 2.0 | ng/l | | | | | | | |
| LCS (W0G1397-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | |
| Bisphenol A | 9.14 | 1.0 | ng/l | 10.0 | | 91 | 53-168 | | | |
| Diclofenac | 9.79 | 1.0 | ng/l | 10.0 | | 98 | 37-218 | | | |
| Gemfibrozil | 8.89 | 1.0 | ng/l | 10.0 | | 89 | 76-122 | | | |
| Ibuprofen | 9.43 | 1.0 | ng/l | 10.0 | | 94 | 67-139 | | | |
| Iopromide | 5.36 | 5.0 | ng/l | 50.0 | | 11 | 0.1-163 | | | |
| Naproxen | 9.54 | 1.0 | ng/l | 10.0 | | 95 | 64-138 | | | |
| Salicylic Acid | 165 | 50 | ng/l | 100 | | 165 | 56-229 | | | |
| Triclosan | 9.10 | 2.0 | ng/l | 10.0 | | 91 | 76-139 | | | |
| LCS Dup (W0G1397-BSD1) | | | | | | | | | | |
| | | | | Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | |
| Bisphenol A | 10.6 | 1.0 | ng/l | 10.0 | | 106 | 53-168 | 15 | 30 | |
| Diclofenac | 10.4 | 1.0 | ng/l | 10.0 | | 104 | 37-218 | 6 | 30 | |
| Gemfibrozil | 9.73 | 1.0 | ng/l | 10.0 | | 97 | 76-122 | 9 | 30 | |
| Ibuprofen | 9.43 | 1.0 | ng/l | 10.0 | | 94 | 67-139 | 0.01 | 30 | |
| Iopromide | 12.1 | 5.0 | ng/l | 50.0 | | 24 | 0.1-163 | 77 | 30 | Q-12 |
| Naproxen | 10.7 | 1.0 | ng/l | 10.0 | | 107 | 64-138 | 11 | 30 | |
| Salicylic Acid | 159 | 50 | ng/l | 100 | | 159 | 56-229 | 3 | 30 | |
| Triclosan | 9.27 | 2.0 | ng/l | 10.0 | | 93 | 76-139 | 2 | 30 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

PPCPs - Pharmaceuticals by LC/MSMS-ESI+

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|-------------|---------------|------|---------|-----|-----------|-----------|
| Batch: W0G1399 - EPA 1694M-ESI+ | | | | | | | | | | |
| Blank (W0G1399-BLK1) | | | | | | | | | | |
| Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | | | | | |
| Acetaminophen | ND | 20 | ng/l | | | | | | | |
| Amoxicillin | ND | 10 | ng/l | | | | | | | |
| Atenolol | 4.71 | 1.0 | ng/l | | | | | | | B |
| Atorvastatin | ND | 1.0 | ng/l | | | | | | | |
| Azithromycin | 18.9 | 10 | ng/l | | | | | | | B |
| Caffeine | 6.76 | 1.0 | ng/l | | | | | | | B |
| Carbamazepine | ND | 1.0 | ng/l | | | | | | | |
| Ciprofloxacin | 146 | 5.0 | ng/l | | | | | | | B |
| Cotinine | 2.80 | 2.0 | ng/l | | | | | | | B |
| DEET | ND | 1.0 | ng/l | | | | | | | |
| Diazepam | ND | 1.0 | ng/l | | | | | | | |
| Fluoxetine | ND | 1.0 | ng/l | | | | | | | |
| Galaxolide (HHCB) | 14.8 | 10 | ng/l | | | | | | | B-06 |
| Meprobamate | ND | 1.0 | ng/l | | | | | | | |
| Methadone | ND | 1.0 | ng/l | | | | | | | |
| Oxybenzone | ND | 1.0 | ng/l | | | | | | | |
| Phenytoin (Dilantin) | ND | 5.0 | ng/l | | | | | | | A-01a |
| Praziquantel | ND | 1.0 | ng/l | | | | | | | |
| Primidone | ND | 1.0 | ng/l | | | | | | | |
| Quinoline | 1.47 | 1.0 | ng/l | | | | | | | B-06 |
| Sucralose | 318 | 5.0 | ng/l | | | | | | | B |
| Sulfamethoxazole | ND | 1.0 | ng/l | | | | | | | |
| TCEP | ND | 1.0 | ng/l | | | | | | | |
| T CPP | ND | 1.0 | ng/l | | | | | | | |
| TDCPP | ND | 1.0 | ng/l | | | | | | | |
| Trimethoprim | ND | 1.0 | ng/l | | | | | | | |
| LCS (W0G1399-BS1) | | | | | | | | | | |
| Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | | | | | |
| Acetaminophen | 75.9 | 20 | ng/l | 200 | | 38 | 66-156 | | | BS-04 |
| Amoxicillin | 212 | 10 | ng/l | 100 | | 212 | 14-167 | | | BS-04 |
| Atenolol | 10.1 | 1.0 | ng/l | 10.0 | | 101 | 56-164 | | | |
| Atorvastatin | 10.4 | 1.0 | ng/l | 10.0 | | 104 | 0.1-173 | | | |
| Azithromycin | 76.4 | 10 | ng/l | 100 | | 76 | 52-166 | | | |
| Caffeine | 10.5 | 1.0 | ng/l | 10.0 | | 105 | 55-152 | | | |
| Carbamazepine | 9.77 | 1.0 | ng/l | 10.0 | | 98 | 60-135 | | | |
| Ciprofloxacin | 100 | 5.0 | ng/l | 50.0 | | 200 | 51-168 | | | BS-H |
| Cotinine | 14.3 | 2.0 | ng/l | 10.0 | | 143 | 68-155 | | | |
| DEET | 12.6 | 1.0 | ng/l | 10.0 | | 126 | 45-135 | | | |
| Diazepam | 8.27 | 1.0 | ng/l | 10.0 | | 83 | 58-127 | | | |
| Fluoxetine | 8.44 | 1.0 | ng/l | 10.0 | | 84 | 55-150 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

PPCPs - Pharmaceuticals by LC/MSMS-ESI+ (Continued)

Table with columns: Analyte, Result, MRL, Units, Spike Level, Source Result, %REC, Limits, RPD, Limit, Qualifier. Includes sections for LCS (W0G1399-BS1) and LCS Dup (W0G1399-BSD1) with various pharmaceuticals listed.



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

PPCPs - Pharmaceuticals by LC/MSMS-ESI+ (Continued)


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-----|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G1399 - EPA 1694M-ESI+ (Continued) | | | | | | | | | | |
| LCS Dup (W0G1399-BSD1) | | | | Prepared: 07/28/20 Analyzed: 08/10/20 | | | | | | |
| TDCPP | 8.44 | 1.0 | ng/l | 10.0 | | 84 | 20-158 | 21 | 30 | |
| Trimethoprim | 9.80 | 1.0 | ng/l | 10.0 | | 98 | 67-139 | 5 | 30 | |

Quality Control Results

(Continued)

Radiological Parameters by APHA/EPA Methods

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|------------|-------|--|---------------|------|--|-----|-----------|-----------|
| Batch: W0G0146 - EPA 900.0 | | | | | | | | | | |
| Blank (W0G0146-BLK1) | | | | Prepared: 07/06/20 Analyzed: 07/07/20 | | | | | | |
| Gross Alpha | 0.42 | | pCi/L | | | | | | | |
| Uncertainty: 0.283 | | MDA: 0.451 | | | | | | | | |
| Gross Beta | -1.6 | | pCi/L | | | | | | | |
| Uncertainty: 0.508 | | MDA: 0.79 | | | | | | | | |
| LCS (W0G0146-BS1) | | | | Prepared: 07/06/20 Analyzed: 07/07/20 | | | | | | |
| Gross Alpha | 11 | | pCi/L | 12.0 | | 91 | 64-139 | | | |
| Uncertainty: 0.73 | | MDA: 0.521 | | | | | | | | |
| Gross Beta | 14 | | pCi/L | 16.0 | | 88 | 77-138 | | | |
| Uncertainty: 0.772 | | MDA: 0.644 | | | | | | | | |
| Matrix Spike (W0G0146-MS1) | | | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/07/20 | | | |
| Gross Alpha | 7.3 | | pCi/L | 12.0 | 0.40 | 58 | 70-130 | | | MS-01 |
| Uncertainty: 0.682 | | MDA: 0.544 | | | | | | | | |
| Gross Beta | 14 | | pCi/L | 16.0 | 1.4 | 80 | 70-130 | | | |
| Uncertainty: 0.775 | | MDA: 0.687 | | | | | | | | |
| Matrix Spike Dup (W0G0146-MSD1) | | | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/07/20 | | | |
| Gross Alpha | 7.5 | | pCi/L | 12.0 | 0.40 | 59 | 70-130 | 2 | 30 | MS-01 |
| Uncertainty: 0.685 | | MDA: 0.513 | | | | | | | | |
| Gross Beta | 17 | | pCi/L | 16.0 | 1.4 | 95 | 70-130 | 15 | 30 | |
| Uncertainty: 0.819 | | MDA: 0.669 | | | | | | | | |
| Batch: W0G0675 - EPA 200.8 | | | | | | | | | | |
| Blank (W0G0675-BLK1) | | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | | | | |
| Uranium Rad | ND | 0.13 | pCi/L | | | | | | | |
| LCS (W0G0675-BS1) | | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | | | | |
| Uranium Rad | 32.1 | 0.13 | pCi/L | 33.5 | | 96 | 85-115 | | | |
| Matrix Spike (W0G0675-MS1) | | | | Source: 0G08072-03RE1 | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | |
| Uranium Rad | 31.5 | 0.13 | pCi/L | 33.5 | 0.131 | 94 | 70-130 | | | |
| Matrix Spike Dup (W0G0675-MSD1) | | | | Source: 0G08072-03RE1 | | | Prepared: 07/09/20 Analyzed: 07/13/20 | | | |
| Uranium Rad | 31.7 | 0.13 | pCi/L | 33.5 | 0.131 | 94 | 70-130 | 0.5 | 30 | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Semivolatile Organic Compounds by GC/MS

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|-----------------------------------|--------|------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0136 - EPA 525.2 | | | | | | | | | | |
| Blank (W0G0136-BLK1) | | | | Prepared: 07/06/20 Analyzed: 07/22/20 | | | | | | |
| Alachlor | ND | 0.10 | ug/l | | | | | | | |
| Atrazine | ND | 0.10 | ug/l | | | | | | | |
| Benzo (a) pyrene | ND | 0.10 | ug/l | | | | | | | |
| Bis(2-ethylhexyl)adipate | ND | 5.0 | ug/l | | | | | | | |
| Bis(2-ethylhexyl)phthalate | ND | 3.0 | ug/l | | | | | | | |
| Bromacil | ND | 0.50 | ug/l | | | | | | | |
| Butachlor | ND | 0.10 | ug/l | | | | | | | |
| Captan | ND | 1.0 | ug/l | | | | | | | |
| Chlorpropham | ND | 0.10 | ug/l | | | | | | | |
| Cyanazine | ND | 0.10 | ug/l | | | | | | | |
| Diazinon | ND | 0.10 | ug/l | | | | | | | |
| Dimethoate | ND | 0.20 | ug/l | | | | | | | |
| Diphenamid | ND | 0.10 | ug/l | | | | | | | |
| Disulfoton | ND | 0.10 | ug/l | | | | | | | |
| EPTC | ND | 0.10 | ug/l | | | | | | | |
| Metolachlor | ND | 0.10 | ug/l | | | | | | | |
| Metribuzin | ND | 0.10 | ug/l | | | | | | | |
| Molinate | ND | 0.10 | ug/l | | | | | | | |
| Prometon | ND | 0.10 | ug/l | | | | | | | |
| Prometryn | ND | 0.10 | ug/l | | | | | | | |
| Simazine | ND | 0.10 | ug/l | | | | | | | |
| Terbacil | ND | 2.0 | ug/l | | | | | | | |
| Thiobencarb | ND | 0.10 | ug/l | | | | | | | |
| Trithion | ND | 0.10 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,3-Dimethyl-2-nitrobenzene | 4.97 | | ug/l | 5.00 | | 99 | 70-130 | | | |
| Perylene-d12 | 4.14 | | ug/l | 5.00 | | 83 | 50-120 | | | |
| Triphenyl phosphate | 4.64 | | ug/l | 5.00 | | 93 | 70-130 | | | |
| LCS (W0G0136-BS1) | | | | Prepared: 07/06/20 Analyzed: 07/22/20 | | | | | | |
| Alachlor | 5.92 | 0.10 | ug/l | 5.00 | | 118 | 70-130 | | | |
| Atrazine | 5.82 | 0.10 | ug/l | 5.00 | | 116 | 70-130 | | | |
| Benzo (a) pyrene | 4.40 | 0.10 | ug/l | 5.00 | | 88 | 60-130 | | | |
| Bis(2-ethylhexyl)adipate | 5.17 | 5.0 | ug/l | 5.00 | | 103 | 70-130 | | | |
| Bis(2-ethylhexyl)phthalate | 5.10 | 3.0 | ug/l | 5.00 | | 102 | 70-130 | | | |
| Bromacil | 5.02 | 0.50 | ug/l | 5.00 | | 100 | 70-130 | | | |
| Butachlor | 5.19 | 0.10 | ug/l | 5.00 | | 104 | 70-130 | | | |
| Captan | 5.49 | 1.0 | ug/l | 5.00 | | 110 | 70-130 | | | |
| Chlorpropham | 5.60 | 0.10 | ug/l | 5.00 | | 112 | 70-130 | | | |
| Cyanazine | 5.26 | 0.10 | ug/l | 5.00 | | 105 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Semivolatile Organic Compounds by GC/MS (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|---------------------------|-------|--|--|------|--------|-----|-----------|-----------|
| Batch: W0G0136 - EPA 525.2 (Continued) | | | | | | | | | | |
| LCS (W0G0136-BS1) | | | | | | | | | | |
| | | | | Prepared: 07/06/20 Analyzed: 07/22/20 | | | | | | |
| Diazinon | 4.60 | 0.10 | ug/l | 5.00 | | 92 | 50-120 | | | |
| Dimethoate | 4.48 | 0.20 | ug/l | 5.00 | | 90 | 50-120 | | | |
| Diphenamid | 5.83 | 0.10 | ug/l | 5.00 | | 117 | 70-130 | | | |
| Disulfoton | 3.88 | 0.10 | ug/l | 5.00 | | 78 | 50-120 | | | |
| EPTC | 5.63 | 0.10 | ug/l | 5.00 | | 113 | 70-130 | | | |
| Metolachlor | 5.54 | 0.10 | ug/l | 5.00 | | 111 | 60-130 | | | |
| Metribuzin | 4.75 | 0.10 | ug/l | 5.00 | | 95 | 50-120 | | | |
| Molinate | 5.50 | 0.10 | ug/l | 5.00 | | 110 | 70-130 | | | |
| Prometon | 2.09 | 0.10 | ug/l | 5.00 | | 42 | 15-120 | | | |
| Prometryn | 3.90 | 0.10 | ug/l | 5.00 | | 78 | 30-120 | | | |
| Simazine | 5.12 | 0.10 | ug/l | 5.00 | | 102 | 60-130 | | | |
| Terbacil | 5.77 | 2.0 | ug/l | 5.00 | | 115 | 70-130 | | | |
| Thiobencarb | 5.51 | 0.10 | ug/l | 5.00 | | 110 | 70-130 | | | |
| Trithion | 5.31 | 0.10 | ug/l | 5.00 | | 106 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,3-Dimethyl-2-nitrobenzene | 4.91 | | ug/l | 5.00 | | 98 | 70-130 | | | |
| Perylene-d12 | 4.83 | | ug/l | 5.00 | | 97 | 50-120 | | | |
| Triphenyl phosphate | 5.49 | | ug/l | 5.00 | | 110 | 70-130 | | | |
| Matrix Spike (W0G0136-MS1) | | | | | | | | | | |
| | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/22/20 | | | | | |
| Alachlor | 5.94 | 0.10 | ug/l | 5.00 | ND | 119 | 70-130 | | | |
| Atrazine | 6.10 | 0.10 | ug/l | 5.00 | ND | 122 | 70-130 | | | |
| Benzo (a) pyrene | 4.62 | 0.10 | ug/l | 5.00 | ND | 92 | 60-130 | | | |
| Bis(2-ethylhexyl)adipate | 5.30 | 5.0 | ug/l | 5.00 | ND | 106 | 70-130 | | | |
| Bis(2-ethylhexyl)phthalate | 5.15 | 3.0 | ug/l | 5.00 | ND | 103 | 70-130 | | | |
| Bromacil | 5.23 | 0.50 | ug/l | 5.00 | ND | 105 | 70-130 | | | |
| Butachlor | 5.40 | 0.10 | ug/l | 5.00 | ND | 108 | 70-130 | | | |
| Captan | 5.66 | 1.0 | ug/l | 5.00 | ND | 113 | 70-130 | | | |
| Chlorpropham | 6.03 | 0.10 | ug/l | 5.00 | ND | 121 | 70-130 | | | |
| Cyanazine | 5.38 | 0.10 | ug/l | 5.00 | ND | 108 | 70-130 | | | |
| Diazinon | 4.82 | 0.10 | ug/l | 5.00 | ND | 96 | 50-120 | | | |
| Dimethoate | 5.62 | 0.20 | ug/l | 5.00 | ND | 112 | 50-120 | | | |
| Diphenamid | 5.80 | 0.10 | ug/l | 5.00 | ND | 116 | 70-130 | | | |
| Disulfoton | 4.34 | 0.10 | ug/l | 5.00 | ND | 87 | 50-120 | | | |
| EPTC | 5.62 | 0.10 | ug/l | 5.00 | ND | 112 | 70-130 | | | |
| Metolachlor | 5.62 | 0.10 | ug/l | 5.00 | ND | 112 | 60-130 | | | |
| Metribuzin | 5.16 | 0.10 | ug/l | 5.00 | ND | 103 | 50-120 | | | |
| Molinate | 5.62 | 0.10 | ug/l | 5.00 | ND | 112 | 70-130 | | | |
| Prometon | 3.03 | 0.10 | ug/l | 5.00 | ND | 61 | 15-120 | | | |
| Prometryn | 4.19 | 0.10 | ug/l | 5.00 | ND | 84 | 30-120 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59


Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Semivolatile Organic Compounds by GC/MS (Continued)

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|---|--------|------|---------------------------|-------------|---------------|--|--------|-----|-----------|-----------|
| Batch: W0G0136 - EPA 525.2 (Continued) | | | | | | | | | | |
| Matrix Spike (W0G0136-MS1) | | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/22/20 | | | | |
| Simazine | 5.32 | 0.10 | ug/l | 5.00 | ND | 106 | 60-130 | | | |
| Terbacil | 6.15 | 2.0 | ug/l | 5.00 | ND | 123 | 70-130 | | | |
| Thiobencarb | 5.57 | 0.10 | ug/l | 5.00 | ND | 111 | 70-130 | | | |
| Trithion | 5.36 | 0.10 | ug/l | 5.00 | ND | 107 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,3-Dimethyl-2-nitrobenzene | 5.09 | | ug/l | 5.00 | | 102 | 70-130 | | | |
| Perylene-d12 | 4.75 | | ug/l | 5.00 | | 95 | 50-120 | | | |
| Triphenyl phosphate | 5.49 | | ug/l | 5.00 | | 110 | 70-130 | | | |
| Matrix Spike Dup (W0G0136-MSD1) | | | Source: 0G01005-01 | | | Prepared: 07/06/20 Analyzed: 07/22/20 | | | | |
| Alachlor | 5.95 | 0.10 | ug/l | 5.00 | ND | 119 | 70-130 | 0.1 | 30 | |
| Atrazine | 5.65 | 0.10 | ug/l | 5.00 | ND | 113 | 70-130 | 8 | 30 | |
| Benzo (a) pyrene | 4.55 | 0.10 | ug/l | 5.00 | ND | 91 | 60-130 | 1 | 30 | |
| Bis(2-ethylhexyl)adipate | 5.29 | 5.0 | ug/l | 5.00 | ND | 106 | 70-130 | 0.1 | 30 | |
| Bis(2-ethylhexyl)phthalate | 5.17 | 3.0 | ug/l | 5.00 | ND | 103 | 70-130 | 0.4 | 30 | |
| Bromacil | 5.47 | 0.50 | ug/l | 5.00 | ND | 109 | 70-130 | 5 | 30 | |
| Butachlor | 5.42 | 0.10 | ug/l | 5.00 | ND | 108 | 70-130 | 0.4 | 30 | |
| Captan | 5.65 | 1.0 | ug/l | 5.00 | ND | 113 | 70-130 | 0.1 | 30 | |
| Chlorpropham | 5.78 | 0.10 | ug/l | 5.00 | ND | 116 | 70-130 | 4 | 30 | |
| Cyanazine | 5.27 | 0.10 | ug/l | 5.00 | ND | 105 | 70-130 | 2 | 30 | |
| Diazinon | 4.91 | 0.10 | ug/l | 5.00 | ND | 98 | 50-120 | 2 | 30 | |
| Dimethoate | 5.00 | 0.20 | ug/l | 5.00 | ND | 100 | 50-120 | 12 | 30 | |
| Diphenamid | 5.76 | 0.10 | ug/l | 5.00 | ND | 115 | 70-130 | 0.8 | 30 | |
| Disulfoton | 4.24 | 0.10 | ug/l | 5.00 | ND | 85 | 50-120 | 2 | 30 | |
| EPTC | 5.63 | 0.10 | ug/l | 5.00 | ND | 113 | 70-130 | 0.1 | 30 | |
| Metolachlor | 5.69 | 0.10 | ug/l | 5.00 | ND | 114 | 60-130 | 1 | 30 | |
| Metribuzin | 5.09 | 0.10 | ug/l | 5.00 | ND | 102 | 50-120 | 1 | 30 | |
| Molinate | 5.53 | 0.10 | ug/l | 5.00 | ND | 111 | 70-130 | 2 | 30 | |
| Prometon | 2.85 | 0.10 | ug/l | 5.00 | ND | 57 | 15-120 | 6 | 30 | |
| Prometryn | 4.38 | 0.10 | ug/l | 5.00 | ND | 88 | 30-120 | 4 | 30 | |
| Simazine | 5.29 | 0.10 | ug/l | 5.00 | ND | 106 | 60-130 | 0.5 | 30 | |
| Terbacil | 5.66 | 2.0 | ug/l | 5.00 | ND | 113 | 70-130 | 8 | 30 | |
| Thiobencarb | 5.49 | 0.10 | ug/l | 5.00 | ND | 110 | 70-130 | 1 | 30 | |
| Trithion | 5.52 | 0.10 | ug/l | 5.00 | ND | 110 | 70-130 | 3 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,3-Dimethyl-2-nitrobenzene | 4.95 | | ug/l | 5.00 | | 99 | 70-130 | | | |
| Perylene-d12 | 4.79 | | ug/l | 5.00 | | 96 | 50-120 | | | |
| Triphenyl phosphate | 5.59 | | ug/l | 5.00 | | 112 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Semivolatiles Organics - Low Level by Tandem GC/MS/MS


| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|-----------------------------------|--------|------|-------|--|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0914 - EPA 1613B | | | | | | | | | | |
| Blank (W0G0914-BLK1) | | | | | | | | | | |
| 2,3,7,8-TCDD (Dioxin) | ND | 5.00 | pg/l | | | | | | | |
| | | | | Prepared: 07/17/20 Analyzed: 07/23/20 | | | | | | |
| LCS (W0G0914-BS1) | | | | | | | | | | |
| 2,3,7,8-TCDD (Dioxin) | 4.54 | 5.00 | pg/l | 5.00 | | 91 | 50-148 | | | |
| | | | | Prepared: 07/17/20 Analyzed: 07/23/20 | | | | | | |
| LCS Dup (W0G0914-BSD1) | | | | | | | | | | |
| 2,3,7,8-TCDD (Dioxin) | 4.89 | 5.00 | pg/l | 5.00 | | 98 | 50-148 | 7 | 20 | |

Quality Control Results

(Continued)

Volatile Organic Compounds by P&T and GC/MS

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|-----------------------------------|--------|-----|-------|-------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0128 - EPA 524.2 | | | | | | | | | | |
| Blank (W0G0128-BLK1) | | | | | | | | | | |
| Acrylonitrile | ND | 2.0 | ug/l | | | | | | | |
| Epichlorohydrin | ND | 20 | ug/l | | | | | | | |
| Tert-butyl alcohol | ND | 2.0 | ug/l | | | | | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,2-Dichlorobenzene-d4 | 9.78 | | ug/l | 10.0 | | 98 | 70-130 | | | |
| 1,2-Dichlorobenzene-d4 | 9.78 | | ug/l | 10.0 | | 98 | 70-130 | | | |
| 4-Bromofluorobenzene | 9.87 | | ug/l | 10.0 | | 99 | 70-130 | | | |
| 4-Bromofluorobenzene | 9.87 | | ug/l | 10.0 | | 99 | 70-130 | | | |
| LCS (W0G0128-BS1) | | | | | | | | | | |
| Epichlorohydrin | 52.1 | 20 | ug/l | 50.0 | | 104 | 70-130 | | | |
| Tert-butyl alcohol | 23.0 | 2.0 | ug/l | 20.0 | | 115 | 70-130 | | | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,2-Dichlorobenzene-d4 | 10.2 | | ug/l | 10.0 | | 102 | 70-130 | | | |
| 1,2-Dichlorobenzene-d4 | 10.2 | | ug/l | 10.0 | | 102 | 70-130 | | | |
| 4-Bromofluorobenzene | 10.3 | | ug/l | 10.0 | | 103 | 70-130 | | | |
| 4-Bromofluorobenzene | 10.3 | | ug/l | 10.0 | | 103 | 70-130 | | | |
| LCS Dup (W0G0128-BSD1) | | | | | | | | | | |
| Epichlorohydrin | 56.3 | 20 | ug/l | 50.0 | | 113 | 70-130 | 8 | 30 | |
| Tert-butyl alcohol | 21.8 | 2.0 | ug/l | 20.0 | | 109 | 70-130 | 5 | 30 | |
| <i>Surrogate(s)</i> | | | | | | | | | | |
| 1,2-Dichlorobenzene-d4 | 10.0 | | ug/l | 10.0 | | 100 | 70-130 | | | |
| 1,2-Dichlorobenzene-d4 | 10.0 | | ug/l | 10.0 | | 100 | 70-130 | | | |
| 4-Bromofluorobenzene | 10.1 | | ug/l | 10.0 | | 101 | 70-130 | | | |
| 4-Bromofluorobenzene | 10.1 | | ug/l | 10.0 | | 101 | 70-130 | | | |



WECK LABORATORIES, INC.

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Certificate of Analysis

FINAL REPORT

Project Number: Pure Water Testing

Reported:

08/21/2020 15:59

Project Manager: Frank Almaguer

Quality Control Results

(Continued)

Volatile Organics by P&T and GC/MS

| Analyte | Result | MRL | Units | Spike Level | Source Result | %REC | Limits | RPD | RPD Limit | Qualifier |
|--|--------|-------|-------|-------------|---------------|------|--------|-----|-----------|-----------|
| Batch: W0G0107 - EPA 524.3 | | | | | | | | | | |
| Blank (W0G0107-BLK1) | | | | | | | | | | |
| Prepared: 07/02/20 Analyzed: 07/03/20 | | | | | | | | | | |
| 1,2-Dibromo-3-chloropropane | ND | 0.010 | ug/l | | | | | | | |
| 1,2-Dibromoethane (EDB) | ND | 0.020 | ug/l | | | | | | | |
| LCS (W0G0107-BS1) | | | | | | | | | | |
| Prepared: 07/02/20 Analyzed: 07/03/20 | | | | | | | | | | |
| 1,2-Dibromo-3-chloropropane | 0.0513 | 0.010 | ug/l | 0.0500 | | 103 | 70-130 | | | |
| 1,2-Dibromoethane (EDB) | 0.0521 | 0.020 | ug/l | 0.0500 | | 104 | 70-130 | | | |
| LCS Dup (W0G0107-BSD1) | | | | | | | | | | |
| Prepared: 07/02/20 Analyzed: 07/03/20 | | | | | | | | | | |
| 1,2-Dibromo-3-chloropropane | 0.0471 | 0.010 | ug/l | 0.0500 | | 94 | 70-130 | 9 | 30 | |
| 1,2-Dibromoethane (EDB) | 0.0498 | 0.020 | ug/l | 0.0500 | | 100 | 70-130 | 5 | 30 | |

Las Virgenes Municipal Water District
4232 Las Virgenes Road
Calabasas, CA 91302

Project Number: Pure Water Testing

Reported:
08/21/2020 15:59

Project Manager: Frank Almaguer

Notes and Definitions

| Item | Definition |
|--------|---|
| * | The recommended holding time for this analysis is only 15 minutes. The sample was analyzed as soon as it was possible but it was received and analyzed past holding time. |
| A-01 | filtered acidified to pH<2 in lab 07/06/20 9:30am jlp |
| A-01a | MRL was raised because of low sensitivity. |
| A-01b | The analyte failed RPD criteria due to high recovery in the BS & was reported based on the BSD passing recovery criteria. |
| A-01c | The analyte failed RPD criteria due to low recovery in the BS & was reported based on the BSD passing recovery criteria. |
| B | Blank contamination. The analyte was found in the associated blank as well as in the sample. |
| B-06 | This analyte was found in the method blank, which was possibly contaminated during sample preparation. The batch was accepted since this analyte was either not detected or more than 10 times of the blank value for all the samples in the batch. |
| B-07 | This analyte was found in the method blank at levels above the MDL but below the reporting limit. |
| BS-04 | The recovery of this analyte in LCS or LCSD was outside control limit. Sample was accepted based on the remaining LCS, LCSD or LCS-LL. |
| BS-H | The recovery of this analyte in the BS/LCS was over the control limit. Sample result is suspect. |
| BS-L | The recovery of this analyte in the BS/LCS was below the control limit. Sample result is suspect. |
| E-01 | The concentration indicated for this analyte is an estimated value above the calibration range. |
| I-05 | Low internal standard recovery possibly due to matrix interference. The result is suspect. |
| M-05 | Due to the nature of matrix interferences, sample was diluted prior to analysis. The MDL and MRL were raised due to the dilution. |
| MS-01 | The spike recovery for this QC sample is outside of established control limits possibly due to sample matrix interference. |
| O-20 | As per vial label, this sample was received with HCl preservation, however sample pH was found to be >2 after VOC analysis possibly due to matrix effect or loss of acid during sampling. |
| Q-08 | High bias in the QC sample does not affect sample result since analyte was not detected or below the reporting limit. |
| Q-12 | The RPD result exceeded the QC control limits; however, both percent recoveries were acceptable. Sample results for the QC batch were accepted based on the percent recoveries and/or other acceptable QC data. |
| QC-2 | This QC sample was reanalyzed to complement samples that require re-analysis on different date. See analysis date. |
| R-01 | The Reporting Limit for this analyte has been raised to account for matrix interference. |
| S-11 | Surrogate recovery outside of control limits. The data was accepted based on valid recovery of the remaining surrogate. |
| S-GC | Surrogate recovery outside of control limits due to a possible matrix effect. The data was accepted based on valid recovery of the remaining surrogate. |
| %REC | Percent Recovery |
| Dil | Dilution |
| dry | Sample results reported on a dry weight basis |
| MDA | Minimum Detectable Activity |
| MRL | The minimum levels, concentrations, or quantities of a target variable (e.g., target analyte) that can be reported with a specified degree of confidence. The MRL is also known as Limit of Quantitation (LOQ) |
| ND | A result of ND for odor corresponds to No Odor Observed |
| ND | NOT DETECTED at or above the Method Reporting Limit (MRL). If Method Detection Limit (MDL) is reported, then ND means not detected at or above the MDL. |
| RPD | Relative Percent Difference |
| Source | Sample that was matrix spiked or duplicated. |

Any remaining sample(s) will be disposed of one month from the final report date unless other arrangements are made in advance.

All results are expressed on wet weight basis unless otherwise specified.

All samples collected by Weck Laboratories have been sampled in accordance to laboratory SOP Number MIS002.



LA Testing

520 Mission Street South Pasadena, CA 91030
 Phone/Fax: (323) 254-9960 / (323) 254-9982
<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order ID: 322011638
 Customer ID: 32WECK62
 Customer PO:
 Project ID:

Attn: Regina Giancola
 Weck Laboratories, Inc.
 14859 East Clark Avenue
 City of Industry, CA 91745-1396

Phone: (626) 336-2139
 Fax: (626) 336-2634
 Received: 07/01/2020
 Analyzed: 07/10/2020

Proj: 0F30024

Test Report: Determination of Asbestos Structures >10µm in Drinking Water Performed by the 100.2 Method (EPA 600/R-94/134)

| Sample ID Client / EMSL | Sample Filtration Date/Time | Original Sample Vol. Filtered (ml) | Effective Filter Area (mm ²) | Area Analyzed (mm ²) | ASBESTOS | | | | |
|--|-----------------------------------|---|---|--|-------------------|--------------------|---------------------------|---|----------------------|
| | | | | | Asbestos Types | Fibers Detected | Analytical Sensitivity | Concentration MFL (million fibers per liter) | Confidence Limits |
| 0F30024-01/Finished Water 322011638-0001 | 7/1/2020 11:45 AM | 100 | 1288 | 0.0640 | None Detected | ND | 0.20 | <0.20 | 0.00 - 0.74 |
| Collection Date/Time: 06/30/2020 10:00 AM | | | | | | | | | |

Analyst(s)
 Kyeong Corbin (1)

Jerry Drapala Ph.D, Laboratory Manager
 or Other Approved Signatory

Any questions please contact Jerry Drapala.

Initial report from: 07/10/2020 13:20:06

Sample collection and containers provided by the client, acceptable bottle blank level is defined as ≤0.01MFL>10µm. ND=None Detected. This report relates only to those items tested. This report may not be reproduced, except in full, without written permission by LA Testing. Samples received in good condition unless otherwise noted.

Samples analyzed by LA Testing South Pasadena, CA CA ELAP 2283

July 24, 2020

Regina Giancola
Weck Laboratories, Inc.
14859 East Clark Avenue
City of Industry, CA 91745

RE: Project: 0F30024
Pace Project No.: 30370940

Dear Regina Giancola:

Enclosed are the analytical results for sample(s) received by the laboratory on July 06, 2020. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Greensburg

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Jacquelyn Collins
jacquelyn.collins@pacelabs.com
(724)850-5612
Project Manager

Enclosures



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: 0F30024
Pace Project No.: 30370940

Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601

ANAB DOD-ELAP Rad Accreditation #: L2417

Alabama Certification #: 41590

Arizona Certification #: AZ0734

Arkansas Certification

California Certification #: 04222CA

Colorado Certification #: PA01547

Connecticut Certification #: PH-0694

Delaware Certification

EPA Region 4 DW Rad

Florida/TNI Certification #: E87683

Georgia Certification #: C040

Florida: Cert E871149 SEKS WET

Guam Certification

Hawaii Certification

Idaho Certification

Illinois Certification

Indiana Certification

Iowa Certification #: 391

Kansas/TNI Certification #: E-10358

Kentucky Certification #: KY90133

KY WW Permit #: KY0098221

KY WW Permit #: KY0000221

Louisiana DHH/TNI Certification #: LA180012

Louisiana DEQ/TNI Certification #: 4086

Maine Certification #: 2017020

Maryland Certification #: 308

Massachusetts Certification #: M-PA1457

Michigan/PADEP Certification #: 9991

Missouri Certification #: 235

Montana Certification #: Cert0082

Nebraska Certification #: NE-OS-29-14

Nevada Certification #: PA014572018-1

New Hampshire/TNI Certification #: 297617

New Jersey/TNI Certification #: PA051

New Mexico Certification #: PA01457

New York/TNI Certification #: 10888

North Carolina Certification #: 42706

North Dakota Certification #: R-190

Ohio EPA Rad Approval: #41249

Oregon/TNI Certification #: PA200002-010

Pennsylvania/TNI Certification #: 65-00282

Puerto Rico Certification #: PA01457

Rhode Island Certification #: 65-00282

South Dakota Certification

Tennessee Certification #: 02867

Texas/TNI Certification #: T104704188-17-3

Utah/TNI Certification #: PA014572017-9

USDA Soil Permit #: P330-17-00091

Vermont Dept. of Health: ID# VT-0282

Virgin Island/PADEP Certification

Virginia/VELAP Certification #: 9526

Washington Certification #: C868

West Virginia DEP Certification #: 143

West Virginia DHHR Certification #: 9964C

Wisconsin Approve List for Rad

Wyoming Certification #: 8TMS-L

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE SUMMARY

Project: 0F30024
Pace Project No.: 30370940

| Lab ID | Sample ID | Matrix | Date Collected | Date Received |
|---------------|------------------|----------------|-----------------------|----------------------|
| 30370940001 | 0F30024-01 | Drinking Water | 06/30/20 10:00 | 07/06/20 09:40 |

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: 0F30024
Pace Project No.: 30370940

| Lab ID | Sample ID | Method | Analysts | Analytes Reported | Laboratory |
|-------------|------------|-----------|----------|-------------------|------------|
| 30370940001 | 0F30024-01 | EPA 903.1 | MK1 | 1 | PASI-PA |
| | | EPA 904.0 | VAL | 1 | PASI-PA |
| | | EPA 905.0 | JJY | 1 | PASI-PA |
| | | EPA 906.0 | CLA | 1 | PASI-PA |

PASI-PA = Pace Analytical Services - Greensburg

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 0F30024
Pace Project No.: 30370940

Sample: 0F30024-01 **Lab ID: 30370940001** Collected: 06/30/20 10:00 Received: 07/06/20 09:40 Matrix: Drinking Water
PWS: Site ID: Sample Type:

| Parameters | Method | Act ± Unc (MDC) Carr Trac | Units | Analyzed | CAS No. | Qual |
|--------------|---------------------------------------|---|-------|----------------|------------|------|
| | Pace Analytical Services - Greensburg | | | | | |
| Radium-226 | EPA 903.1 | 0.508 ± 0.431 (0.590) C:NA T:85% | pCi/L | 07/17/20 15:47 | 13982-63-3 | |
| | Pace Analytical Services - Greensburg | | | | | |
| Radium-228 | EPA 904.0 | 0.519 ± 0.438 (0.903) C:71% T:81% | pCi/L | 07/16/20 14:22 | 15262-20-1 | |
| | Pace Analytical Services - Greensburg | | | | | |
| Strontium-90 | EPA 905.0 | -0.203 ± 0.377 (0.769) C:102% T:NA | pCi/L | 07/20/20 19:04 | 10098-97-2 | |
| | Pace Analytical Services - Greensburg | | | | | |
| Tritium | EPA 906.0 | -77.3 ± 127 (232) C:NA T:NA | pCi/L | 07/11/20 19:06 | 10028-17-8 | |

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 0F30024
Pace Project No.: 30370940

| | |
|----------------------------|---|
| QC Batch: 404025 | Analysis Method: EPA 904.0 |
| QC Batch Method: EPA 904.0 | Analysis Description: 904.0 Radium 228 |
| | Laboratory: Pace Analytical Services - Greensburg |

Associated Lab Samples: 30370940001

METHOD BLANK: 1955145 Matrix: Water

Associated Lab Samples: 30370940001

| Parameter | Act ± Unc (MDC) Carr Trac | Units | Analyzed | Qualifiers |
|------------|-----------------------------------|-------|----------------|------------|
| Radium-228 | 0.259 ± 0.328 (0.695) C:75% T:88% | pCi/L | 07/16/20 14:22 | |

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 0F30024
Pace Project No.: 30370940

| | |
|----------------------------|---|
| QC Batch: 404450 | Analysis Method: EPA 906.0 |
| QC Batch Method: EPA 906.0 | Analysis Description: 906.0 Tritium |
| | Laboratory: Pace Analytical Services - Greensburg |

Associated Lab Samples: 30370940001

METHOD BLANK: 1957302 Matrix: Water

Associated Lab Samples: 30370940001

| Parameter | Act ± Unc (MDC) Carr Trac | Units | Analyzed | Qualifiers |
|-----------|-----------------------------|-------|----------------|------------|
| Tritium | -2.49 ± 131 (232) C:NA T:NA | pCi/L | 07/11/20 11:57 | |

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 0F30024
Pace Project No.: 30370940

| | |
|----------------------------|---|
| QC Batch: 404026 | Analysis Method: EPA 903.1 |
| QC Batch Method: EPA 903.1 | Analysis Description: 903.1 Radium-226 |
| | Laboratory: Pace Analytical Services - Greensburg |

Associated Lab Samples: 30370940001

METHOD BLANK: 1955146 Matrix: Water

Associated Lab Samples: 30370940001

| Parameter | Act ± Unc (MDC) Carr Trac | Units | Analyzed | Qualifiers |
|------------|------------------------------------|-------|----------------|------------|
| Radium-226 | -0.0508 ± 0.386 (0.806) C:NA T:80% | pCi/L | 07/17/20 15:23 | |

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 0F30024
Pace Project No.: 30370940

| | |
|----------------------------|---|
| QC Batch: 405208 | Analysis Method: EPA 905.0 |
| QC Batch Method: EPA 905.0 | Analysis Description: 905.0 Strontium 89/90 |
| | Laboratory: Pace Analytical Services - Greensburg |

Associated Lab Samples: 30370940001

METHOD BLANK: 1960906 Matrix: Water

Associated Lab Samples: 30370940001

| Parameter | Act ± Unc (MDC) Carr Trac | Units | Analyzed | Qualifiers |
|--------------|-------------------------------------|-------|----------------|------------|
| Strontium-90 | -0.0910 ± 0.106 (0.222) C:104% T:NA | pCi/L | 07/20/20 19:08 | |

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: 0F30024
Pace Project No.: 30370940

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Act - Activity

Unc - Uncertainty: For Safe Drinking Water Act (SDWA) analyses, the reported Unc. is the calculated Count Uncertainty (95% confidence interval) using a coverage factor of 1.96. For all other matrices (non-SDWA), the reported Unc. is the calculated Expanded Uncertainty (aka Combined Standard Uncertainty, CSU), reported at the 95% confidence interval using a coverage factor of 1.96.

Gamma Spec: The Unc. reported for all gamma-spectroscopy analyses (EPA 901.1), is the calculated Expanded Uncertainty (CSU) at the 95.4% confidence interval, using a coverage factor of 2.0.

(MDC) - Minimum Detectable Concentration

Trac - Tracer Recovery (%)

Carr - Carrier Recovery (%)

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



WECK LABORATORIES, INC.

Subcontract Order

Subcontracted Laboratory:

Pace Analytical Services - Greensburg PA
1638 Roseytown Road Ste 2
Greensburg, PA 15601
Phone: (724) 850-5600
Fax: (724) 850-5601

Turn Around Time: Normal unless noted in comments

Project Manager: Regina M. Giancola

Project Name: Pure Water Testing

Project Number: Pure Water Testing

Sampler Employed by: _____

Work Order: 0F30024

| Analysis | Expires | Comments |
|---|------------------|---|
| Sample ID: 0F30024-01/Finished Water | | Sampled: 06/30/2020 10:00 |
| Sample comment: | | Matrix: Water Sampled By: ATS |
| Tritium (EPA 906.0) - sub | 12/27/2020 10:00 | 001 |
| Strontium-90 (EPA 905.0) - sub | 12/27/2020 10:00 | |
| Radium-228 (EPA 904.0) - sub | 12/27/2020 10:00 | |
| Radium-226 (EPA 903.1) - sub | 12/27/2020 10:00 | |
| <i>Containers Supplied:</i> | | |

WO# : 30370940



my
Remarks / Special Comments:

Sample Condition

Temperature: _____

Preserved: Yes / No

Evidence Seal Intact: Yes / No

Container Attacked: Yes / No

Preserved at Lab: Yes / No

Thounglan 7/6/20 13:30 *Fedex*

Relinquished By _____ Date / Time _____ Received By _____ Date / Time _____

Heather Gross 7-6-20 9:40

Relinquished By _____ Date / Time _____ Received By _____ Date / Time _____

Pittsburgh Lab Sample Condition Upon Receipt

30370940



Client Name: Weck

Project # _____

Courier: Fed Ex UPS USPS Client Commercial Pace Other _____

Tracking #: 7708 5439 1206

| | |
|------------|------------|
| Label | <u>BLM</u> |
| LIMS Login | <u>BLM</u> |

Custody Seal on Cooler/Box Present: yes no Seals Intact: yes no

Thermometer Used N/A Type of Ice: Wet Blue None

Cooler Temperature Observed Temp _____ °C Correction Factor: _____ °C Final Temp: _____ °C
Temp should be above freezing to 6°C

| Comments: | pH paper Lot# | | | Date and Initials of person examining contents: |
|--|-------------------------------------|--------------------------|--------------------------|--|
| | Yes | No | N/A | |
| Chain of Custody Present: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 1. <u>10D5191</u> |
| Chain of Custody Filled Out: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 2. |
| Chain of Custody Relinquished: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 3. |
| Sampler Name & Signature on COC: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 4. |
| Sample Labels match COC: -Includes date/time/ID | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 5. <u>no time on samples</u> |
| Samples Arrived within Hold Time: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 6. |
| Short Hold Time Analysis (<72hr remaining): | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 7. |
| Rush Turn Around Time Requested: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 8. |
| Sufficient Volume: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 9. |
| Correct Containers Used: -Pace Containers Used: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 10. |
| Containers Intact: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 11. |
| Orthophosphate field filtered | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12. |
| Hex Cr Aqueous sample field filtered | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 13. |
| Organic Samples checked for dechlorination: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 14. |
| Filtered volume received for Dissolved tests | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 15. |
| All containers have been checked for preservation. exceptions: VOA, coliform, TOC, O&G, Phenolics, Radon, Non-aqueous matrix | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 16. <u>pH 2</u> |
| All containers meet method preservation requirements. | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Initial when completed: <u>He</u> Date/time of preservation: _____ |
| | | | | Lot # of added preservative: _____ |
| Headspace in VOA Vials (>6mm): | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 17. |
| Trip Blank Present: | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 18. |
| Trip Blank Custody Seals Present | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | |
| Rad Samples Screened < 0.5 mrem/hr | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Initial when completed: <u>He</u> Date: <u>7-10-20</u> |

Client Notification/ Resolution:

Person Contacted: _____ Date/Time: _____ Contacted By: _____

Comments/ Resolution: _____

A check in this box indicates that additional information has been stored in ereports.

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers)
*PM review is documented electronically in LIMS. When the Project Manager closes the SRF Review schedule in LIMS. The review is in the Status section of the Workorder Edit Screen.

Appendix C

PRELIMINARY RO CONCENTRATE NPDES COMPLIANCE ANALYSIS

PRELIMINARY RO CONCENTRATE NPDES COMPLIANCE ANALYSIS

Reverse osmosis (RO) concentrate presents potential challenges to National Pollutant Discharge Elimination System (NPDES) discharge compliance to a future brine line disposal. This analysis, which is preliminary and must be expanded by the Las Virgenes - Triunfo Joint Powers Authority (JPA's) program management team, is intended to define important parameters to measure in RO concentrate.

C.1 Concentrate Chemical Constituent and Toxicity Analysis

C.1.1 Regulatory Requirements

This test plan assumes that RO concentrate will ultimately need to comply with the Calleguas Municipal Water District (CMWD) Salinity Management Pipeline (SMP) NPDES permit water quality requirements for disposal, which requires both chemical constituent compliance and toxicity compliance. With specific water quality requirements indicated in Table 4 of Order R4-2014-0033 NPDES No. CA0064521 (Appendix E within this report), discharges into the SMP need to comply with Discharge Point 001 (Initial Dilution Ratio = 72:1) water quality requirements with compliance measured at Monitoring Location EFF-001. If the ultimate brine disposal location changes (i.e., to the City of Thousand Oaks Hill Canyon Wastewater Treatment Plant instead of the CMWD SMP) or the dilution ratio changes, this analysis will need to be revised to take into account the alternate disposal location NPDES permit and/or dilution ratio.

In addition to NPDES compliance, ocean discharges need to comply with the State Water Resources Control Board (SWRCB) Water Quality Control Plan for the Ocean Waters of California (Ocean Plan). The Ocean Plan is reviewed every three years to guarantee that its Water Quality Objectives (WQOs) are adequate to prevent degradation of marine species and to protect public health. The most recent amendment to the Ocean Plan (Resolution 2015-0033) was adopted on May 6, 2015 and was put into effect January 28, 2016. If a conflict exists between the Ocean Plan WQOs and the NPDES Permit effluent limits, the more stringent provision shall apply. Effluent limits are determined using the following equation:

$$C_e = C_o + D_m \times (C_o - C_s)$$

Where:

C_e = effluent concentration limit (micrograms per liter [$\mu\text{g/L}$]).

C_o = concentration (WQO) to be met at the completion of initial dilution ($\mu\text{g/L}$).

C_s = background seawater concentration ($\mu\text{g/L}$), based on Table 6 of the Ocean Plan.

D_m = minimum probable initial dilution expressed as parts seawater per part wastewater, assumed to be a maximum of 75 per the CMWD SMP NPDES permit.

Tables C-1 through C-4 summarize the CMWD SMP NPDES and Ocean Plan permit effluent limits.

C.1.2 RO Concentrate Characterization Data and Calculations

To characterize the RO concentrate from the Demonstration Facility and future AWP, Carollo Engineers, Inc. (Carollo) compiled average and maximum pollutant concentrations from Tapia Water Reclamation Facility (WRF) effluent, based on annual reports (January 2014 through

Table C.1 Comparison of Projected RO Concentrate Pollutant Concentrations with NPDES Permit with Ocean Plan WQO Limits – Technology-Based and Bacteriological

| Parameter | Units | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | Average Monthly NPDES Permit Effluent Limit (mg/L) | 30-Day Average Ocean Plan WQO-Based Effluent Limit (mg/L) |
|---------------------------------|------------|-------|-----------|---|--|--|---|
| Biochemical Oxygen Demand (BOD) | mg/L | 2.0 | SM 5210 B | 3.30 | 21 | 30 | Note ⁽¹⁾ |
| Total Suspended Solids (TSS) | mg/L | 1.0 | SM 2540 D | 2.0 | 13 | 60 | Note ⁽²⁾ |
| Grease and Oil | mg/L | 1.3 | EPA 1664B | NM | Note ⁽³⁾ | 25 | 25 |
| Settleable Solids | mL/L | 0.2 | EPA 160.5 | NM | Note ⁽³⁾ | 1.0 | 1.0 |
| Turbidity | NTU | 0.024 | SM 2130 B | NM | Note ⁽³⁾ | 75 | 75 |
| pH | s.u. | 0 | EPA 150.2 | 7.2 | Note ⁽⁴⁾ | 6.0 to 9.0 | 6.0 to 9.0 |
| Total coliform | MPN/100 mL | 0 | EPA 1604 | NM | Note ⁽⁵⁾ | 1,100 ⁽⁶⁾ | 1,100 ⁽⁶⁾ |
| Fecal coliform | MPN/100 mL | 0 | EPA 1604 | NM | Note ⁽⁵⁾ | 200 ⁽⁶⁾ | 200 ⁽⁶⁾ |
| Enterococcus | MPN/100 mL | 0 | EPA 1600 | NM | Note ⁽⁵⁾ | 100 ⁽⁶⁾ | 100 ⁽⁶⁾ |

Notes:

- (1) Instead of a numerical WQO for BOD, the Ocean Plan’s Chemical Characteristics standards include a provision that dissolved oxygen in the receiving water shall not be depressed more than 10 percent from that which occurs naturally as a result of discharge.
- (2) For suspended solids, the Ocean Plan includes a removal target rather than a TSS effluent limit: dischargers shall, as a 30-day average, remove 75 percent of suspended solids from the influent stream before discharging wastewaters to the ocean.
- (3) Upstream pretreatment processes at Tapia WRF and at the future AWPf will maintain RO concentrate levels below these regulated thresholds.
- (4) pH in RO concentrate will be controlled as necessary at the future AWPf to remain within the acceptable range.
- (5) The future AWPf will disinfect RO concentrate as necessary in order to minimize bacteria levels below regulatory threshold.
- (6) Calculated as a 30-day geometric mean using the result of the five most recent samples.

Table C.2 Comparison of Projected RO Concentrate Pollutant Concentrations with NPDES Permit with Ocean Plan WQO Limits – Protection of Marine Aquatic Life

| Parameter | Units | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | 6-Month Median NPDES Permit Effluent Limit | 6-Month Median Ocean Plan WQO (C _o) | Background Seawater Concentration (C _s) | 6-Month Median Ocean Plan Effluent Limit (C _e) Dm = 72 |
|---|-------|--------|-------------|---|--|---|---|---|--|
| Arsenic | µg/L | 0.074 | EPA 200.8 | 1.8 | 12.0 | 370 | 8 | 3 | 368 |
| Cadmium | µg/L | 0.041 | EPA 200.8 | 0.2 | 1.2 | 73 | 1 | | 73 |
| Chromium VI | µg/L | 0.0048 | EPA 218.6 | 0.2 | 1.4 | 150 | 2 | | 146 |
| Copper | µg/L | 0.13 | EPA 200.8 | 3.5 | 23 | 75 | 3 | 2 | 75 |
| Lead | µg/L | 0.031 | EPA 218.6 | 0.3 | 2 | 150 | 2 | | 146 |
| Mercury | µg/L | 0.017 | EPA 245.1 | 0.3 | 2 | 2.9 | 0.04 | 0.0005 | 2.9 |
| Nickel | µg/L | 0.045 | EPA 200.8 | 3.4 | 22.2 | 370 | 5 | | 365 |
| Selenium | µg/L | 0.14 | EPA 7741A | 0.9 | 5.6 | 1,100 | 15 | | 1,095 |
| Silver | µg/L | 0.062 | EPA 200.8 | 0.8 | 5.1 | 40 | 0.7 | 0.16 | 40 |
| Zinc | µg/L | 0.94 | EPA 200.8 | 37 | 241 | 880 | 20 | 8 | 884 |
| Cyanide | µg/L | 2.7 | EPA 335.4 | 6.4 | 42 | 73 | 1 | | 73 |
| Total Chlorine Residual | µg/L | 2 | SM 4500Cl-G | 1,943 | ND ⁽¹⁾ | 150 | 2 | | 146 |
| Ammonia as N | µg/L | 0.048 | EPA 350.1 | 0.8 | 5.2 | 44,000 | 600 | | 43,800 |
| Phenolic Compounds (non-chlorinated) ⁽²⁾ | µg/L | 4.47 | EPA 625 | 2.24 | 14 | 2,200 | 30 | | 2,190 |
| Chlorinated Phenolics ⁽³⁾ | µg/L | 1.18 | EPA 625 | 0.59 | 3.8 | 73 | 1 | | 73 |
| Endosulfan | µg/L | 0.017 | EPA 608 | 0.0085 | 0.06 | 0.66 | 0.009 | | 0.66 |
| Endrin | µg/L | 0.028 | EPA 608 | 0.01 | 0.09 | 0.15 | 0.002 | | 0.15 |
| HCH ⁽⁴⁾ | µg/L | 0.0095 | EPA 608 | 0.0048 | 0.03 | 0.29 | 0.004 | | 0.29 |
| Radioactivity ⁽⁵⁾ | pCi/L | Varies | EPA 900 | 15 | 100 | Not to exceed limits specified in Title 22 California Code of Regulations (CCR) § 64443 | | | |

Notes:

- (1) Chlorine residual in RO concentrate will be quenched with sodium bisulfite prior to discharge.
- (2) Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
- (3) Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
- (4) HCH is the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
- (5) Title 22 CCR § 64443 specifies Maximum Contaminant Limits (MCLs) for beta/photon emitters, Strontium-90, and Tritium. The 4 millirems/year MCL for beta/photon emitters has an equivalent gross beta particle activity concentration of 4 picocurie/liter (pCi/L). Similarly, Strontium-90 is 8 pCi/L, and C-4 ritium is 20,000 pCi/L. A screening-level of 50 pCi/L gross beta particle activity is used in this characterization to indicate whether further testing for specific radionuclides is deemed necessary.

Table C.3 Comparison of Projected RO Concentrate Pollutant Concentrations with NPDES Permit with Ocean Plan WQO Limits – Protection of Human Health (Non-Carcinogens)

| Parameter | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | 30-Day Average NPDES Permit Effluent Limit (µg/L) | 30-Day Average Ocean Plan WQO-Based Effluent Limit (µg/L) | 30-Day Average Ocean Plan Effluent Limit (C _e) Dm = 72 |
|---------------------------------|-------|----------------------|---|--|---|---|--|
| Acrolein | 2.2 | EPA 624 | 1.1 | 7.1 | 16,000 | 220 | 16,060 |
| Antimony | 0.045 | EPA 200.8 | 0.0225 | 0.1 | 88,000 | 1,200 | 87,600 |
| Bis(2-Chloroethoxy) Methane | 0.25 | EPA 625 | 0.125 | 0.8 | N/A | 4.4 | 321 |
| Bis(2-Chloroisopropyl) Ether | 0.27 | EPA 625 | 0.14 | 0.9 | N/A | 1,200 | 87,600 |
| Chlorobenzene | 0.21 | EPA 624 | 0.11 | 0.7 | 42,000 | 570 | 41,610 |
| Chromium (III) | 0.035 | EPA 218.6, EPA 200.8 | 0.08 | 0.54 | 14,000,000 | 190,000 | 13,870,000 |
| Di-n-Butyl Phthalate | 0.24 | EPA 625 | 0.12 | 0.8 | N/A | 3,500 | 255,500 |
| Dichlorobenzenes ⁽¹⁾ | 1.08 | EPA 625 | 1 | 3.5 | N/A | 5,100 | 372,300 |
| Diethyl Phthalate | 0.15 | EPA 625 | 0.075 | 0.5 | N/A | 33,000 | 2,409,000 |
| Dimethyl Phthalate | 0.18 | EPA 625 | 0.09 | 0.6 | N/A | 820,000 | 59,860,000 |
| 4,6-Dinitro-2-Methylphenol | 1.7 | EPA 625 | 0.85 | 5.52 | N/A | 220 | 16,060 |
| 2,4-Dinitrophenol | 1.6 | EPA 625 | 0.80 | 5.20 | N/A | 4.0 | 292 |
| Ethylbenzene | 0.17 | EPA 624 | 0.09 | 0.55 | 300,000 | 4,100 | 299,300 |
| Fluoranthene | 0.22 | EPA 625 | 0.11 | 0.715 | N/A | 15 | 1,095 |
| Hexachlorocyclopentadiene | 1.5 | EPA 625 | 0.75 | 4.87 | 4,200 | 58 | 4,234 |

| Parameter | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | 30-Day Average NPDES Permit Effluent Limit (µg/L) | 30-Day Average Ocean Plan WQO-Based Effluent Limit (µg/L) | 30-Day Average Ocean Plan Effluent Limit (C _e) Dm = 72 |
|-----------------------|--------|--------------------|---|--|---|---|--|
| Nitrobenzene | 0.36 | EPA 625 | 0.18 | 1.17 | 360 | 4.9 | 358 |
| Thallium | 0.014 | EPA 200.8 | 0.007 | 0.0 | 150 | 2 | 146 |
| Toluene | 0.22 | EPA 624 | 0.11 | 0.71 | 6,200,000 | 85,000 | 6,205,000 |
| Tributyltin | 0.0012 | Krone, et al, 1989 | NM | N/A | 0.10 | 0.0014 | 0.10 |
| 1,1,1-Trichloroethane | 0.38 | EPA 624 | 0.19 | 1.23 | 39,000,000 | 540,000 | 39,420,000 |

Note:

(1) Dichlorobenzenes is the sum of 1,2- and 1,3-dichlorobenzene.

Table C.4 Comparison of Projected RO Concentrate Pollutant Concentrations with NPDES Permit with Ocean Plan WQO Limits – Protection of Human Health (Carcinogens)

| Parameter | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | 30-Day Average NPDES Permit Effluent Limit (µg/L) | 30-Day Average Ocean Plan WQO-Based Effluent Limit (µg/L) | 30-Day Average Ocean Plan Effluent Limit (C _e) D _m = 72 |
|------------------------------|--------|-----------|---|--|---|---|--|
| Acrylonitrile | 1.8 | EPA 624 | 0.9 | 5.8 | 7 | 0.10 | 7.3 |
| Aldrin | 0.0015 | EPA 608 | 0.00075 | 0.0049 | 0.0016 | 0.000022 | 0.0016 |
| Benzene | 0.23 | EPA 624 | 0.115 | 0.7 | 430 | 5.9 | 431 |
| Benzidine | 3.7 | EPA 625 | 1.9 | 12 | N/A | 0.000069 | 0.0050 |
| Beryllium | 0.033 | EPA 200.8 | 0.017 | 0.1 | 1.4 | 0.033 | 2.41 |
| Bis (2-chloroethyl) ether | 0.27 | EPA 625 | 0.14 | 0.9 | N/A | 0.045 | 3.29 |
| Bis (2-ethylhexyl) phthalate | 2.3 | EPA 625 | 15 | 99 | N/A | 3.5 | 256 |
| Carbon Tetrachloride | 0.33 | EPA 624 | 0.17 | 1.1 | 66 | 0.90 | 66 |
| Chlordane | 0.05 | EPA 608 | 0.025 | 0.2 | 0.0017 | 0.000023 | 0.0017 |
| Chlorodibromomethane | 0.38 | EPA 624 | 13 | 84 | 630 | 8.6 | 628 |
| Chloroform | 0.25 | EPA 624 | 35 | 225 | 9,500 | 130 | 9,490 |
| DDT | 0.005 | EPA 608 | 0.0025 | 0.016 | 0.012 | 0.00017 | 0.012 |
| 1,4-Dichlorobenzene | 0.55 | EPA 625 | 0.28 | 1.8 | N/A | 18 | 1,314 |
| 3,3-Dichlorobenzidine | 1.2 | EPA 625 | 0.6 | 3.9 | N/A | 0.0081 | 0.59 |
| 1,2-Dichloroethane | 0.24 | EPA 624 | 0.12 | 0.8 | 2,000 | 28 | 2,044 |

| Parameter | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | 30-Day Average NPDES Permit Effluent Limit (µg/L) | 30-Day Average Ocean Plan WQO-Based Effluent Limit (µg/L) | 30-Day Average Ocean Plan Effluent Limit (C _e) D _m = 72 |
|--------------------------------------|---------------------|----------------|---|--|---|---|---|
| 1,1-Dichloroethylene | 0.12 | EPA 624 | 0.06 | 0.4 | 66 | 0.9 | 65.7 |
| Dichlorobromomethane | 0.28 | EPA 624 | 27 | 176 | 1,400 | 6.2 | 452.6 |
| Dichloromethane (Methylene Chloride) | 0.25 | EPA 624 | 0.13 | 0.8 | 33,000 | 450 | 32,850 |
| 1,3-Dichloropropene | 0.32 | EPA 624 | 0.16 | 1.0 | 650 | 8.9 | 650 |
| Dieldrin | 0.0021 | EPA 608 | 0.00105 | 0.0068 | 0.0029 | 0.00004 | 0.0029 |
| 2,4-Dinitrotoluene | 0.18 | EPA 625 | 0.09 | 0.6 | N/A | 2.6 | 190 |
| 1,2-Diphenylhydrazine | 0.25 | EPA 625 | 0.125 | 0.8 | N/A | 0.16 | 12 |
| Halomethanes ⁽¹⁾ | Note ⁽¹⁾ | EPA 624 | 2.2 | 14.2 | 9,600 | 130 | 9,490 |
| Heptachlor | 0.0017 | EPA 608 | 0.00085 | 0.0055 | 0.0037 | 0.00005 | 0.0037 |
| Heptachlor Epoxide | 0.0019 | EPA 608 | 0.00095 | 0.0062 | 0.0015 | 0.00002 | 0.0015 |
| Hexachlorobenzene | 0.49 | EPA 625 | 0.25 | 1.6 | 0.015 | 0.00021 | 0.015 |
| Hexachlorobutadiene | 0.47 | EPA 625 | 0.24 | 1.5 | 1,000 | 14 | 1,022 |
| Hexachloroethane | 0.52 | EPA 625 | 0.26 | 1.7 | 180 | 2.5 | 183 |
| Isophorone | 0.21 | EPA 625 | 0.11 | 0.7 | 53,000 | 730 | 53,290 |
| N-nitrosodimethylamine | 0.14 | EPA 625 | 0.07 | 0.5 | 530 | 7.3 | 533 |
| N-nitrosdi-N-propylamine | 0.26 | EPA 625 | 0.13 | 0.8 | 28 | 0.38 | 28 |

| Parameter | MDL | Method | Average Monthly Concentration in Tapia Effluent | Projected Average Concentration in AWPf RO Concentrate | 30-Day Average NPDES Permit Effluent Limit (µg/L) | 30-Day Average Ocean Plan WQO-Based Effluent Limit (µg/L) | 30-Day Average Ocean Plan Effluent Limit (C _e) D _m = 72 |
|---|---------------------|-----------|---|--|---|---|---|
| N-nitrosodiphenylamine | 0.19 | EPA 625 | 0.095 | 0.6 | 180 | 2.5 | 183 |
| Polynuclear Aromatic Hydrocarbons (PAHs) ⁽²⁾ | Note ⁽²⁾ | EPA 625 | 0.005 | 0.04 | N/A | 0.0088 | 0.64 |
| Polychlorinated Biphenyls (PCBs) ⁽³⁾ | Note ⁽³⁾ | EPA 625 | 0.19 | 1.2 | 0.0014 | 0.000019 | 0.0014 |
| TCDD Equivalents ⁽⁴⁾ | Note ⁽⁴⁾ | EPA 1613B | 0.00000087 | 0.0000057 | 0.00000028 | 0.000000039 | 0.00000028 |
| 1,1,2,2-Tetrachloroethane | 0.18 | EPA 624 | 0.09 | 0.6 | 170 | 2.3 | 168 |
| Tetrachloroethylene | 0.11 | EPA 624 | 0.06 | 0.4 | 150 | 2.0 | 146 |
| Toxaphene | 0.035 | EPA 608 | 0.018 | 0.11 | 0.015 | 0.00021 | 0.015 |
| Trichloroethylene | 0.27 | EPA 624 | 0.14 | 0.9 | 2,000 | 27 | 1,971 |
| 1,1,2-Trichloroethane | 0.25 | EPA 624 | 0.125 | 0.8 | 690 | 9.4 | 686 |
| 2,4,6-Trichlorophenol | 0.22 | EPA 625 | 0.11 | 0.7 | N/A | 0.29 | 21 |
| Vinyl Chloride | 0.33 | EPA 624 | 0.17 | 1.1 | N/A | 36 | 2,628 |

Notes:

- (1) Halomethanes shall mean the sum of bromoform (MDL = 0.32 µg/L), bromomethane (methyl bromide, MDL = 0.47 µg/L), and chloromethane (methyl chloride, MDL = 0.26 µg/L).
- (2) PAHs shall mean the sum of acenaphthylene (MDL = 0.52 nanograms per liter [ng/L]); anthracene (MDL = 0.91 ng/L); 1,2-benzanthracene (MDL = 0.79 ng/L); 3,4-benzofluoranthene (MDL = 1.6 ng/L); benzo(k)fluoranthene (MDL = 0.52 ng/L); 1,12-benzoperylene (MDL = 0.9 ng/L); benzo(a)pyrene (MDL = 0.58 ng/L); chrysene (MDL = 0.52 ng/L); dibenzo(a,h)anthracene (MDL = 1.2 ng/L); fluorene (MDL = 0.75 ng/L); indeno(1,2,3-cd)pyrene (MDL = 0.99 ng/L); phenanthrene (MDL = 0.96 ng/L); and pyrene (MDL = 0.68 ng/L).
- (3) PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016 (MDL = 0.022 µg/L), Aroclor-1221 (MDL = 0.084 µg/L), Aroclor-1232 (MDL = 0.064 µg/L), Aroclor-1242 (MDL = 0.07 µg/L), Aroclor-1248 (MDL = 0.049 µg/L), Aroclor-1254 (MDL = 0.068 µg/L), and Aroclor 1260 (MDL = 0.02 µg/L).
- (4) TCDD Equivalents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors. USEPA method 1613 may be used to analyze dioxin and furan congeners. MDLs are assumed to be as follows: 0.543 picogram per liter [pg/L] for 2,3,7,8-tetra CDD, 0.771 pg/L for 2,3,7,8-penta CDD, 1.05 pg/L for 2,3,7,8-hexa CDDs, 1.18 pg/L for 2,3,7,8-hepta CDD, 2.26 pg/L for octa CDD, 0.449 pg/L for 2,3,7,8-tetra CDF, 1.05 pg/L for 1,2,3,7,8 penta CDF, 1.08 pg/L for 2,3,4,7,8-penta CDF, 0.545 pg/L for 2,3,7,8-hexa CDFs, 0.654 pg/L for 2,3,7,8-hepta CDFs, and 1.22 pg/L for octa CDF.

C.2 Recommended Chemical Constituent Sampling

Additional sampling is required to gather data on Tributyltin because none was available from historical Tapia WRF effluent data. Based on the comparisons in Table C-1 through Table C-4, 14 pollutants had theoretical RO concentrate levels that exceeded the NPDES and/or Ocean Plan effluent limitations. Of these exceedances, 13 were calculated based solely on ND results (using half of the MDL and concentrating by a factor of 6.5). Only 1 exceedance, gross beta, was a true exceedance. Table C-5 lists the pollutants that require additional testing, including those that may exceed effluent limitations in the RO concentrate. **Each parameter will be sampled three times each quarter during the first year of testing to develop a robust dataset of at least 12 samples per pollutant.**

C.3 Recommended Chronic Toxicity Testing

In addition to the parameters listed in these tables, CMWD SMP NPDES and Ocean Plan have effluent limits of 2.46 acute toxic units (TUa) for acute toxicity and 73 chronic toxic units (TUc) for chronic toxicity. Because Dm is less than 100 for this project, chronic toxicity testing (more stringent) is required instead of acute. Chronic toxicity (TUc) is calculated as follows:

$$TUc = 100/NOEL$$

No Observed Effect Level (NOEL) is the maximum percent effluent or receiving water that causes no observable effect on a test organism, as determined by the result of a critical life stage toxicity test listed in Ocean Plan Appendix III, Table III-1.

Toxicity testing for ocean discharge as seen in the Calleguas SMP NPDES permit uses the most sensitive of the following organisms:

1. Topsmelt (*Atherinops affinis* - survival and growth).
2. Purple sea urchin (*Strongylocentrotus purpuratus* - growth and fertilization).
3. Sand dollar (*Dendraster excentricus* - growth and fertilization).
4. Red abalone (*Haliotis rufescens* - shell development).
5. Giant kelp (*Macrocystis pyrifera* - germination and growth).

Testing shall be conducted in accordance with species and test methods in Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to West Coast Marine and Estuarine Organisms (EPA/600/R-95/136, 1995). **Chlorine and ammonia shall be removed from the effluent sample prior to toxicity testing.** A total of eight chronic toxicity samples will be collected, as follows:

- Q1:** Once on each of the sensitive species (total of 5 tests).
- Q2:** Once on the most sensitive species based on Q1 testing (total of 1 test).
- Q3:** Once on the most sensitive species based on Q1 testing (total of 1 test).
- Q4:** Once on the most sensitive species based on Q1 testing (total of 1 test).

Topsmelt has been determined to be the most sensitive to RO concentrate based upon recent RO concentrate work in Pismo Beach, California and is therefore likely to be the most sensitive carried forward in Q2 through Q4. If a sample fails its toxicity test, the test will be repeated again at a different dilution. Dilution water will be lab grade water or saline water to simulate the combined discharge of RO concentrate and its diluent, the sum of which is required to meet the toxicity requirement.

Table C.5 Effluent Limit Exceedances Based on Theoretical RO Concentrate

| Pollutant | Units | Projected Average Concentration in AWPFO RO Concentrate | NPDES and/or Ocean Plan Effluent Limit | MDL | Rational for Additional Testing |
|-----------------------|-------|---|--|---------|--|
| Gross Beta | pCi/L | 100 | 50 | Varies | Projected RO concentrate too high |
| Tributyltin | µg/L | N/A | 0.1 | 0.0012 | No tertiary effluent data available |
| Aldrin | µg/L | 0.0026 | 0.0016 | 0.00079 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Benzidine | µg/L | 4.5 | 0.0050 | 1.4 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Beryllium | µg/L | 1.6 | 1.4 | 0.5 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Chlordane | µg/L | 0.1 | 0.0017 | 0.026 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| DDT | µg/L | 0.016 | 0.012 | 0.005 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| 3,3-Dichlorobenzidine | µg/L | 1.8 | 0.59 | 0.54 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Dieldrin | µg/L | 0.0032 | 0.0029 | 0.00097 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Heptachlor Epoxide | µg/L | 0.0022 | 0.0015 | 0.00069 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Hexachlorobenzene | µg/L | 0.5 | 0.015 | 0.15 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |

| Pollutant | Units | Projected Average Concentration in AWPf RO Concentrate | NPDES and/or Ocean Plan Effluent Limit | MDL | Rational for Additional Testing |
|------------------------------------|-------|--|--|---------------------|--|
| PCBs ⁽¹⁾ | µg/L | 1.0 | 0.0014 | Note ⁽¹⁾ | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| TCDD Equivalentents ⁽²⁾ | µg/L | 0.000023 | 0.00000028 | Note ⁽²⁾ | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |
| Toxaphene | µg/L | 0.11 | 0.015 | 0.035 | Available tertiary effluent data was non-detect but MDL too high to confirm RO concentrate lower than regulatory limit |

Notes:

- (1) PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016 (MDL = 0.05 µg/L), Aroclor-1221 (MDL = 0.063 µg/L), Aroclor-1232 (MDL = 0.05 µg/L), Aroclor-1242 (MDL = 0.05 µg/L), Aroclor-1248 (MDL = 0.02 µg/L), Aroclor-1254 (MDL = 0.05 µg/L), and Aroclor 1260 (MDL = 0.015 µg/L).
- (2) TCDD Equivalentents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors. USEPA method 1613 may be used to analyze dioxin and furan congeners. MDLs are assumed to be as follows: 0.887 pg/L for 2,3,7,8-tetra CDD, 2.56 pg/L for 2,3,7,8-penta CDD, 13.1 pg/L for 2,3,7,8-hexa CDDs, 5.15 pg/L for 2,3,7,8-hepta CDD, 8.5 pg/L for octa CDD, 0.733 pg/L for 2,3,7,8-tetra CDF, 2.96 pg/L for 1,2,3,7,8 penta CDF, 5.4 pg/L for 2,3,4,7,8-penta CDF, 4.7 pg/L for 2,3,7,8-hexa CDFs, 5.74 pg/L for 2,3,7,8-hepta CDFs, and 11.7 pg/L for octa CDF.

Appendix D

DAILY PERFORMANCE LOGS

OPERATION CHECKLISTS

This document contains the daily and weekly checklists for normal operation of the Pure Water Demonstration Plant.

Safety

- The pure water demonstration plant is a sophisticated facility that uses electrical potentials, pressurized gases and fluids, elevated equipment, motorized equipment and hazardous chemicals during the course of normal operations and maintenance that are capable of causing serious injury or death.
- The plant uses chemicals that can be corrosive and oxidizing to many materials.
- Always follow safety practices when working around potential hazards such as electricity, high-pressure gasses, high-pressure fluids, elevated equipment, machinery and corrosive chemicals.
- Always read the chemical safety data sheet (SDS) and use personal protective equipment when working with chemicals.

Daily Checks

The following activities should be carried out daily and the checklist prepared at the end of this document filled out:

- Inspection of skids, chemical tank levels, dosing pumps and ancillary equipment.
- Cross check of Critical Control Points and Operational Control Points.
- Fill out daily checks.
- Download and review data trends for parameters listed in daily checks.

Weekly Checks

The following activities should be carried out up to two times per week and the checklist prepared at the end of this document filled out.

- Take and analyze grab samples to confirm meter readings.
- Analyze grab samples.
- Fill out weekly checklists.
- Take and ship grab samples for external laboratory analysis - See Lab sampling Checklists Doc.

Additional Information

- Startup SOP.
- Operation SOP.
- Chemical Dosing SOP.
- Lab Sampling Checklists.

Checklists

Checklists are provided to assist with daily and weekly checks on the following pages. Print these as needed. Scan and store checklists as part of plant records.

Table 1 Daily Check List MF/UF System

| Las Virgenes Municipal Water District Demonstration Pilot Ultra Filtration Daily Checklist | | | | | |
|--|-----------------|---------------------------|---------------------------|---------------------------|---|
| Operator: | | | Date and Time: | | |
| Parameter | HMI Tag | Sample Location | | | Target |
| System Operating (y/n) | - | | | | y |
| Leaks On Skid? (y/n) | - | | | | n |
| Feed Pressure Gauge (psi) | PG-11248 | | | | > 20 |
| Filtrate Tank Level (%) | LI-36260 | | | | - |
| Feed Temperature (°F) | TI-14078 | | | | |
| Turbidity | Feed [AI-10209] | UF1 Filtrate [AI-31009-1] | UF2 Filtrate [AI-31009-2] | UF3 Filtrate [AI-31009-3] | |
| Turbidity Flowrate (gph) | | | | | 8 - 10 |
| Flowrate adjustment (y/n) | | | | | - |
| Turbidity (NTU) (Record Value <i>after</i> adjusting turbidity flowrate) | | | | | Feed < 10, Filtrate < 0.2 |
| TMP (psi) | on HMI | UF1 | UF2 | UF3 | UF1: < 30.5 UF2: < 45 UF3: < 43.5 |
| | | | | | |
| Feed Pressure (psi) | | PI-31045-1 | PI-31045-2 | PI-31045-3 | 5 - 25 |
| Filtrate Pressure (psi) | | PI-31509-1 | PI-31509-2 | PI-31509-3 | 1.5 - 2 |
| Flux [J] (gfd) | above FI-31032 | | | | |
| Production Volume (gal) | on HMI | | | | |
| UF Filtrate SDI-15 (twice per week) | Onsite Test | | | | < 3 |
| Time & Date of Last MIT | | | | | - |
| Last MIT Start (psi) | PROD/BW /MIT | | | | - |
| Last MIT End (psi) | SETTINGS | | | | - |
| Last LRV | | | | | > 4 |
| Filtrate Ammonia (mg/L) | AI-36210 | | | | > 0.5 |
| Filtrate Total Cl ₂ (mg/L) | AI-31094 | | | | 2 - 3 |
| Filtrate ORP (mV) | AI-31093 | | | | < 460 mV |
| Filtrate pH | AI-31090 | | | | 7 - 8 |
| Reason for shutdown, alarms and notes: | | | | | |

Be sure MF/UF is in production mode when you write down the turbidity meter flowrate, flows and pressures number. Otherwise data will not be representative.

Table 2 Daily Check List RO System

| Las Virgenes Municipal Water District Demonstration Pilot Reverse Osmosis Daily Checklist | | | | | | |
|---|-------------------------|-----------------------|-------------------------|-----------------------|-------------------------------|---------------|
| Operator: | | | Date and Time: | | | |
| Parameter | Sample Location | | | | | Target |
| System Operating (y/n) | | | | | | y |
| Chemical Feed Pump Flow (gph) | Antiscalant P-85300 | | Sulfuric Acid P-85500 | | | - |
| | | | | | | |
| Leaks On Skid? (y/n) | | | | | | n |
| Operating Mode | 2 Stage or 3 Stage | | | | | - |
| Recovery (%) | | | | | | 80 |
| Feed Temperature (°F) | TI-40005 | | | | | - |
| Feed pH | AIT-40008 | | | | | < 6.5 |
| Feed Free Cl ₂ (mg/L) | AIT-40004 | | | | | < 0.1 |
| Feed ORP (mV) | AIT-40005 | | | | | < 560 |
| TOC Flowrate (gph) | RO Feed | | | RO Permeate | | 1 - 3 |
| | FI-40074: | | | FI-41874: | | |
| Flowrate adjustment (y/n) | | | | | | - |
| TOC (mg/L) | AIT-40010: | | | AIT-41810: | | |
| Conductivity (µS/cm) | Feed AIT-40006 | S1 AIT-41092 | S2 AIT-41292 | S3 AIT-41392 | Permeate AIT-41892 | Permeate < 50 |
| | | | | | | |
| Pressure (psi) | S1 Feed PT-41095 | S2 Feed PT-41245 | S2 Conc. PT-41345 | S3 Feed PT-41347 | S3 Conc. PT-41945 | - |
| | | | | | | |
| | S1 Permeate PG-41054 | | S2 Permeate PG-41254 | | Combined Permeate PG-41854 | |
| | | | | | | |
| Flow (gpm) | S1 Perm. FIT-41074 | S2 Perm. FIT-41274 | S3 Perm. FIT-41374 | Permeate FQI-41874 | Conc. FIT-41974 | - |
| | | | | | | |

Las Virgenes Municipal Water District Demonstration Pilot Reverse Osmosis Daily Checklist

| | | | | |
|--|--|----------------------|----------------------|---|
| Differential Pressure (psi) | Stage 1 DPI-41039 | Stage 2 DPI-41239 | Stage 3 DPI-41339 | - |
| | | | | |
| Cartridge Filter Pressure (psi) | Inlet PG-40048 | | Outlet PG-40248 | |
| | | | | |
| Reason for shutdown, alarms and notes: | * FCV-41076 should be closed and stage 1 permeate flow (FIT-41074) should be 0 for 2 stage operation, which is the current mode of operation for July and into August. | | | |

Table 3 Daily Check List UVAOP System

| Las Virgenes Municipal Water District Demonstration Pilot UVAOP Daily Checklist | | | | |
|---|-----------------|----------------|--------|---------------------------------|
| Operator: | | Date and Time: | | |
| Parameter | Sample Location | | | Target |
| System Operating (y/n) | | | | y |
| Leaks On Skid? (y/n) | | | | n |
| Flush Air Release Valve (On UV Reactor) (y/n) | | | | y |
| UV Dose (mJ/cm ²) | | | | > 1500 |
| UV Intensity (mW/cm ²) | | | | - |
| Power (%) | | | | 50 - 100 % |
| Inlet Flow (gpm) | | | | 6 - 8 gpm |
| Lamp Hours (h) | | | | < 14,000 |
| Operating Hours (h) | | | | |
| UV Inlet pH | | | | < 6 |
| UVT (%) | HMI | Inlet | Outlet | > 95 |
| | | | | |
| Free Cl ₂ (mg/L) | Inlet | | Outlet | Inlet: 2 - 3 Outlet: 0.5 - 1 |
| | | | | |
| Total Cl ₂ (mg/L) | Inlet | | Outlet | Outlet: <4 |
| | | | | |

Reason for shutdown, alarms and notes:

Table 4 Daily Chemical Tank Check List

| Daily Chemical Checks | | | | | |
|--|---------------------|-----------------|-------------------------|---------|-----------------------------|
| Operator: | | | Date and Time: | | |
| Chemicals on UV Skid | Volume Onsite (gal) | Pump Flow (gph) | Pump Backpressure (psi) | Refill? | Tank Level |
| CLR (Calcium Lime Rust) on Both UVT Meters | | | N/A | Y / N | Level: [Target: >50%] |
| Chemicals on RO Skid | | | | | |
| Sulfuric Acid Tank - RO Feed [T-85400] | | | N/A | Y / N | Level: [Target: >5 gal] |
| Anti-scalant Tank - RO Feed [T-85200] | | | N/A | Y / N | Level: [Target: >3 gal] |
| Chemicals in Chemical Room | | | | | |
| NaOCl Tank - UF CIP [T-83400] | | | | Y / N | Level: [Target: 5 - 10 gal] |
| NaOH Tank - CIP [T-84200] | | | | Y / N | Level: [Target: > 5 gal] |
| NaOCl Tank - UF Feed [T-81400] | | | | Y / N | Level: [Target: >10 gal] |
| NaOCl Tank - UVAOP Feed [T-89000] | | | | Y / N | Level: [Target: 5 - 20 gal] |
| Calcium Thiosulfate Tank [T-84000] | | | | Y / N | Level: [Target: > 5 gal] |
| Ammonium Sulfate Tank [T-80000] | | | | Y / N | Level: [Target: >10 gal] |
| Citric Acid Tank - CIP [T-83600] | | | | Y / N | Level: [Target: > 5 gal] |
| Sulfuric Acid Tank - CIP [T-81000] | | | | Y / N | Level: [Target: > 5 gal] |

Notes:

Reorder Sodium Hypochlorite when 1 drum is left

Reorder Ammonium Sulfate when 1 drum is left

Reorder Sulfuric Acid when drum is empty

Other chemicals should be reordered when approaching their lower fill value indicated by an orange display on the dosing pump.

When topping up sodium hypochlorite tanks, rotate solution from [T-83400] and [T-89000] into [T-81400] to maintain solution freshness feeding the UV and for UF maintenance cleans.

Only fill T-83400 to approximately 10 gal and T-89000 to 15 - 20 gal to maintain solution freshness.

When filling ammonium sulfate [T], fill half with RO permeate and half with ammonium sulfate so that final solution strength is 20 wt% ammonium sulfate.

Please note any leaks, overflowing or tank damage.

Table 5 Weekly Checklist Instrument Verification

| Weekly Instrument Verification | | | | |
|--------------------------------|--------------------------------|----------------------------------|----------------------------------|----------------------------------|
| Operator | | Date and Time | | |
| Parameter | | Sample Location | | |
| pH | UF Filtrate Combined | | RO Feed | |
| | UVAOP Feed | | | |
| | Grab: Online: [AI-31090] | Grab: Online: [AI-40008] | Grab: Online: [pH-001] | |
| Turbidity (NTU) | UF Feed | | UF Filtrate 1 | UF Filtrate 2 |
| | | | UF Filtrate 3 | |
| | Grab: Online: [AI-10209] | Grab: Online: [AI-31009-1] | Grab: Online: [AI-31009-2] | Grab: Online: [AI-31009-3] |
| Conductivity (µS/cm) | RO Feed | | RO Permeate Stage 1 | RO Permeate Stage 2 |
| | | | RO Permeate Stage 3 | RO Permeate Combined |
| | Grab: Online: [AI-40006] | Grab: Online: [AI-41092] | Grab: Online: [AI-41292] | Grab: Online: [AI-41392] |
| Total Chlorine (mg/L) | UF Filtrate Combined | | UVAOP Inlet | |
| | | | UVAOP Outlet | |
| | Grab: Online: [AI-31094] | Grab: Online: [TCI-001] | Grab: Online: [TCI-002] | |
| Free Chlorine (mg/L) | RO Feed | | UVAOP Inlet | |
| | | | UVAOP Outlet | |
| | Grab: Online: [AI-40004] | Grab: Online: [FCI-001] | Grab: Online: [FCI-002] | |
| ORP (mV) | UF Filtrate Combined | | RO Feed | |
| | | | | |
| | Grab: | Online: [AI-31093] | Grab: | Online: [AI-40005] |
| UVT (%) | UVAOP Inlet | | UVAOP Outlet | |
| | | | | |
| | Grab: | Online: | Grab: | Online: |
| TOC (mg/L) | RO Feed | | RO Permeate Combined | |
| | | | | |
| | Grab: (offsite lab) | Online: [AI-40010] | Grab: (offsite lab) | Online: [AI-41810] |
| Ammonia (mg/L) | UF Filtrate Combined | Grab: | Online: [AI-40005] | |

Notes:

Table 6 Weekly Grab Samples for ONSITE Analysis

| Weekly Grab Samples for ONSITE analysis | | | | | | | |
|--|-----------------|------------------------|---------|-------------|----------------|----------|-----------|
| Date & Time | | Operator | | | | | |
| Parameter | Sample Location | | | | | | |
| | UF Feed | UF Filtrate (combined) | RO Feed | RO Permeate | RO Concentrate | UV Inlet | UV Outlet |
| pH | | | | | | | |
| Turbidity (NTU) | | | | | | | |
| Conductivity (µS/cm) | | | | | | | |
| ORP (mV) | | | | | | | |
| Ammonia | | | | | | | |
| Free Cl ₂ (mg/L) | | | | | | | |
| Total Cl ₂ (mg/L) | | | | | | | |
| Monochloramine (mg/L) | | | | | | | |
| TOC (mg/L) [SM 5310 B] Offsite | | | X* | X* | | | |
| UVT (%) | | | | | | | |
| Dissolved Oxygen (mg/L) | | | | | | | |
| * X = Samples are collected for offsite lab analysis | | | | | | | |
| Notes: | | | | | | | |

Appendix E
CALLEGUAS MUNICIPAL WATER DISTRICT
SALINITY MANAGEMENT PIPELINE NPDES
PERMIT

**CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LOS ANGELES REGION**

320 W. 4th Street, Suite 200, Los Angeles, California 90013
Phone (213) 576-6600 • Fax (213) 576-6640
<http://www.waterboards.ca.gov/losangeles/>

**ORDER R4-2014-0033
NPDES NO. CA0064521**

**WASTE DISCHARGE REQUIREMENTS
FOR CALLEGUAS MUNICIPAL WATER DISTRICT
REGIONAL SALINITY MANAGEMENT PIPELINE**

The following Discharger is subject to waste discharge requirements (WDR's) set forth in this Order:

Table 1. Discharger Information

| | |
|-------------------------|--|
| Discharger | Calleguas Municipal Water District |
| Name of Facility | Regional Salinity Management Pipeline (RSMP) |
| Facility Address | 2100 Olsen Road |
| | Thousand Oaks, CA 91360-6800 |
| | Ventura County |

Table 2. Discharge Location

| Discharge Point | Effluent Description | Discharge Point Latitude | Discharge Point Longitude | Receiving Water |
|------------------------|--|---------------------------------|----------------------------------|-------------------------------------|
| 001 | Treated wastewater and concentrate from brackish groundwater desalter plants and wastewater treatment facilities | 34° 08' 34.75" N | 119° 11' 33.72" W | Pacific Ocean at Port Hueneme Beach |

Table 3. Administrative Information

| | |
|---|--------------------------|
| This Order was adopted on: | March 6, 2014 |
| This Order shall become effective on: | May 1, 2014 |
| This Order shall expire on: | April 30, 2019 |
| The Discharger shall file a Report of Waste Discharge as an application for reissuance of WDR's in accordance with title 23, California Code of Regulations, and an application for reissuance of a National Pollutant Discharge Elimination System (NPDES) permit no later than: | November 22, 2018 |
| The U.S. Environmental Protection Agency (U.S. EPA) and the California Regional Water Quality Control Board, Los Angeles Region have classified this discharge as follows: | Major discharge |

I, Samuel Unger, Executive Officer, do hereby certify that this Order with all attachments is a full, true, and correct copy of the Order adopted by the California Regional Water Quality Control Board, Los Angeles Region, on the date indicated above.


 Samuel Unger, Executive Officer

Contents

I. Facility Information 3
II. Findings 3
III. Discharge Prohibitions 3
IV. Effluent Limitations and Discharge Specifications 4
 A. Effluent Limitations – Discharge Point 001 4
 1. Final Effluent Limitations – Discharge Point 001 4
 B. Land Discharge Specifications – Not Applicable 10
 C. Recycling Specifications – Not Applicable 10
V. Receiving Water Limitations 10
 A. Bacterial Characteristics 10
 B. Physical Characteristics 12
 C. Chemical Characteristics 12
 D. Biological Characteristics 13
 E. Radioactivity 13
VI. Provisions 13
 A. Standard Provisions 13
 B. Monitoring and Reporting Program (MRP) Requirements 15
 C. Special Provisions 16
 1. Reopener Provisions 16
 2. Special Studies, Technical Reports and Additional Monitoring Requirements 16
 3. Best Management Practices and Pollution Prevention 17
 4. Construction, Operation and Maintenance Specifications 17
 5. Other Special Provisions – Not Applicable 17
 6. Compliance Schedules – Not Applicable 17
VII. Compliance Determination 17

Tables

Table 1. Discharger Information 1
Table 2. Discharge Location 1
Table 3. Administrative Information 1
Table 4. Effluent Limitations 4

Attachments

Attachment A – Definitions A-1
Attachment B – Map B-1
Attachment C – Flow Schematic C-1
Attachment D – Standard Provisions D-1
Attachment E – Monitoring and Reporting Program (MRP No. 9404) E-1
Attachment F – Fact Sheet F-1
Attachment G – Storm Water Pollution Prevention Plan Requirements G-1
Attachment H – State Water Board Minimum Levels H-1

I. FACILITY INFORMATION

Information describing the Regional Salinity Management Pipeline (Facility or RSMP) is summarized in Table 1 and in sections I and II of the Fact Sheet (Attachment F). Section I of the Fact Sheet also includes information regarding the Facility's permit application.

II. FINDINGS

The California Regional Water Quality Control Board, Los Angeles Region (hereinafter Los Angeles Regional Water Board), finds:

- A. **Legal Authorities.** This Order serves as WDR's pursuant to article 4, chapter 4, division 7 of the California Water Code (commencing with section 13260). This Order is also issued pursuant to section 402 of the federal Clean Water Act (CWA) and implementing regulations adopted by the U.S. EPA and chapter 5.5, division 7 of the Water Code (commencing with section 13370). It shall serve as an NPDES permit for point source discharges from this facility to surface waters.
- B. **Background and Rationale for Requirements.** The Los Angeles Regional Water Board developed the requirements in this Order based on information submitted as part of the application, through monitoring and reporting programs, and other available information. The Fact Sheet (Attachment F), which contains background information and rationale for the requirements in this Order, is hereby incorporated into and constitutes Findings for this Order. Attachments A through E and G through H are also incorporated into this Order.
- C. **Notification of Interested Parties.** The Los Angeles Regional Water Board has notified the Discharger and interested agencies and persons of its intent to prescribe WDR's for the discharge and has provided them with an opportunity to submit their written comments and recommendations. Details of the notification are provided in the Fact Sheet.
- D. **Consideration of Public Comment.** The Los Angeles Regional Water Board, in a public meeting, heard and considered all comments pertaining to the discharge. Details of the Public Hearing are provided in the Fact Sheet.

THEREFORE, IT IS HEREBY ORDERED, that this Order supersedes Order R4-2008-0014 except for enforcement purposes, and, in order to meet the provisions contained in division 7 of the Water Code (commencing with section 13000) and regulations adopted thereunder, and the provisions of the CWA and regulations and guidelines adopted thereunder, the Discharger shall comply with the requirements in this Order. This action in no way prevents the Los Angeles Regional Water Board from taking enforcement action for past violations of the previous Order.

III. DISCHARGE PROHIBITIONS

- A. Wastes discharged shall be limited to a maximum of 17.52 MGD of treated effluent from wastewater treatment plants and concentrate generated at brackish groundwater desalter plants or wastewater treatment facilities throughout the Calleguas Creek Watershed through Discharge Point 001. The discharge of wastes from accidental spills or other sources is prohibited.
- B. Discharges of water, materials, thermal wastes, elevated temperature wastes, toxic wastes, deleterious substances, or wastes other than those authorized by this Order, to a storm drain system, the Pacific Ocean, or other waters of the State, are prohibited.
- C. Neither the treatment nor the discharge of pollutants shall create pollution, contamination, or a nuisance as defined by section 13050 of the Water Code.

- D. Wastes discharged shall not contain any substances in concentrations toxic to human, animal, plant, or aquatic life.
- E. The discharge shall not cause a violation of any applicable water quality standards for receiving waters adopted by the Regional Water Board or the California State Water Resources Control Board (State Water Board) as required by the Federal CWA and regulations adopted thereunder. If more stringent applicable water quality standards are promulgated pursuant to section 303 of the Federal CWA, and amendments thereto, the Regional Water Board will revise and modify this Order in accordance with such more stringent standards.
- F. The discharge of any radiological, chemical, or biological warfare agent into the waters of the state is prohibited under Water Code section 13375.
- G. Any discharge of wastes at any point(s) other than specifically described in this Order is prohibited, and constitutes a violation of this Order.

IV. EFFLUENT LIMITATIONS AND DISCHARGE SPECIFICATIONS

A. Effluent Limitations – Discharge Point 001

1. Final Effluent Limitations – Discharge Point 001

(Initial Dilution Ratio = 72:1)

- a. The Discharger shall maintain compliance with the following effluent limitations at Discharge Point 001, with compliance measured at Monitoring Location EFF-001 as described in the Monitoring and Reporting Program, Attachment E:

Table 4. Effluent Limitations

| Parameter | Units | Effluent Limitations | | | | |
|---|------------------------|----------------------|----------------|----------------------|-----------------------|------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Biochemical Oxygen Demand (BOD), 5-day @ 20°C | mg/L | 30 | 45 | -- | -- | -- |
| | lbs/day ¹ | 4,400 | 6,600 | | -- | -- |
| Oil and Grease | mg/L | 25 | 40 | -- | 75 | -- |
| | lbs/day ¹ | 3,700 | 5,800 | -- | 11,000 | -- |
| pH | s.u. | 6.0 - 9.0 | | | | |
| Settleable Solids | ml/L | 1.0 | 1.5 | -- | 3.0 | -- |
| Total Suspended Solids (TSS) | mg/L | 60 | -- | -- | -- | -- |
| | lbs/day ¹ | 8,800 | -- | -- | -- | -- |
| Turbidity | NTU | 75 | 100 | -- | 225 | -- |
| Total Residual Chlorine | µg/L | -- | -- | 580 | 4,400 | 150 |
| | lbs/day ¹ | -- | -- | 85 | 640 | 22 |
| Ammonia as N | µg/L | -- | -- | 180,000 | 440,000 | 44,000 |
| | lbs/day ¹ | -- | -- | 26,000 | 64,000 | 6,400 |
| Chronic Toxicity ² | Pass or Fail, % Effect | Pass ³ | | Pass or % Effect <50 | -- | -- |
| Total coliform | MPN/100ml | 4 | | | | |
| Fecal coliform | MPN/100ml | 4 | | | | |
| Enterococcus | MPN/100ml | 4 | | | | |

| Parameter | Units | Effluent Limitations | | | | |
|---|----------------------|----------------------|----------------|---------------|-----------------------|------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Antimony, Total Recoverable | µg/L | 88,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 13,000 | -- | -- | -- | -- |
| Arsenic, Total Recoverable | µg/L | -- | -- | 2100 | 5,600 | 370 |
| | lbs/day ¹ | -- | -- | 310 | 820 | 54 |
| Beryllium, Total Recoverable | µg/L | 2.4 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.35 | -- | -- | -- | -- |
| Cadmium, Total Recoverable | µg/L | -- | -- | 290 | 730 | 73 |
| | lbs/day ¹ | -- | -- | 42 | 110 | 11 |
| Chromium (III) , Total Recoverable | µg/L | 1.4E+07 | -- | -- | -- | -- |
| | lbs/day ¹ | 2.0E+06 | -- | -- | -- | -- |
| Chromium (VI) , Total Recoverable | µg/L | -- | -- | 580 | 1,500 | 150 |
| | lbs/day ¹ | -- | -- | 85 | 210 | 22 |
| Copper, Total Recoverable | µg/L | -- | -- | 730 | 2,000 | 75 |
| | lbs/day ¹ | -- | -- | 110 | 290 | 11 |
| Lead, Total Recoverable | µg/L | -- | -- | 580 | 1500 | 150 |
| | lbs/day ¹ | -- | -- | 85 | 220 | 22 |
| Mercury, Total Recoverable | µg/L | -- | -- | 12 | 29 | 2.9 |
| | lbs/day ¹ | -- | -- | 1.8 | 4.2 | 0.42 |
| Nickel, Total Recoverable | µg/L | -- | -- | 1,500 | 3,700 | 370 |
| | lbs/day ¹ | -- | -- | 220 | 530 | 53 |
| Selenium, Total Recoverable | µg/L | -- | -- | 4,400 | 11,000 | 1,100 |
| | lbs/day ¹ | -- | -- | 640 | 1600 | 160 |
| Silver, Total Recoverable | µg/L | -- | -- | 190 | 500 | 40 |
| | lbs/day ¹ | -- | -- | 28 | 73 | 5.8 |
| Thallium, Total Recoverable | µg/L | 150 | -- | -- | -- | -- |
| | lbs/day ¹ | 22 | -- | -- | -- | -- |
| Zinc, Total Recoverable | µg/L | -- | -- | 5,300 | 14,000 | 880 |
| | lbs/day ¹ | -- | -- | 770 | 2,000 | 130 |
| Cyanide | µg/L | -- | -- | 290 | 730 | 73 |
| | lbs/day ¹ | -- | -- | 42 | 110 | 11 |
| Phenolic Compounds (non-chlorinated) ⁵ | µg/L | -- | -- | 8,800 | 22,000 | 2,200 |
| | lbs/day ¹ | -- | -- | 1,300 | 3,200 | 320 |
| Chlorinated Phenolics ⁶ | µg/L | -- | -- | 290 | 730 | 73 |
| | lbs/day ¹ | -- | -- | 42 | 110 | 11 |
| TCDD Equivalentents ⁷ | µg/L | 2.8E-07 | -- | -- | -- | -- |
| | lbs/day ¹ | 4.1E-08 | -- | -- | -- | -- |
| Acrolein | µg/L | 16,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 2,300 | -- | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | | |
|---------------------------|----------------------|----------------------|----------------|---------------|-----------------------|------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Acrylonitrile | µg/L | 7.3 | -- | -- | -- | -- |
| | lbs/day ¹ | 1.1 | -- | -- | -- | -- |
| Benzene | µg/L | 430 | -- | -- | -- | -- |
| | lbs/day ¹ | 63 | -- | -- | -- | -- |
| Carbon Tetrachloride | µg/L | 66 | -- | -- | -- | -- |
| | lbs/day ¹ | 9.6 | -- | -- | -- | -- |
| Chlorobenzene | µg/L | 42,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 6,100 | -- | -- | -- | -- |
| Chlorodibromomethane | µg/L | 630 | -- | -- | -- | -- |
| | lbs/day ¹ | 92 | -- | -- | -- | -- |
| Chloroform | µg/L | 9,500 | -- | -- | -- | -- |
| | lbs/day ¹ | 1,400 | -- | -- | -- | -- |
| Dichlorobromomethane | µg/L | 450 | -- | -- | -- | -- |
| | lbs/day ¹ | 66 | -- | -- | -- | -- |
| 1,2-Dichloroethane | µg/L | 2,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 290 | -- | -- | -- | -- |
| 1,1-Dichloroethylene | µg/L | 66 | -- | -- | -- | -- |
| | lbs/day ¹ | 9.6 | -- | -- | -- | -- |
| 1,3-Dichloropropylene | µg/L | 650 | -- | -- | -- | -- |
| | lbs/day ¹ | 95 | -- | -- | -- | -- |
| Ethylbenzene | µg/L | 3.0E+5 | -- | -- | -- | -- |
| | lbs/day ¹ | 44,000 | -- | -- | -- | -- |
| Halomethanes ⁸ | µg/L | 9,500 | -- | -- | -- | -- |
| | lbs/day ¹ | 1,400 | -- | -- | -- | -- |
| Dichloromethane | µg/L | 33,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 4,800 | -- | -- | -- | -- |
| 1,1,2,2-Tetrachloroethane | µg/L | 170 | -- | -- | -- | -- |
| | lbs/day ¹ | 25 | -- | -- | -- | -- |
| Tetrachloroethylene | µg/L | 150 | -- | -- | -- | -- |
| | lbs/day ¹ | 22 | -- | -- | -- | -- |
| Toluene | µg/L | 6.2E+06 | -- | -- | -- | -- |
| | lbs/day ¹ | 9.1E+05 | -- | -- | -- | -- |
| 1,1,1-Trichloroethane | µg/L | 3.9E+07 | -- | -- | -- | -- |
| | lbs/day ¹ | 5.7E+06 | -- | -- | -- | -- |
| 1,1,2-Trichloroethane | µg/L | 690 | -- | -- | -- | -- |
| | lbs/day ¹ | 100 | -- | -- | -- | -- |
| Trichloroethylene | µg/L | 2,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 290 | -- | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | | |
|---|----------------------|----------------------|----------------|---------------|-----------------------|------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Vinyl Chloride | µg/L | 2,600 | -- | -- | -- | -- |
| | lbs/day ¹ | 380 | -- | -- | -- | -- |
| 4,6-Dinitro-2-Methylphenol | µg/L | 16,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 2,300 | -- | -- | -- | -- |
| 2,4-Dinitrophenol | µg/L | 290 | -- | -- | -- | -- |
| | lbs/day ¹ | 42 | -- | -- | -- | -- |
| 2,4,6-Trichlorophenol | µg/L | 21 | -- | -- | -- | -- |
| | lbs/day ¹ | 3.1 | -- | -- | -- | -- |
| Benzidine | µg/L | 0.0050 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00073 | -- | -- | -- | -- |
| Polynuclear Aromatic Hydrocarbons (PAHs) ⁹ | µg/L | 0.64 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.094 | -- | -- | -- | -- |
| Bis(2-chloroethoxy)Methane | µg/L | 320 | -- | -- | -- | -- |
| | lbs/day ¹ | 47 | -- | -- | -- | -- |
| Bis(2-chloroethyl)Ether | µg/L | 3.3 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.48 | -- | -- | -- | -- |
| Bis(2-chloroisopropyl)Ether | µg/L | 88,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 13,000 | -- | -- | -- | -- |
| Bis(2-ethylhexyl)Phthalate | µg/L | 260 | -- | -- | -- | -- |
| | lbs/day ¹ | 38 | -- | -- | -- | -- |
| Dichlorobenzenes | µg/L | 3.7E+05 | -- | -- | -- | -- |
| | lbs/day ¹ | 54,000 | -- | -- | -- | -- |
| 1,4-Dichlorobenzene | µg/L | 1300 | -- | -- | -- | -- |
| | lbs/day ¹ | 190 | -- | -- | -- | -- |
| 3,3'-Dichlorobenzidine | µg/L | 0.59 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.086 | -- | -- | -- | -- |
| Diethyl Phthalate | µg/L | 2.4E+06 | -- | -- | -- | -- |
| | lbs/day ¹ | 3.5E+05 | -- | -- | -- | -- |
| Dimethyl Phthalate | µg/L | 6.0E+07 | -- | -- | -- | -- |
| | lbs/day ¹ | 8.8E+06 | -- | -- | -- | -- |
| Di-n-Butyl Phthalate | µg/L | 2.6E+05 | -- | -- | -- | -- |
| | lbs/day ¹ | 38,000 | -- | -- | -- | -- |
| 2,4-Dinitrotoluene | µg/L | 190 | -- | -- | -- | -- |
| | lbs/day ¹ | 28 | -- | -- | -- | -- |
| 1,2-Diphenylhydrazine | µg/L | 12 | -- | -- | -- | -- |
| | lbs/day ¹ | 1.8 | -- | -- | -- | -- |
| Fluoranthene | µg/L | 1,100 | -- | -- | -- | -- |
| | lbs/day ¹ | 160 | -- | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | | |
|--|----------------------|----------------------|----------------|---------------|-----------------------|------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Hexachlorobenzene | µg/L | 0.015 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0022 | -- | -- | -- | -- |
| Hexachlorobutadiene | µg/L | 1,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 150 | -- | -- | -- | -- |
| Hexachlorocyclopentadiene | µg/L | 4,200 | -- | -- | -- | -- |
| | lbs/day ¹ | 610 | -- | -- | -- | -- |
| Hexachloroethane | µg/L | 180 | -- | -- | -- | -- |
| | lbs/day ¹ | 26 | -- | -- | -- | -- |
| Isophorone | µg/L | 53,000 | -- | -- | -- | -- |
| | lbs/day ¹ | 7,700 | -- | -- | -- | -- |
| Nitrobenzene | µg/L | 360 | -- | -- | -- | -- |
| | lbs/day ¹ | 53 | -- | -- | -- | -- |
| N-Nitrosodimethylamine | µg/L | 530 | -- | -- | -- | -- |
| | lbs/day ¹ | 77 | -- | -- | -- | -- |
| N-Nitrosodi-N-propylamine | µg/L | 28 | -- | -- | -- | -- |
| | lbs/day ¹ | 4.1 | -- | -- | -- | -- |
| N-Nitrosodiphenylamine | µg/L | 180 | -- | -- | -- | -- |
| | lbs/day ¹ | 26 | -- | -- | -- | -- |
| Aldrin | µg/L | 0.0016 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00023 | -- | -- | -- | -- |
| HCH ¹⁰ | µg/L | -- | -- | 0.58 | 0.88 | 0.29 |
| | lbs/day ¹ | -- | -- | 0.085 | 0.13 | 0.042 |
| Chlordane | µg/L | 0.0017 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00025 | -- | -- | -- | -- |
| DDT ¹¹ | µg/L | 0.012 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0018 | -- | -- | -- | -- |
| Dieldrin | µg/L | 0.0029 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00042 | -- | -- | -- | -- |
| Endosulfan | µg/L | -- | -- | 1.3 | 2.0 | 0.66 |
| | lbs/day ¹ | -- | -- | 0.19 | 0.29 | 0.096 |
| Endrin | µg/L | -- | -- | 0.29 | 0.44 | 0.15 |
| | lbs/day ¹ | -- | -- | 0.042 | 0.064 | 0.022 |
| Heptachlor | µg/L | 0.0037 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00054 | -- | -- | -- | -- |
| Heptachlor Epoxide | µg/L | 0.0015 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00022 | -- | -- | -- | -- |
| Polychlorinated Biphenyls (PCBs) ¹² | µg/L | 0.0014 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.00020 | -- | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | | |
|---------------|--|----------------------|----------------|---------------|-----------------------|------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Toxaphene | µg/L | 0.015 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0022 | -- | -- | -- | -- |
| Tributyltin | µg/L | 0.10 | -- | -- | -- | -- |
| | lbs/day ¹ | 0.015 | -- | -- | -- | -- |
| Radioactivity | Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, §30253 of the California Code of Regulations. Reference to §30253 is prospective, including future changes to any incorporated provisions of federal law, as the changes take effect. | | | | | |

1. The mass-based effluent limitations are based on the facility design flow rate of 17.52 MGD.
 Mass-based effluent limitation (lbs/day) = C * Q * 8.34
 Where: C = concentration-based effluent limitation (mg/L)
 Q = maximum discharge flow rate (MGD)
2. "Pass" or "Fail" for Median Monthly Effluent Limitation (MMEL). "Pass" or "Fail" and "% Effect" for Maximum Daily Effluent Limitation (MDEL). The MMEL for chronic toxicity shall only apply when there is a discharge more than one day in a calendar month period. During such calendar months, exactly three independent toxicity tests are required when one toxicity test results in "Fail".
3. This is a Median Monthly Effluent Limitation.
4. Bacteria limitations:
 - a. 30-day Geometric Mean – The geometric mean shall be calculated using the results of five most recent samples.
 - i. Total coliform density shall not exceed 1,000/100 ml;
 - ii. Fecal coliform density shall not exceed 200/100 ml; and
 - iii. Enterococcus density shall not exceed 35/100 ml.
 - b. Single Sample Maximum (SSM)
 - i. Total coliform density shall not exceed 10,000/100 ml;
 - ii. Fecal coliform density shall not exceed 400/100 ml;
 - iii. Enterococcus density shall not exceed 104/100 ml; and
 - iv. Total coliform density shall not exceed 1,000/100 ml, when the fecal coliform/total coliform ratio exceeds 0.1.

If a single sample exceeds any of the single sample maximum (SSM) standards, repeat sampling shall be conducted to determine the extent and persistence of the exceedance. Repeat sampling shall be conducted within 24 hours of receiving analytical results and continued until the sample result is less than the SSM standard.

When repeat sampling is required because of an exceedance of any one single sample density, values from all samples collected during that 30-day period will be used to calculate the geometric mean.
5. Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
6. Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
7. TCDD Equivalents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown in the table below. USEPA method 1613 may be used to analyze dioxin and furan congeners.

$$\text{Dioxin-TEQ (TCDD Equivalents)} = \sum (C_x \times \text{TEF}_x)$$

Where:

C_x = concentration of dioxin or furan congener x

TEF_x = TEF for congener x

Toxicity Equivalency Factors

| Isomer Group | Toxicity Equivalency Factor (TEF) |
|---------------------|-----------------------------------|
| 2,3,7,8-tetra CDD | 1.0 |
| 2,3,7,8-penta CDD | 0.5 |
| 2,3,7,8-hexa CDDs | 0.1 |
| 2,3,7,8-hepta CDD | 0.01 |
| Octa CDD | 0.001 |
| 2,3,7,8 tetra CDF | 0.1 |
| 1,2,3,7,8 penta CDF | 0.05 |
| 2,3,4,7,8 penta CDF | 0.5 |
| 2,3,7,8 hexa CDFs | 0.1 |
| 2,3,7,8 hepta CDFs | 0.01 |
| Octa CDF | 0.001 |

8. Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
9. PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorine; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.
10. HCH shall mean the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
11. DDT shall mean the sum of 4,4'-DDT, 2,4'-DDT, 4,4'-DDE, 2,4'-DDE, 4,4'-DDD, and 2,4'-DDD.
12. PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, and Aroclor-1260.

b. Temperature Limitations

- i. The temperature of wastes discharged shall not exceed the natural temperature of receiving waters by more than 20° F.
- ii. The temperature of wastes discharged shall not result in increases in the natural water temperature exceeding 4° F at (a) the shoreline, (b) the surface of any ocean substrate, or (c) the ocean surface beyond 1,000 feet from the discharge system. The surface temperature limitation shall be maintained at least 50 percent of the duration of any complete tidal cycle.

B. Land Discharge Specifications – Not Applicable

C. Recycling Specifications – Not Applicable

V. RECEIVING WATER LIMITATIONS

Receiving water limitations are based on water quality objectives contained in the California Ocean Plan, as most recently amended effective August 19, 2013 (“Ocean Plan”), and are a required part of this Order. Unless specifically excepted by this Order, the discharge, by itself or jointly with any other discharge(s), shall not cause violation of the following water quality objectives. Compliance with these objectives shall be determined by samples collected at stations representative of the area within the waste field where initial dilution is completed (i.e., outside the zone of initial dilution).

A. Bacterial Characteristics

1. Water Contact Standards

Both the State Water Board and the California Department of Public Health (CDPH) have established standards to protect water contact recreation in coastal waters from bacterial contamination. Subsection a of this section contains bacterial objectives adopted by the State Water Board for ocean waters used for water contact recreation. Subsection b

describes the bacteriological standards adopted by CDPH for coastal waters adjacent to public beaches and public water contact sports areas in ocean waters.

a. State/Regional Water Board Water Contact Standards

In marine water designated for water contact recreation (REC-1), the waste discharged shall not cause the following bacterial standards to be exceeded in the receiving water outside the initial dilution zone.

Geometric Mean Limits

- i. Total coliform density shall not exceed 1,000/100 ml;
- ii. Fecal coliform density shall not exceed 200/100 ml; and
- iii. Enterococcus density shall not exceed 35/100 ml.

Single Sample Maximum (SSM)

- i. Total coliform density shall not exceed 10,000/100 ml;
- ii. Fecal coliform density shall not exceed 400/100 ml;
- iii. Enterococcus density shall not exceed 104/100 ml; and
- iv. Total coliform density shall not exceed 1,000/100 ml, when the fecal coliform/total coliform ratio exceeds 0.1.

b. CDPH Standards

CDPH has established minimum protective bacteriological standards for coast water adjacent to public beaches and for public water-contact sports areas in ocean waters. These standards are found in the California Code of Regulations, title 17, section 7958, and they are identical to the objectives contained in subsection a. above. When a public beach or public water-contact sports area fails to meet these standards, CDPH or the local public health officer may post with warning signs or otherwise restrict use of the public beach or public water-contact sports area until the standards are met. The CDPH regulations impose more frequent monitoring and more stringent posting and closure requirements on certain high-use public beaches that are located adjacent to a storm drain that flows in the summer.

For beaches not covered under AB 411 regulations, CDPH imposes the same standards as contained in Title 17 and requires weekly sampling but allows the county health officer more discretion in making posting and closure decisions.

2. Shellfish Harvesting Standards

At all areas where shellfish may be harvested for human consumption, as determined by the Los Angeles Regional Water Board, the waste discharged shall not cause the following bacterial standards to be exceeded:

- a.** The median total coliform density for any 6-month period shall not exceed 70 per 100 ml, and not more than 10 percent of the samples during any 6-month period shall exceed 230 per 100 ml.

3. Implementation Provisions for Bacterial Characteristics

- a.** At a minimum, monthly samples shall be collected from each sampling location. The geometric mean values should be calculated using the five most recent sample results. If sampling occurs more frequently than monthly, all samples taken during the previous 30-day period shall be used to calculate the geometric mean.

- b. If a single sample exceeds any of the single sample maximum (SSM) standards, repeat sampling at that location shall be conducted to determine the extent and persistence of the exceedance. Repeat sampling shall be conducted within 24 hours of receiving analytical results and continued until the sample result is less than the SSM standard or until the Los Angeles Regional Water Board requires the Discharger or appropriate agency to conduct a sanitary survey to determine the source of the high bacterial densities. A sanitary survey shall also be required if three out of four samples taken during any 30-day period exceed any SSM standard, or if 75 percent of the samples from more frequent testing during any 30-day period exceed any SSM standard.

When repeat sampling is required because of an exceedance of any one single sample density, values from all samples collected during that 30-day period will be used to calculate the geometric mean.

- c. It is state policy that the geometric mean bacterial objectives are strongly preferred for use in water body assessment decisions, for example, in developing the CWA Section 303(d) List of impaired waters, because the geometric mean objectives are a more reliable measure of long-term water body conditions. In making assessment decisions on bacterial quality, SSM data must be considered together with any available geometric mean data. The use of only SSM bacterial data is generally inappropriate unless there is a limited data set, the water is subject to short-term spikes in bacterial concentrations, or other circumstances justify the use of only SSM data.

B. Physical Characteristics

1. Floating particulates and grease and oil shall not be visible as a result of wastes discharged.
2. The discharge of waste shall not alter the color of the receiving waters; create a visual contrast with the natural appearance of the water; nor cause aesthetically undesirable discoloration of the ocean surface.
3. Natural light shall not be significantly reduced at any point outside the initial dilution zone as the result of the discharge of waste.
4. The rate of deposition of inert solids and the characteristics of inert solids in ocean sediments shall not be changed such that benthic communities are degraded.

C. Chemical Characteristics

1. The dissolved oxygen concentration shall not at any time be depressed more than 10 percent from that which occurs naturally, as the result of the discharge of oxygen demanding waste materials; excluding effects of naturally induced upwelling.
2. The pH shall not be changed at any time more than 0.2 units from that which occurs naturally.
3. The dissolved sulfide concentration of waters in and near sediments shall not be significantly increased above that present under natural conditions.
4. The concentration of substances set forth in Chapter II, Table 1 of the Ocean Plan, shall not be increased in marine sediments to levels that would degrade indigenous biota.
5. The concentration of organic materials in marine sediments shall not be increased to levels that would degrade marine life.

6. Nutrient materials shall not cause objectionable aquatic growths or degrade indigenous biota.
7. Numerical water quality objectives established in Chapter II, Table 1 of the California Ocean Plan shall not be exceeded outside of the zone of initial dilution as a result of discharges from the Facility.

D. Biological Characteristics

1. Marine communities, including vertebrate, invertebrate, and plant species, shall not be degraded.
2. The natural taste, odor, and color of fish, shellfish, or other marine resources used for human consumption shall not be altered.
3. The concentration of organic materials in fish, shellfish, or other marine resources used for human consumption shall not bioaccumulate to levels that are harmful to human health.

E. Radioactivity

1. Discharge of radioactive waste shall not degrade marine life.

VI. PROVISIONS

A. Standard Provisions

1. **Federal Standard Provisions.** The Discharger shall comply with all Standard Provisions included in Attachment D of this Order.
2. **Regional Water Board Standard Provisions.** The Discharger shall comply with the following provisions. In the event that there is any conflict, duplication, or overlap between provisions specified by this Order, the more stringent provision shall apply:
 - a. This Order may be modified, revoked, reissued, or terminated in accordance with the provisions of 40 C.F.R.sections 122.44, 122.62, 122.63, 122.64, 125.62 and 125.64. Causes for taking such actions include, but are not limited to: failure to comply with any condition of this Order; endangerment to human health or the environment resulting from the permitted activity; or acquisition of newly-obtained information which would have justified the application of different conditions if known at the time of Order adoption. The filing of a request by the Discharger for an Order modification, revocation, and issuance or termination, or a notification of planned changes or anticipated noncompliance does not stay any condition of this Order.
 - b. The Discharger must comply with the lawful requirements of municipalities, counties, drainage districts, and other local agencies regarding discharges of storm water to storm drain systems or other water courses under their jurisdiction; including applicable requirements in the municipal storm water management program developed to comply with NPDES permits issued by the Regional Water Board to local agencies.
 - c. Discharge of wastes to any point other than specifically described in this Order and permit is prohibited and constitutes a violation thereof.
 - d. The Discharger shall comply with all applicable effluent limitations, national standards of performance, toxic effluent standards, and all federal regulations established pursuant to sections 301, 302, 303(d), 304, 306, 307, 316, 318, 405, and 423 of the Federal CWA and amendments thereto.

- e. These requirements do not exempt the operator of the facility from compliance with any other laws, regulations, or ordinances which may be applicable; they do not legalize this waste disposal facility, and they leave unaffected any further restraints on the disposal of wastes at this site which may be contained in other statutes or required by other agencies.
- f. Oil or oily material, chemicals, refuse, or other pollutionable materials shall not be stored or deposited in areas where they may be picked up by rainfall and carried off of the property and/or discharged to surface waters. Any such spill of such materials shall be contained and removed immediately.
- g. A copy of these waste discharge specifications shall be maintained at the control room where the operation of the RSMP is overseen, so as to be available at all times to operating personnel.
- h. After notice and opportunity for a hearing, this Order may be terminated or modified for cause, including, but not limited to:
 - i. Violation of any term or condition contained in this Order;
 - ii. Obtaining this Order by misrepresentation, or failure to disclose all relevant facts;
 - iii. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- i. If there is any storage of hazardous or toxic materials or hydrocarbons at this facility and if the facility is not manned at all times, a 24-hour emergency response telephone number shall be prominently posted where it can easily be read from the outside.
- j. The Discharger shall notify the Regional Water Board not later than 120 days in advance of implementation of any plans to alter production capacity of the product line of the manufacturing, producing or processing facility by more than ten percent. Such notification shall include estimates of proposed production rate, the type of process, and projected effects on effluent quality. Notification shall include submittal of a new Report of Waste Discharge appropriate filing fee.
- k. The Discharger shall file with the Regional Water Board a report of waste discharge at least 120 days before making any material change or proposed change in the character, location or volume of the discharge.
- l. All existing manufacturing, commercial, mining, and silvicultural dischargers must notify the Regional Water Board as soon as they know or have reason to believe that they have begun or expect to begin to use or manufacture an intermediate or final product or byproduct of any toxic pollutant that was not reported on their application.
- m. In the event of any change in name, ownership, or control of the facility, the discharger shall notify this Regional Water Board of the change and shall notify the succeeding owner or operator of the existence of this Order by letter, a copy of which shall be forwarded to the Regional Water Board.
- n. The Water Code provides that any person who violates a waste discharge requirement or a provision of the Water Code is subject to civil penalties of up to \$5,000 per day, \$10,000 per day, or \$25,000 per day of violation, or when the violation involves the discharge of pollutants, is subject to civil penalties of up to \$10

per gallon per day or \$25 per gallon per day of violation; or some combination thereof, depending on the violation, or upon the combination of violations.

- o.** Violation of any of the provisions of the NPDES program or of any of the provisions of this Order may subject the violator to any of the penalties described herein, or any combination thereof, at the discretion of the prosecuting authority; except that only one kind of penalty may be applied for each kind of violation.
- p.** The discharge of any product registered under the Federal Insecticide, Fungicide, and Rodenticide Act to any waste stream which may ultimately be released to waters of the United States, is prohibited unless specifically authorized elsewhere in this permit or another NPDES permit. This requirement is not applicable to products used for lawn and agricultural purposes.
- q.** The discharge of any waste resulting from the combustion of toxic or hazardous wastes to any waste stream that ultimately discharges to waters of the United States is prohibited, unless specifically authorized elsewhere in this permit.
- r.** The Discharger shall notify the Executive Officer in writing no later than 6 months prior to the planned discharge of any chemical, other than the products previously reported to the Executive Officer, which may be toxic to aquatic life. Such notification shall include:

 - i. Name and general composition of the chemical,
 - ii. Frequency of use,
 - iii. Quantities to be used,
 - iv. Proposed discharge concentrations, and
 - v. USEPA registration number, if applicable.
- s.** Failure to comply with provisions or requirements of this Order, or violation of other applicable laws or regulations governing discharges from this facility, may subject the Discharger to administrative or civil liabilities, criminal penalties, and/or other enforcement remedies to ensure compliance. Additionally, certain violations may subject the Discharger to civil or criminal enforcement from appropriate local, state, or federal law enforcement entities.
- t.** In the event the Discharger does not comply or will be unable to comply for any reason, with any prohibition, maximum daily effluent limitation, average weekly effluent limitation, average monthly effluent limitation, instantaneous maximum/minimum effluent limitations, six-month median effluent limitation or receiving water limitation of this Order, the Discharger shall notify the Los Angeles Regional Water Board by telephone (213) 576-6600 within 24 hours of having knowledge of such noncompliance, and shall confirm this notification in writing within five days, unless the Los Angeles Regional Water Board waives confirmation. The written notification shall state the nature, time, duration, and cause of noncompliance, and shall describe the measures being taken to remedy the current noncompliance and, prevent recurrence including, where applicable, a schedule of implementation. Other noncompliance requires written notification as above at the time of the normal monitoring report.

B. Monitoring and Reporting Program (MRP) Requirements

The Discharger shall comply with the MRP, and future revisions thereto, in Attachment E.

C. Special Provisions

1. Reopener Provisions

- a. This Order may be reopened for modification to include an effluent limitation if monitoring establishes that the discharge causes, has the reasonable potential to cause, or contributes to an excursion above the Ocean Plan Table 1 water quality objective.
- b. If more stringent applicable water quality standards are promulgated or approved pursuant to section 303 of the Federal CWA, and amendments thereto, the Regional Water Board will revise and modify this Order in accordance with such more stringent standards.
- c. This Order may be reopened and modified, in accordance with the provisions set forth in Parts 122 and 124, to include requirements for the implementation of the watershed management approach or to include new minimum levels (MLs).
- d. This Order may be reopened and modified to revise effluent limitations as a result of future Ocean Plan Amendments, such as an update of the objectives or the adoption of a TMDL.
- e. This Order may be reopened upon submission by the Discharger of adequate information, as determined by the Regional Water Board, to provide for modifications to dilution credits or the mixing zone, as may be appropriate.
- f. This Order may be reopened and modified, revoked, and reissued or terminated in accordance with the provisions of 40 CFR sections 122.24, 122.62 to 122.64, 125.62, and 125.64. Causes for taking such actions include, but are not limited to, failure to comply with any condition of this Order and permit, or endangerment to human health or the environment resulting from the permitted activity.
- g. This Order may be modified, or revoked and reissued, based on the results of Magnuson-Stevens Conservation and Management Act and/or Endangered Species Act section 7 consultations with the National Marine Fisheries Service and/or the U.S. Fish and Wildlife Service.

2. Special Studies, Technical Reports and Additional Monitoring Requirements

- a. **Initial Investigation Toxicity Reduction Evaluation (TRE) Workplan.** The Discharger shall submit to the Regional Water Board an Initial Investigation TRE workplan (1-2 pages) within **90 days** of the effective date of this permit. This plan shall describe the steps the permittee intends to follow in the event that toxicity is detected. See section V of the Monitoring and Reporting Program (Attachment E) for an overview of Toxicity Reduction Evaluation (TRE) requirements.
- b. **Mixing Zone Study Work Plan.** The Discharger shall develop and submit to the Los Angeles Regional Water Board for review a work plan detailing how the Discharger will conduct a Mixing Zone Study, within **90 days** after the adoption of this permit. The study should include monitoring upstream of the discharge point, directly above the discharge location, at the boundary of the Zone of Initial Dilution as defined using the modeling results, and outside the Zone of Initial Dilution for the list of constituents included in Attachment E, Section VIII.A.1
- c. **Sediment Loading Study Work Plan.** The Discharger shall develop and submit to the Los Angeles Regional Water Board for review a plan detailing how the Discharger will conduct a sediment loading study, within **90 days** after the adoption

of this permit. The study is to monitor the concentrations of constituents present in the sediment inside and outside of the mixing zone. The sampling must target all constituents present in the discharge that bioaccumulate in the tissue of aquatic life that may be present in the area.

3. Best Management Practices and Pollution Prevention

The Discharger shall develop and submit, within **90 days** of the effective date of this Order:

a. An updated Storm Water Pollution Prevention Plan (SWPPP)

The SWPPP shall describe site-specific management practices for minimizing contamination of storm water runoff and for preventing contaminated storm water runoff from being discharged directly to waters of the State. Further, the SWPPP should address erosion and sediment control practices in areas affected by construction and land disturbance activities. The SWPPP shall be developed in accordance with the requirements in Attachment G.

b. An updated Best Management Practice Plan (BMPP)

The BMPP shall entail site-specific procedures implemented and/or to be implemented to prevent the discharge of pollutants in non-storm water discharges. The BMPP shall be site-specific and shall cover all areas of the Facility including connectors and pumping stations. Further, BMPs should address reducing or eliminating pollutants in storm water discharges from construction and land disturbance activities.

The Discharger shall implement their SWPPP and BMPP within 10 days of the approval by the Executive Officer or **no later than 90 days** after submission to the Los Angeles Regional Water Board, whichever comes first. The plans shall be reviewed annually and revised, if necessary, at the same time. Updated information shall be submitted within 30 days of revision.

4. Construction, Operation and Maintenance Specifications

a. The Discharger shall at all times properly operate and maintain all facilities and systems installed or used to achieve compliance with this Order.

5. Other Special Provisions – Not Applicable

6. Compliance Schedules – Not Applicable

VII. COMPLIANCE DETERMINATION

A. Compliance with Effluent Limitations expressed as Single Constituents

If the concentration of the pollutant in the monitoring sample is greater than the effluent limitation and greater than or equal to the reported Minimum Level (see Reporting Requirement I.G. of the MRP), then the Discharger is out of compliance.

B. Compliance with Effluent Limitations expressed as Sum of Several Constituents

Dischargers are out of compliance with an effluent limitation which applies to the sum of a group of chemicals (e.g., PCB's) if the sum of the individual pollutant concentrations is greater than the effluent limitation. Individual pollutants of the group will be considered to have a concentration of zero if the constituent is reported as "Not Detected" (ND) or "Detected, but Not Quantified" (DNQ).

C. Multiple Sample Data Reduction

The concentration of the pollutant in the effluent may be estimated from the result of a single sample analysis or by a measure of central tendency (arithmetic mean, geometric mean, median, etc.) of multiple sample analyses when all sample results are quantifiable (i.e., greater than or equal to the reported Minimum Level). When one or more sample results are reported as ND or DNQ, the central tendency concentration of the pollutant shall be the median (middle) value of the multiple samples, where DNQ is lower than a quantified value and ND is lower than DNQ. If, in an even number of samples, one or both of the middle values is ND or DNQ, the median will be the lower of the two middle values.

D. Average Monthly Effluent Limitation (AMEL)

If the average of daily discharges over a calendar month exceeds the AMEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for each day of that month for that parameter (e.g., resulting in 31 days of non-compliance in a 31-day month). However, an alleged violation of the AMEL will be considered one violation for the purpose of assessing mandatory minimum penalties. The average of daily discharges over a calendar month that exceeds the AMEL for a parameter will be considered out of compliance for that month only. If only a single sample (daily discharge) is taken over a calendar month and the analytical result for that sample exceeds the AMEL, the Discharger will be considered out of compliance for that month. If no sample (daily discharge) is taken over a calendar month, no compliance determination can be made for that month with respect to effluent violation determination, but compliance determination can be made for that month with respect to reporting violation determination.

In determining compliance with the AMEL, the following provisions shall also apply to all constituents:

1. If the analytical result of a single sample, monitored monthly, quarterly, semiannually, or annually, does not exceed the AMEL for that constituent, the Discharger has demonstrated compliance with the AMEL for that month;
2. If the analytical result of a single sample, monitored monthly, quarterly, semiannually, or annually, exceeds the AMEL for any constituent, the Discharger shall collect four additional samples at approximately equal intervals during the month. All five analytical results shall be reported in the monitoring report for that month, or 45 days after results for the additional samples were received, whichever is later.

When all sample results are greater than or equal to the reported Minimum Level (see Reporting Requirement I.G. of the MRP), the numerical average of the analytical results of these five samples will be used for compliance determination.

When one or more sample results are reported as “Not-Detected (ND)” or “Detected, but Not Quantified (DNQ)” (see Reporting Requirement I.G. of the MRP), the median value of these four samples shall be used for compliance determination. If one or both of the middle values is ND or DNQ, the median shall be the lower of the two middle values.

In the event of noncompliance with an AMEL, the sampling frequency for that constituent shall be increased to weekly and shall continue at this level until compliance with the AMEL has been demonstrated.

3. If only one sample was obtained for the month or more than a monthly period and the result exceeds the AMEL, then the Discharger is in violation of the AMEL.

E. Average Weekly Effluent Limitation (AWEL)

If the average of daily discharges over a calendar week exceeds the AWEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for each day of that week for that parameter (e.g., resulting in seven days of non-compliance). However, an alleged violation of the AWEL will be considered one violation for the purpose of assessing mandatory minimum penalties. The average of daily discharges over a calendar week that exceeds the AWEL for a parameter will be considered out of compliance for that week only. If only a single sample (daily discharge) is taken over a calendar week and the analytical result for that sample exceeds the AWEL, the Discharger will be considered out of compliance for that week. If no sample (daily discharge) is taken over a calendar week, no compliance determination can be made for that week with respect to effluent violation determination, but compliance determination can be made for that week with respect to reporting violation determination.

A calendar week will begin on Sunday and end on Saturday. Partial calendar weeks at the end of the calendar month will be carried forward to the next month in order to calculate and report a consecutive seven-day average value on Saturday.

F. Maximum Daily Effluent Limitation (MDEL)

If a daily discharge on a calendar day exceeds the MDEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for that day for that parameter. If no sample (daily discharge) is taken over a calendar day, no compliance determination can be made for that day with respect to an effluent violation determination, but compliance determination can be made for that day with respect to reporting violation determination.

G. Instantaneous Minimum Effluent Limitation

If the analytical result of a single grab sample is lower than the instantaneous minimum effluent limitation for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for that single sample for that parameter. Non-compliance for each single grab sample will be considered separately (e.g., the analytical results of two grab samples taken over a calendar day that are lower than the instantaneous minimum effluent limitation would result in two instances of non-compliance with the instantaneous minimum effluent limitation).

H. Instantaneous Maximum Effluent Limitation

If the analytical result of a single grab sample exceeds (is higher than) the instantaneous maximum effluent limitation for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for that single sample for that parameter. Non-compliance for each single grab sample will be considered separately (e.g., the analytical results of two grab samples taken over a calendar day that both are higher than the instantaneous maximum effluent limitation would result in two instances of non-compliance with the instantaneous maximum effluent limitation).

I. Six-Month Median Effluent Limitation

If the median of daily discharges over any 180-day period exceeds the six-month median effluent limitation for a given parameter, an alleged violation will be flagged and the discharger will be considered out of compliance for each day of that 180-day period for that parameter. The next assessment of compliance will occur after the next sample is taken. If only a single sample is taken during a given 180-day period and the analytical result for that sample exceeds the six-month median, the discharger will be considered out of compliance

for the 180-day period. For any 180-period during which no sample is taken, no compliance determination can be made for the six-month median limitation.

The six-month median shall apply as a moving median of daily values for any 180-day period in which daily values represent flow weighted average concentrations within a 24-hour period. For intermittent discharges, the daily value shall be considered to equal zero for days on which no discharge occurred. If only one sample is collected during the time period associated with the 6-month median water quality objective, the single measurement shall be used to determine compliance with the effluent limitation for the entire time period.

J. Median Monthly Effluent Limitation (MMEL)

If the median of daily discharges over a calendar month exceeds the MMEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for each day of that month for that parameter (e.g., resulting in 31 days of non-compliance in a 31-day month). However, an alleged violation of the MMEL will be considered one violation for the purpose of assessing State mandatory minimum penalties. If no sample (daily discharge) is taken over a calendar month, no compliance determination can be made for that month with respect to effluent violation determination, but compliance determination can be made for that month with respect to reporting violation determination.

K. Chronic Toxicity

The discharge is subject to determination of “Pass” or “Fail” and “Percent Effect” from a single-effluent concentration chronic toxicity test at the discharge IWC using the Test of Significant Toxicity (TST) approach described in *National Pollutant Discharge Elimination System Test of Significant Toxicity Implementation Document* (EPA 833-R-10-003, 2010), Appendix A, Figure A-1, and Table A-1. The null hypothesis (H_0) for the TST approach is: Mean discharge IWC response $\leq 0.75 \times$ Mean control response. A test result that rejects this null hypothesis is reported as “Pass”. A test result that does not reject this null hypothesis is reported as “Fail”. The relative “Percent Effect” at the discharge IWC is defined and reported as: $((\text{Mean control response} - \text{Mean discharge IWC response}) \div \text{Mean control response}) \times 100$.

The Maximum Daily Effluent Limitation (MDEL) for chronic toxicity is exceeded and a violation will be flagged when a chronic toxicity test, analyzed using the TST approach, results in “Fail” and the “Percent Effect” is ≥ 0.50 .

The Median Monthly Effluent Limitation (MMEL) for chronic toxicity is exceeded and a violation will be flagged when the median of no more than three independent chronic toxicity tests, conducted within the same calendar month and analyzed using the TST approach, results in “Fail”. The MMEL for chronic toxicity shall only apply when there is a discharge more than one day in a calendar month period. During such calendar months, exactly three independent toxicity tests are required when one toxicity test results in “Fail”.

L. Mass and Concentration Limitations

Compliance with mass effluent limitations and concentration effluent limitations for the same parameter shall be determined separately. When the concentration for a parameter in a sample is reported as ND or DNQ, the corresponding mass emission rate determined using that sample concentration shall also be reported as ND or DNQ.

M. Bacterial Standards and Analyses

The geometric mean used for determining compliance with bacterial standards is calculated using the following equation:

$$\text{Geometric Mean} = (C_1 \times C_2 \times \dots \times C_n)^{1/n}$$

where n is the number of days samples were collected during the period and C is the concentration of bacteria (MPN/100 mL or CFU/100 mL) found on each day of sampling.

For bacterial analyses, sample dilutions should be performed so the expected range of values is bracketed (for example, with multiple tube fermentation method or membrane filtration method, 2 to 16,000 per 100 mL for total and fecal coliform, at a minimum, and 1 to 1000 per 100 mL for *Enterococcus*). The detection method used for each analysis shall be reported with the results of the analysis.

Detection methods used for coliforms (total and fecal) and *Enterococcus* shall be those presented in Table 1A of 40 CFR section 136 (revised May 18, 2012), unless alternate methods have been approved by USEPA pursuant to 40 CFR section 136, or improved methods have been determined by the Executive Officer and/or USEPA.

ATTACHMENT A – DEFINITIONS

Acute Toxicity

- a. Acute Toxicity
Expressed in Toxic Units Acute (TUa)

$$TUa = \frac{100}{96\text{-hr LC } 50\%}$$

- b. Lethal Concentration 50% (LC 50)
LC 50 (percent waste giving 50% survival of test organisms) shall be determined by static or continuous flow bioassay techniques using standard marine test species as specified in Ocean Plan Appendix III. If specific identifiable substances in wastewater can be demonstrated by the discharger as being rapidly rendered harmless upon discharge to the marine environment, but not as a result of dilution, the LC 50 may be determined after the test samples are adjusted to remove the influence of those substances.

When it is not possible to measure the 96-hour LC 50 due to greater than 50 percent survival of the test species in 100 percent waste, the toxicity concentration shall be calculated by the expression:

$$TUa = \frac{\log(100 - S)}{1.7}$$

where:

S = percentage survival in 100% waste. If S > 99, TUa shall be reported as zero.

Areas of Special Biological Significance (ASBS)

Those areas designated by the State Water Resources Control Board (State Water Board) as ocean areas requiring protection of species or biological communities to the extent that alteration of natural water quality is undesirable. All Areas of Special Biological Significance are also classified as a subset of STATE WATER QUALITY PROTECTION AREAS.

Average Monthly Effluent Limitation (AMEL)

The highest allowable average of daily discharges over a calendar month, calculated as the sum of all daily discharges measured during a calendar month divided by the number of daily discharges measured during that month.

Average Weekly Effluent Limitation (AWEL)

The highest allowable average of daily discharges over a calendar week (Sunday through Saturday), calculated as the sum of all daily discharges measured during a calendar week divided by the number of daily discharges measured during that week.

Best Management Practices (BMPs)

BMPs are methods, measures, or practices designed and selected to reduce or eliminate the discharge of pollutants to surface waters from point and nonpoint source discharges including storm water. BMPs include structural and non-structural control, and operation maintenance procedures, which can be applied before, during, and/or after pollution-producing activities.

Chlorinated Phenolic Compounds

Chlorinated Phenolic Compounds shall mean, at a minimum, the sum of 2-Chlorophenol, 2,4-Dichlorophenol, 4-Chloro-3-methylphenol, 2,4,6-Trichlorophenol, and Pentachlorophenol.

Chlordane

Shall mean the sum of chlordane-alpha, chlordane-gamma, chlordene-alpha, chlordene-gamma, nonachlor-alpha, nonachlor-gamma, and oxychlordane.

Chronic Toxicity

This parameter shall be used to measure the acceptability of waters for supporting a healthy marine biota until improved methods are developed to evaluate biological response.

- a. Chronic Toxicity (TUc)
Expressed as Toxic Units Chronic (TUc)

$$TUc = \frac{100}{NOEL}$$

- b. No Observed Effect Level (NOEL)

The NOEL is expressed as the maximum percent effluent or receiving water that causes no observable effect on a test organism, as determined by the result of a critical life stage toxicity test listed in Ocean Plan Appendix II.

Coefficient of Variation (CV)

CV is a measure of the data variability and is calculated as the estimated standard deviation divided by the arithmetic mean of the observed values.

Composite Sample

Composite Sample, for flow rate measurements, means the arithmetic mean of no fewer than eight individual measurements taken at equal intervals for 24 hours or for the duration of discharge, whichever is shorter.

Composite sample, for other than flow rate measurement, means:

- a. No fewer than eight individual sample portions taken at equal time intervals for 24 hours, or the duration of the discharge, whichever is shorter. The volume of each individual sample portion shall be directly proportional to the discharge flow rate at the time of sampling; or,
- b. No fewer than eight individual sample portions taken of equal time volume taken over a 24 hour period. The time interval between each individual sample portion shall vary such that the volume of the discharge between each individual sample portion remains constant.

The compositing period shall equal the specified sampling period, or 24 hours, if no period is specified.

For a composite sample, if the duration of the discharge is less than 24 hours but greater than 8 hours, at least eight flow-weighted individual sample portions shall be taken during the duration of the discharge and composited. For a discharge duration of 8 hours or less, eight individual "grab samples" may be substituted and composited.

The composite sample result shall be reported for the calendar day during which composite sampling ends.

Daily Discharge

Daily Discharge is defined as either: (1) the total mass of the constituent discharged over the calendar day (12:00 am through 11:59 pm) or any 24-hour period that reasonably represents a calendar day for purposes of sampling (as specified in the permit), for a constituent with limitations expressed in units of mass or; (2) the unweighted arithmetic mean measurement of the constituent over the day for a constituent with limitations expressed in other units of measurement (e.g., concentration).

The daily discharge may be determined by the analytical results of a composite sample taken over the course of one day (a calendar day or other 24-hour period defined as a day) or by the arithmetic mean of analytical results from one or more grab samples taken over the course of the day.

For composite sampling, if 1 day is defined as a 24-hour period other than a calendar day, the analytical result for the 24-hour period will be considered as the result for the calendar day in which the 24-hour period ends.

DDT

Shall mean the sum of 4,4'DDT, 2,4'DDT, 4,4'DDE, 2,4'DDE, 4,4'DDD, and 2,4'DDD.

Degrade (Degradation)

Degradation shall be determined by comparison of the waste field and reference site(s) for characteristic species diversity, population density, contamination, growth anomalies, debility, or supplanting of normal species by undesirable plant and animal species. Degradation occurs if there are significant differences in any of three major biotic groups, namely, demersal fish, benthic invertebrates, or attached algae. Other groups may be evaluated where benthic species are not affected, or are not the only ones affected.

Detected, but Not Quantified (DNQ)

Sample results that are less than the reported Minimum Level, but greater than or equal to the laboratory's MDL. Sample results reported as DNQ are estimated concentrations.

Dichlorobenzenes

Shall mean the sum of 1,2- and 1,3-dichlorobenzene.

Downstream Ocean Waters

Waters downstream with respect to ocean currents.

Dredged Material

Any material excavated or dredged from the navigable waters of the United States, including material otherwise referred to as "spoil."

Enclosed Bays

Indentations along the coast that enclose an area of oceanic water within distinct headlands or harbor works. Enclosed bays include all bays where the narrowest distance between headlands or outermost harbor works is less than 75 percent of the greatest dimension of the enclosed portion of the bay. This definition includes but is not limited to: Humboldt Bay, Bodega Harbor, Tomales Bay, Drakes Estero, San Francisco Bay, Morro Bay, Los Angeles Harbor, Upper and Lower Newport Bay, Mission Bay, and San Diego Bay.

Endosulfan

The sum of endosulfan-alpha and -beta and endosulfan sulfate.

Estuaries and Coastal Lagoons

Estuaries and Coastal Lagoons are waters at the mouths of streams that serve as mixing zones for fresh and ocean waters during a major portion of the year. Mouths of streams that are temporarily separated from the ocean by sandbars shall be considered as estuaries. Estuarine waters will generally be considered to extend from a bay or the open ocean to the upstream limit of tidal action but may be considered to extend seaward if significant mixing of fresh and salt water occurs in the open coastal waters. The waters described by this definition include but are not limited to the Sacramento-San Joaquin Delta as defined by Section 12220 of the California Water Code, Suisun Bay, Carquinez Strait downstream to Carquinez Bridge, and appropriate areas of the Smith, Klamath, Mad, Eel, Noyo, and Russian Rivers.

Grab Sample

Grab Sample means an individual sample collected during a period of time not to exceed 15 minutes. Grab samples shall be collected during normal peak loading conditions for the parameter of interest, which may or may not occur during hydraulic peaks.

Halomethanes

Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide) and chloromethane (methyl chloride).

HCH

HCH shall mean the sum of the alpha, beta, gamma (lindane) and delta isomers of hexachlorocyclohexane.

Initial Dilution

The process that results in the rapid and irreversible turbulent mixing of wastewater with ocean water around the point of discharge.

For a submerged buoyant discharge, characteristic of most municipal and industrial wastes that are released from the submarine outfalls, the momentum of the discharge and its initial buoyancy act together to produce turbulent mixing. Initial dilution in this case is completed when the diluting wastewater ceases to rise in the water column and first begins to spread horizontally.

For shallow water submerged discharges, surface discharges, and non-buoyant discharges, characteristic of cooling water wastes and some individual discharges, turbulent mixing results primarily from the momentum of discharge. Initial dilution, in these cases, is considered to be completed when the momentum induced velocity of the discharge ceases to produce significant mixing of the waste, or the diluting plume reaches a fixed distance from the discharge to be specified by the Los Angeles Regional Water Board, whichever results in the lower estimate for initial dilution.

Instantaneous Maximum Effluent Limitation

The highest allowable value for any single grab sample or aliquot (i.e., each grab sample or aliquot is independently compared to the instantaneous maximum limitation).

Instantaneous Minimum Effluent Limitation

The lowest allowable value for any single grab sample or aliquot (i.e., each grab sample or aliquot is independently compared to the instantaneous minimum limitation).

Kelp Beds

For purposes of the bacteriological standards of the Ocean Plan, are significant aggregations of marine algae of the genera Macrocystis and Nereocystis. Kelp beds include the total foliage canopy of Macrocystis and Nereocystis plants throughout the water column.

Mariculture

The culture of plants and animals in marine waters independent of any pollution source.

Material

(a) In common usage: (1) the substance or substances of which a thing is made or composed (2) substantial; (b) For purposes of the Ocean Plan relating to waste disposal, dredging and the disposal of dredged material and fill, MATERIAL means matter of any kind or description which is subject to regulation as waste, or any material dredged from the navigable waters of the United States. See also, DREDGED MATERIAL.

Maximum Daily Effluent Limitation (MDEL)

The highest allowable daily discharge of a pollutant.

Median

The middle measurement in a set of data. The median of a set of data is found by first arranging the measurements in order of magnitude (either increasing or decreasing order). If the number of measurements (n) is odd, then the median = $X_{(n+1)/2}$. If n is even, then the median = $(X_{n/2} + X_{(n/2)+1})/2$ (i.e., the midpoint between the $n/2$ and $n/2+1$).

Method Detection Limit (MDL)

The minimum concentration of a substance that can be measured and reported with 99 percent confidence that the analyte concentration is greater than zero, as defined in 40 C.F.R. part 136, Attachment B.

Minimum Level (ML)

The concentration at which the entire analytical system must give a recognizable signal and acceptable calibration point. The ML is the concentration in a sample that is equivalent to the concentration of the lowest calibration standard analyzed by a specific analytical procedure, assuming that all the method specified sample weights, volumes, and processing steps have been followed.

Mixing Zone

Mixing Zone is a limited volume of receiving water that is allocated for mixing with a wastewater discharge where water quality criteria can be exceeded without causing adverse effects to the overall water body.

Natural Light

Reduction of natural light may be determined by the Los Angeles Regional Water Board by measurement of light transmissivity or total irradiance, or both, according to the monitoring needs of the Los Angeles Regional Water Board.

Not Detected (ND)

Those sample results less than the laboratory's MDL.

Ocean Waters

The territorial marine waters of the state as defined by California law to the extent these waters are outside of enclosed bays, estuaries, and coastal lagoons. If a discharge outside the territorial waters of the state could affect the quality of the waters of the state, the discharge may be regulated to assure no violation of the Ocean Plan will occur in ocean waters.

PAHs (polynuclear aromatic hydrocarbons)

The sum of acenaphthylene, anthracene, 1,2-benzanthracene, 3,4-benzofluoranthene, benzo[k]fluoranthene, 1,12-benzoperylene, benzo[a]pyrene, chrysene, dibenzo[ah]anthracene, fluorene, indeno[1,2,3-cd]pyrene, phenanthrene and pyrene.

PCBs (polychlorinated biphenyls)

The sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254 and Aroclor-1260.

Persistent Pollutants

Persistent pollutants are substances for which degradation or decomposition in the environment is nonexistent or very slow.

Pollutant Minimization Program (PMP)

PMP means waste minimization and pollution prevention actions that include, but are not limited to, product substitution, waste stream recycling, alternative waste management methods, and education of the public and businesses. The goal of the PMP shall be to reduce all potential sources of a priority pollutant(s) through pollutant minimization (control) strategies, including pollution prevention measures as appropriate, to maintain the effluent concentration at or below the water quality-based effluent limitation. Pollution prevention measures may be particularly appropriate for persistent bioaccumulative priority pollutants where there is evidence that beneficial uses are being impacted. The Regional Water Board may consider cost effectiveness when establishing the requirements of a PMP. The completion and implementation of a Pollution Prevention Plan, if required pursuant to Water Code section 13263.3(d), shall be considered to fulfill the PMP requirements.

Reported Minimum Level

The reported ML (also known as the Reporting Level or RL) is the ML (and its associated analytical method) chosen by the Discharger for reporting and compliance determination from the MLs included in this Order, including an additional factor if applicable as discussed herein. The MLs included in this Order correspond to approved analytical methods for reporting a sample result that are selected by the Los Angeles Regional Water Board either from Appendix II of the Ocean Plan in accordance with section III.C.5.a. of the Ocean Plan or established in accordance with section III.C.5.b. of the Ocean Plan. The ML is based on the proper application of method-based analytical procedures for sample preparation and the absence of any matrix interferences. Other factors may be applied to the ML depending on the specific sample preparation steps employed. For example, the treatment typically applied in cases where there are matrix-effects is to dilute the sample or sample aliquot by a factor of ten. In such cases, this additional factor must be applied to the ML in the computation of the reported ML.

Shellfish

Organisms identified by the California Department of Public Health as shellfish for public health purposes (i.e., mussels, clams and oysters).

Significant Difference

Defined as a statistically significant difference in the means of two distributions of sampling results at the 95 percent confidence level.

Six-Month Median Effluent Limitation

The highest allowable moving median of all daily discharges for any 180-day period.

State Water Quality Protection Areas (SWQPAs)

Non-terrestrial marine or estuarine areas designated to protect marine species or biological communities from an undesirable alteration in natural water quality. All AREAS OF SPECIAL BIOLOGICAL SIGNIFICANCE (ASBS) that were previously designated by the State Water Board in Resolution No.s 74-28, 74-32, and 75-61 are now also classified as a subset of State Water Quality Protection Areas and require special protections afforded by the Ocean Plan.

TCDD Equivalentents

The sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown in the table below.

| Isomer Group | Toxicity Equivalence Factor |
|---------------------|-----------------------------|
| 2,3,7,8-tetra CDD | 1.0 |
| 2,3,7,8-penta CDD | 0.5 |
| 2,3,7,8-hexa CDDs | 0.1 |
| 2,3,7,8-hepta CDD | 0.01 |
| octa CDD | 0.001 |
| 2,3,7,8 tetra CDF | 0.1 |
| 1,2,3,7,8 penta CDF | 0.05 |
| 2,3,4,7,8 penta CDF | 0.5 |
| 2,3,7,8 hexa CDFs | 0.1 |
| 2,3,7,8 hepta CDFs | 0.01 |
| octa CDF | 0.001 |

Toxicity Reduction Evaluation (TRE)

A study conducted in a step-wise process designed to identify the causative agents of effluent or ambient toxicity, isolate the sources of toxicity, evaluate the effectiveness of toxicity control options, and then confirm the reduction in toxicity. The first steps of the TRE consist of the collection of data relevant to the toxicity, including additional toxicity testing, and an evaluation of facility operations and maintenance practices, and best management practices. A Toxicity Identification Evaluation (TIE) may be required as part of the TRE, if appropriate. (A TIE is a set of procedures to identify the specific chemical(s) responsible for toxicity. These procedures are performed in three phases (characterization, identification, and confirmation) using aquatic organism toxicity tests.)

Waste

As used in the Ocean Plan, waste includes a Discharger's total discharge, of whatever origin, i.e., gross, not net, discharge.

Water Quality-Based Effluent Limit (WQBEL)

A value determined by selecting the most stringent of the effluent limits calculated using all applicable water quality criteria (e.g., aquatic life, human health, and wildlife) for a specific point source to a specific receiving water for a given pollutant.

Water Quality Criteria

Comprised of numeric and narrative criteria. Numeric criteria are scientifically derived ambient concentrations developed by USEPA or States for various pollutants of concern to protect human health and aquatic life. Narrative criteria are statements that describe the desired water quality goal.

Water Quality Standard

A law or regulation that consists of the beneficial use or uses of a waterbody, the numeric and narrative water quality criteria that are necessary to protect the use or uses of that particular waterbody, and an antidegradation statement.

Whole Effluent Toxicity (WET)

The total toxic effect of an effluent measured directly with a toxicity test.

Zone of Initial Dilution (ZID)

Zone of Initial Dilution (ZID) means, for purposes of designating monitoring stations, the region within a horizontal distance equal to a specified water depth (usually depth of outfall or average depth of diffuser) from any point of the diffuser or end of the outfall and the water column above and below that region, including the underlying seabed.

Water Recycling


The treatment of wastewater to render it suitable for reuse, the transportation of treated wastewater to the place of use, and the actual use of treated wastewater for a direct beneficial use or controlled use that would not otherwise occur.

ACRONYMS AND ABBREVIATIONS


| | |
|------------------|---|
| AMEL | Average Monthly Effluent Limitation |
| B | Background Concentration |
| BAT | Best Available Technology Economically Achievable |
| Basin Plan | Water Quality Control Plan for the Coastal Watersheds of Los Angeles and Ventura Counties |
| BCT | Best Conventional Pollutant Control Technology |
| BMP | Best Management Practices |
| BMPP | Best Management Practices Plan |
| BPJ | Best Professional Judgment |
| BOD | Biochemical Oxygen Demand 5-day @ 20 °C |
| BPT | Best Practicable Treatment Control Technology |
| C | Water Quality Objective |
| CCR | California Code of Regulations |
| CEQA | California Environmental Quality Act |
| CFR | Code of Federal Regulations |
| CTR | California Toxics Rule |
| CV | Coefficient of Variation |
| CWA | Clean Water Act |
| CWC | California Water Code |
| Discharger | Calleguas Municipal Water District |
| DMR | Discharge Monitoring Report |
| DNQ | Detected But Not Quantified |
| ELAP | California Department of Public Health Environmental Laboratory Accreditation Program |
| ELG | Effluent Limitations, Guidelines and Standards |
| Facility | Regional Salinity Management Pipeline (RSMP) |
| g/kg | grams per kilogram |
| gpd | gallons per day |
| IC | Inhibition Coefficient |
| IC ₁₅ | Concentration at which the organism is 15% inhibited |
| IC ₂₅ | Concentration at which the organism is 25% inhibited |
| IC ₄₀ | Concentration at which the organism is 40% inhibited |
| IC ₅₀ | Concentration at which the organism is 50% inhibited |
| LA | Load Allocations |
| LOEC | Lowest Observed Effect Concentration |
| µg/L | micrograms per Liter |
| mg/L | milligrams per Liter |
| MDEL | Maximum Daily Effluent Limitation |
| MEC | Maximum Effluent Concentration |
| MGD | Million Gallons Per Day |
| ML | Minimum Level |
| MRP | Monitoring and Reporting Program |
| ND | Not Detected |
| ng/L | nanograms per liter |
| NOEC | No Observable Effect Concentration |
| NPDES | National Pollutant Discharge Elimination System |
| NSPS | New Source Performance Standards |
| NTR | National Toxics Rule |
| OAL | Office of Administrative Law |

| | |
|----------------------------------|---|
| PAHs | Polynuclear Aromatic Hydrocarbons |
| pg/L | picograms per liter |
| PMEL | Proposed Maximum Daily Effluent Limitation |
| PMP | Pollutant Minimization Plan |
| POTW | Publicly Owned Treatment Works |
| ppm | parts per million |
| ppb | parts per billion |
| QA | Quality Assurance |
| QA/QC | Quality Assurance/Quality Control |
| Ocean Plan | Water Quality Control Plan for Ocean Waters of California |
| Los Angeles Regional Water Board | California Regional Water Quality Control Board, Los Angeles Region |
| RPA | Reasonable Potential Analysis |
| SCP | Spill Contingency Plan |
| SIP | State Implementation Policy (Policy for Implementation of Toxics Standards for Inland Surface Waters, Enclosed Bays, and Estuaries of California) |
| SMR | Self-Monitoring Reports |
| State Water Board | California State Water Resources Control Board |
| SWPPP | Storm Water Pollution Prevention Plan |
| TAC | Test Acceptability Criteria |
| Thermal Plan | Water Quality Control Plan for Control of Temperature in the Coastal and Interstate Water and Enclosed Bays and Estuaries of California |
| TIE | Toxicity Identification Evaluation |
| TMDL | Total Maximum Daily Load |
| TOC | Total Organic Carbon |
| TRE | Toxicity Reduction Evaluation |
| TSD | Technical Support Document |
| TSS | Total Suspended Solid |
| TU _c | Chronic Toxicity Unit |
| USEPA | United States Environmental Protection Agency |
| WDR | Waste Discharge Requirements |
| WET | Whole Effluent Toxicity |
| WLA | Waste Load Allocations |
| WQBELs | Water Quality-Based Effluent Limitations |
| WQS | Water Quality Standards |
| % | Percent |

ATTACHMENT B – MAP



ATTACHMENT C – FLOW SCHEMATIC



Salinity Management Pipeline

ATTACHMENT D – STANDARD PROVISIONS

I. STANDARD PROVISIONS – PERMIT COMPLIANCE

A. Duty to Comply

1. The Discharger must comply with all of the conditions of this Order. Any noncompliance constitutes a violation of the Clean Water Act (CWA) and the California Water Code and is grounds for enforcement action, for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application. (40 C.F.R. § 122.41(a).)
2. The Discharger shall comply with effluent standards or prohibitions established under Section 307(a) of the CWA for toxic pollutants and with standards for sewage sludge use or disposal established under Section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions, even if this Order has not yet been modified to incorporate the requirement. (40 C.F.R. § 122.41(a)(1).)

B. Need to Halt or Reduce Activity Not a Defense

It shall not be a defense for a Discharger in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this Order. (40 C.F.R. § 122.41(c).)

C. Duty to Mitigate

The Discharger shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this Order that has a reasonable likelihood of adversely affecting human health or the environment. (40 C.F.R. § 122.41(d).)

D. Proper Operation and Maintenance

The Discharger shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Discharger to achieve compliance with the conditions of this Order. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities or similar systems that are installed by a Discharger only when necessary to achieve compliance with the conditions of this Order. (40 C.F.R. § 122.41(e).)

E. Property Rights

1. This Order does not convey any property rights of any sort or any exclusive privileges. (40 C.F.R. § 122.41(g).)
2. The issuance of this Order does not authorize any injury to persons or property or invasion of other private rights, or any infringement of state or local law or regulations. (40 C.F.R. § 122.5(c).)

F. Inspection and Entry

The Discharger shall allow the Los Angeles Regional Water Board, State Water Board, U.S. EPA, and/or their authorized representatives (including an authorized contractor acting as their representative), upon the presentation of credentials and other documents, as may be required by law, to (40 C.F.R. § 122.41(i); Wat. Code, § 13383):

1. Enter upon the Discharger's premises where a regulated facility or activity is located or conducted, or where records are kept under the conditions of this Order (40 C.F.R. § 122.41(i)(1));

2. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Order (40 C.F.R. § 122.41(i)(2));
3. Inspect and photograph, at reasonable times, any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Order (40 C.F.R. § 122.41(i)(3)); and
4. Sample or monitor, at reasonable times, for the purposes of assuring Order compliance or as otherwise authorized by the CWA or the Water Code, any substances or parameters at any location. (40 C.F.R. § 122.41(i)(4).)

G. Bypass

1. Definitions
 - a. “Bypass” means the intentional diversion of waste streams from any portion of a treatment facility. (40 C.F.R. § 122.41(m)(1)(i).)
 - b. “Severe property damage” means substantial physical damage to property, damage to the treatment facilities, which causes them to become inoperable, or substantial and permanent loss of natural resources that can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production. (40 C.F.R. § 122.41(m)(1)(ii).)
2. Bypass not exceeding limitations. The Discharger may allow any bypass to occur which does not cause exceedances of effluent limitations, but only if it is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions listed in Standard Provisions – Permit Compliance I.G.3, I.G.4, and I.G.5 below. (40 C.F.R. § 122.41(m)(2).)
3. Prohibition of bypass. Bypass is prohibited, and the Los Angeles Regional Water Board may take enforcement action against a Discharger for bypass, unless (40 C.F.R. § 122.41(m)(4)(i)):
 - a. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage (40 C.F.R. § 122.41(m)(4)(i)(A));
 - b. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance (40 C.F.R. § 122.41(m)(4)(i)(B)); and
 - c. The Discharger submitted notice to the Los Angeles Regional Water Board as required under Standard Provisions – Permit Compliance I.G.5 below. (40 C.F.R. § 122.41(m)(4)(i)(C).)
4. The Los Angeles Regional Water Board may approve an anticipated bypass, after considering its adverse effects, if the Los Angeles Regional Water Board determines that it will meet the three conditions listed in Standard Provisions – Permit Compliance I.G.3 above. (40 C.F.R. § 122.41(m)(4)(ii).)
5. Notice
 - a. Anticipated bypass. If the Discharger knows in advance of the need for a bypass, it shall submit a notice, if possible at least 10 days before the date of the bypass. (40 C.F.R. § 122.41(m)(3)(i).)

- b. Unanticipated bypass. The Discharger shall submit notice of an unanticipated bypass as required in Standard Provisions - Reporting V.E below (24-hour notice). (40 C.F.R. § 122.41(m)(3)(ii).)

H. Upset

Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the Discharger. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation. (40 C.F.R. § 122.41(n)(1).)

1. Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of Standard Provisions – Permit Compliance I.H.2 below are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review. (40 C.F.R. § 122.41(n)(2).)
2. Conditions necessary for a demonstration of upset. A Discharger who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that (40 C.F.R. § 122.41(n)(3)):
 - a. An upset occurred and that the Discharger can identify the cause(s) of the upset (40 C.F.R. § 122.41(n)(3)(i));
 - b. The permitted facility was, at the time, being properly operated (40 C.F.R. § 122.41(n)(3)(ii));
 - c. The Discharger submitted notice of the upset as required in Standard Provisions – Reporting V.E.2.b below (24-hour notice) (40 C.F.R. § 122.41(n)(3)(iii)); and
 - d. The Discharger complied with any remedial measures required under Standard Provisions – Permit Compliance I.C above. (40 C.F.R. § 122.41(n)(3)(iv).)
3. Burden of proof. In any enforcement proceeding, the Discharger seeking to establish the occurrence of an upset has the burden of proof. (40 C.F.R. § 122.41(n)(4).)

II. STANDARD PROVISIONS – PERMIT ACTION

A. General

This Order may be modified, revoked and reissued, or terminated for cause. The filing of a request by the Discharger for modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any Order condition. (40 C.F.R. § 122.41(f).)

B. Duty to Reapply

If the Discharger wishes to continue an activity regulated by this Order after the expiration date of this Order, the Discharger must apply for and obtain a new permit. (40 C.F.R. § 122.41(b).)

C. Transfers

This Order is not transferable to any person except after notice to the Los Angeles Regional Water Board. The Los Angeles Regional Water Board may require modification or revocation

and reissuance of the Order to change the name of the Discharger and incorporate such other requirements as may be necessary under the CWA and the Water Code. (40 C.F.R. § 122.41(l)(3); § 122.61.)

III. STANDARD PROVISIONS – MONITORING

- A. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity. (40 C.F.R. § 122.41(j)(1).)
- B. Monitoring results must be conducted according to test procedures under 40 C.F.R. part 136 or, in the case of sludge use or disposal, approved under 40 C.F.R. part 136 unless otherwise specified in 40 C.F.R. part 503 unless other test procedures have been specified in this Order. (40 C.F.R. § 122.41(j)(4); § 122.44(i)(1)(iv).)

IV. STANDARD PROVISIONS – RECORDS

- A. Except for records of monitoring information required by this Order related to the Discharger's sewage sludge use and disposal activities, which shall be retained for a period of at least five years (or longer as required by 40 C.F.R. part 503), the Discharger shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this Order, and records of all data used to complete the application for this Order, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the Los Angeles Regional Water Board Executive Officer at any time. (40 C.F.R. § 122.41(j)(2).)
- B. Records of monitoring information shall include:
 - 1. The date, exact place, and time of sampling or measurements (40 C.F.R. § 122.41(j)(3)(i));
 - 2. The individual(s) who performed the sampling or measurements (40 C.F.R. § 122.41(j)(3)(ii));
 - 3. The date(s) analyses were performed (40 C.F.R. § 122.41(j)(3)(iii));
 - 4. The individual(s) who performed the analyses (40 C.F.R. § 122.41(j)(3)(iv));
 - 5. The analytical techniques or methods used (40 C.F.R. § 122.41(j)(3)(v)); and
 - 6. The results of such analyses. (40 C.F.R. § 122.41(j)(3)(vi).)
- C. Claims of confidentiality for the following information will be denied (40 C.F.R. § 122.7(b)):
 - 1. The name and address of any permit applicant or Discharger (40 C.F.R. § 122.7(b)(1)); and
 - 2. Permit applications and attachments, permits and effluent data. (40 C.F.R. § 122.7(b)(2).)

V. STANDARD PROVISIONS – REPORTING

A. Duty to Provide Information

The Discharger shall furnish to the Los Angeles Regional Water Board, State Water Board, or U.S. EPA within a reasonable time, any information which the Los Angeles Regional Water Board, State Water Board, or U.S. EPA may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this Order or to determine compliance with this Order. Upon request, the Discharger shall also furnish to the Los Angeles Regional Water

Board, State Water Board, or U.S. EPA copies of records required to be kept by this Order. (40 C.F.R. § 122.41(h); Wat. Code, § 13267.)

B. Signatory and Certification Requirements

1. All applications, reports, or information submitted to the Los Angeles Regional Water Board, State Water Board, and/or U.S. EPA shall be signed and certified in accordance with Standard Provisions – Reporting V.B.2, V.B.3, V.B.4, and V.B.5 below. (40 C.F.R. § 122.41(k).)
2. All permit applications shall be signed by either a principal executive officer or ranking elected official. For purposes of this provision, a principal executive officer of a federal agency includes: (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrators of U.S. EPA). (40 C.F.R. § 122.22(a)(3).)
3. All reports required by this Order and other information requested by the Los Angeles Regional Water Board, State Water Board, or U.S. EPA shall be signed by a person described in Standard Provisions – Reporting V.B.2 above, or by a duly authorized representative of that person. A person is a duly authorized representative only if:
 - a. The authorization is made in writing by a person described in Standard Provisions – Reporting V.B.2 above (40 C.F.R. § 122.22(b)(1));
 - b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position.) (40 C.F.R. § 122.22(b)(2)); and
 - c. The written authorization is submitted to the Los Angeles Regional Water Board and State Water Board. (40 C.F.R. § 122.22(b)(3).)
4. If an authorization under Standard Provisions – Reporting V.B.3 above is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of Standard Provisions – Reporting V.B.3 above must be submitted to the Los Angeles Regional Water Board and State Water Board prior to or together with any reports, information, or applications, to be signed by an authorized representative. (40 C.F.R. § 122.22(c).)
5. Any person signing a document under Standard Provisions – Reporting V.B.2 or V.B.3 above shall make the following certification:

“I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.” (40 C.F.R. § 122.22(d).)

C. Monitoring Reports

1. Monitoring results shall be reported at the intervals specified in the Monitoring and Reporting Program (Attachment E) in this Order. (40 C.F.R. § 122.41(l)(4).)
2. Monitoring results must be reported on a Discharge Monitoring Report (DMR) form or forms provided or specified by the Los Angeles Regional Water Board or State Water Board for reporting results of monitoring of sludge use or disposal practices. (40 C.F.R. § 122.41(l)(4)(i).)
3. If the Discharger monitors any pollutant more frequently than required by this Order using test procedures approved under 40 C.F.R. part 136, or another method required for an industry-specific waste stream under 40 C.F.R. subchapters N or O, the results of such monitoring shall be included in the calculation and reporting of the data submitted in the DMR or sludge reporting form specified by the Los Angeles Regional Water Board. (40 C.F.R. § 122.41(l)(4)(ii).)
4. Calculations for all limitations, which require averaging of measurements, shall utilize an arithmetic mean unless otherwise specified in this Order. (40 C.F.R. § 122.41(l)(4)(iii).)

D. Compliance Schedules

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this Order, shall be submitted no later than 14 days following each schedule date. (40 C.F.R. § 122.41(l)(5).)

E. Twenty-Four Hour Reporting

1. The Discharger shall report any noncompliance that may endanger health or the environment. Any information shall be provided orally within 24 hours from the time the Discharger becomes aware of the circumstances. A written submission shall also be provided within five (5) days of the time the Discharger becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. (40 C.F.R. § 122.41(l)(6)(i).)
2. The following shall be included as information that must be reported within 24 hours under this paragraph (40 C.F.R. § 122.41(l)(6)(ii)):
 - a. Any unanticipated bypass that exceeds any effluent limitation in this Order. (40 C.F.R. § 122.41(l)(6)(ii)(A).)
 - b. Any upset that exceeds any effluent limitation in this Order. (40 C.F.R. § 122.41(l)(6)(ii)(B).)
3. The Los Angeles Regional Water Board may waive the above-required written report under this provision on a case-by-case basis if an oral report has been received within 24 hours. (40 C.F.R. § 122.41(l)(6)(iii).)

F. Planned Changes

The Discharger shall give notice to the Los Angeles Regional Water Board as soon as possible of any planned physical alterations or additions to the permitted facility. Notice is required under this provision only when (40 C.F.R. § 122.41(l)(1)):

1. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in section 122.29(b) (40 C.F.R. § 122.41(l)(1)(i)); or
2. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are subject neither to effluent limitations in this Order nor to notification requirements under section 122.42(a)(1) (see Additional Provisions—Notification Levels VII.A.1). (40 C.F.R. § 122.41(l)(1)(ii).)
3. The alteration or addition results in a significant change in the Discharger's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan. (40 C.F.R. § 122.41(l)(1)(iii).)

G. Anticipated Noncompliance

The Discharger shall give advance notice to the Los Angeles Regional Water Board or State Water Board of any planned changes in the permitted facility or activity that may result in noncompliance with this Order's requirements. (40 C.F.R. § 122.41(l)(2).)

H. Other Noncompliance

The Discharger shall report all instances of noncompliance not reported under Standard Provisions – Reporting V.C, V.D, and V.E above at the time monitoring reports are submitted. The reports shall contain the information listed in Standard Provision – Reporting V.E above. (40 C.F.R. § 122.41(l)(7).)

I. Other Information

When the Discharger becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Los Angeles Regional Water Board, State Water Board, or U.S. EPA, the Discharger shall promptly submit such facts or information. (40 C.F.R. § 122.41(l)(8).)

VI. STANDARD PROVISIONS – ENFORCEMENT

The Los Angeles Regional Water Board is authorized to enforce the terms of this permit under several provisions of the Water Code, including, but not limited to, sections 13385, 13386, and 13387.

VII. ADDITIONAL PROVISIONS – NOTIFICATION LEVELS

A. Non-Municipal Facilities

Existing manufacturing, commercial, mining, and silvicultural Dischargers shall notify the Los Angeles Regional Water Board as soon as they know or have reason to believe (40 C.F.R. § 122.42(a)):

1. That any activity has occurred or will occur that would result in the discharge, on a routine or frequent basis, of any toxic pollutant that is not limited in this Order, if that discharge will exceed the highest of the following "notification levels" (40 C.F.R. § 122.42(a)(1)):
 - a. 100 micrograms per liter (µg/L) (40 C.F.R. § 122.42(a)(1)(i));

ATTACHMENT E – MONITORING AND REPORTING PROGRAM (MRP NO. 9404)

Contents

I. General Monitoring Provisions E-2
II. Monitoring Locations E-4
III. Influent Monitoring Requirements – Not Applicable E-5
IV. Effluent Monitoring Requirements E-5
 A. Monitoring Location EFF-001 E-5
V. Whole Effluent Toxicity Testing Requirements E-9
VI. Land Discharge Monitoring Requirements – Not Applicable E-12
VII. Recycling Monitoring Requirements – Not Applicable E-12
VIII. Receiving Water Monitoring Requirements E-13
 A. Monitoring Location RSW-001, RSW-002, RSW-003, and RSW-004 E-13
IX. Other Monitoring Requirements E-16
X. Reporting Requirements E-17
 A. General Monitoring and Reporting Requirements E-17
 B. Self-Monitoring Reports (SMR’s) E-17
 C. Discharge Monitoring Reports (DMR’s) E-19
 D. Other Reports E-20

Tables

Table E-1. Monitoring Station Locations E-4
Table E-2. Effluent Monitoring E-5
Table E-3. Receiving Water Monitoring Requirements E-13
Table E-4. Monitoring Periods and Reporting Schedule E-18

ATTACHMENT E – MONITORING AND REPORTING PROGRAM (MRP) NO. 9404

The Code of Federal Regulations (40 C.F.R. § 122.48) requires that all NPDES permits specify monitoring and reporting requirements. Water Code sections 13267 and 13383 also authorize the <Los Angeles Regional Water Board to require technical and monitoring reports. This MRP establishes monitoring and reporting requirements that implement federal and California regulations.

I. GENERAL MONITORING PROVISIONS

- A. An effluent sampling station shall be established for the point of discharge (Discharge Point 001 [Latitude 34° 08' 34.75" North, Longitude 119° 11' 33.72" West]) and shall be located where representative samples of that effluent can be obtained.
- B. Effluent samples shall be taken downstream of any treatment works and prior to mixing with the receiving waters.
- C. The Los Angeles Regional Water Board shall be notified in writing of any change in the sampling stations once established or in the methods for determining the quantities of pollutants in the individual waste streams.
- D. Pollutants shall be analyzed using the analytical methods described in 40 CFR sections 136.3, 136.4, and 136.5 (revised May 18, 2012); or, where no methods are specified for a given pollutant, by methods approved by this Regional Water Board or the State Water Resources Control Board (State Water Board). Laboratories analyzing effluent samples and receiving water samples shall be certified by the California Department of Public Health Environmental Laboratory Accreditation Program (ELAP) or approved by the Executive Officer and must include quality assurance/quality control (QA/QC) data in their reports. A copy of the laboratory certification shall be provided each time a new certification and/or renewal of the certification is obtained from ELAP.
- E. For any analyses performed for which no procedure is specified in the U.S. Environmental Protection Agency (USEPA) guidelines or in the MRP, the constituent or parameter analyzed and the method or procedure used must be specified in the monitoring report.
- F. Each monitoring report must affirm in writing that "all analyses were conducted at a laboratory certified for such analyses by the Department of Public Health or approved by the Executive Officer and in accordance with current USEPA guideline procedures or as specified in this MRP".
- G. The monitoring reports shall specify the analytical method used, the Method Detection Limit (MDL), and the Minimum Level (ML) for each pollutant. For the purpose of reporting compliance with numerical limitations, performance goals, and receiving water limitations, analytical data shall be reported by one of the following methods, as appropriate:
 - 1. actual numerical value for sample results greater than or equal to the ML; or
 - 2. "Detected, but Not Quantified (DNQ)" if results are greater than or equal to the laboratory's MDL but less than the ML; or,
 - 3. "Not-Detected (ND)" for sample results less than the laboratory's MDL with the MDL indicated for the analytical method used.

Analytical data reported as "less than" for the purpose of reporting compliance with permit limitations shall be the same or lower than the permit limit(s) established for the given parameter'.

Current MLs (Attachment H) are those published in Appendix II of the Ocean Plan. In addition, samples for metals analyses, waste seawater discharge, storm water effluent samples, reference station samples, and receiving water samples must be analyzed by the approved analytical method with the lowest MDL (currently Inductively Coupled Plasma/Mass Spectrometry) described in the Ocean Plan.

- H. Where possible, the MLs employed for effluent analyses shall be lower than the permit limitations established for a given parameter. If the ML value is not below the effluent limitation, then the lowest ML value and its associated analytical method shall be selected for compliance purposes. At least once a year, the Discharger shall submit a list of the analytical methods employed for each test and associated laboratory QA/QC procedures.

The Regional Water Board, in consultation with the State Water Board Quality Assurance Program, shall establish a ML that is not contained in Attachment H to be included in the Discharger's permit in any of the following situations:

1. When the pollutant under consideration is not included in Attachment H;
 2. When the Discharger and Regional Water Board agree to include in the permit a test method that is more sensitive than that specified in 40 CFR section 136 (revised May 18, 2012);
 3. When the Discharger agrees to use an ML that is lower than that listed in Attachment H;
 4. When the Discharger demonstrates that the calibration standard matrix is sufficiently different from that used to establish the ML in Attachment H, and proposes an appropriate ML for their matrix; or,
 5. When the Discharger uses a method whose quantification practices are not consistent with the definition of an ML. Examples of such methods are the USEPA-approved method 1613 for dioxins and furans, method 1624 for volatile organic substances, and method 1625 for semi-volatile organic substances. In such cases, the Discharger, the Regional Water Board, and the State Water Board shall agree on a lowest quantifiable limit and that limit will substitute for the ML for reporting and compliance determination purposes.
- I. Water/wastewater samples must be analyzed within allowable holding time limits as specified in section 136.3. All QA/QC items must be run on the same dates the samples were actually analyzed, and the results shall be reported in the Regional Water Board format, when it becomes available, and submitted with the laboratory reports. Proper chain of custody procedures must be followed, and a copy of the chain of custody shall be submitted with the report.
- J. All analyses shall be accompanied by the chain of custody, including but not limited to date and time of sampling, sample identification, and name of person who performed sampling, date of analysis, name of person who performed analysis, QA/QC data, method detection limits, analytical methods, copy of laboratory certification, and a perjury statement executed by the person responsible for the laboratory.
- K. The Discharger shall calibrate and perform maintenance procedures on all monitoring instruments and to insure accuracy of measurements, or shall insure that both equipment activities will be conducted.
- L. The Discharger shall have, and implement, an acceptable written quality assurance (QA) plan for laboratory analyses. Unless otherwise specified in the analytical method, duplicate samples must be analyzed at a frequency of 5% (1 in 20 samples) with at least one if there

are fewer than 20 samples in a batch. A batch is defined as a single analytical run encompassing no more than 24 hours from start to finish. A similar frequency shall be maintained for analyzing spiked samples.

- M. When requested by the Regional Water Board or USEPA, the Discharger will participate in the NPDES discharge monitoring report QA performance study. The Discharger must have a success rate equal to or greater than 80%.
- N. For parameters that both average monthly and daily maximum limits are specified and the monitoring frequency is less than four times a month, the following shall apply. If an analytical result is greater than the average monthly limit, the Discharger shall collect four additional samples at approximately equal intervals during the month, if possible, until compliance with the average monthly limit has been demonstrated. All five analytical results shall be reported in the monitoring report for that month, or 45 days after results for the additional samples were received, whichever is later. In the event of noncompliance with an average monthly effluent limitation, the sampling frequency for that constituent shall be increased to weekly and shall continue at this level until compliance with the average monthly effluent limitation has been demonstrated. The Discharger shall provide for the approval of the Executive Officer a program to ensure future compliance with the average monthly limit.
- O. In the event wastes are transported to a different disposal site during the report period, the following shall be reported in the monitoring report:
 - 1. Types of wastes and quantity of each type;
 - 2. Name and address for each hauler of wastes (or method of transport if other than by hauling); and
 - 3. Location of the final point(s) of disposal for each type of waste.

If no wastes are transported off-site during the reporting period, a statement to that effect shall be submitted.
- P. Each monitoring report shall state whether or not there was any change in the discharge as described in the Order during the reporting period.

II. MONITORING LOCATIONS

The Discharger shall establish the following monitoring locations to demonstrate compliance with the effluent limitations, discharge specifications, and other requirements in this Order:

Table E-1. Monitoring Station Locations

| Discharge Point Name | Monitoring Location Name | Monitoring Location Description |
|----------------------|--------------------------|--|
| 001 | EFF-001 | Effluent discharged from the Facility (RSMP) [Latitude 34° 08' 34.75" N, Longitude 119° 11' 33.72" W] |
| --- | RSW-001 | Center line of mixing zone (within Zone of Initial Dilution) |
| --- | RSW-002 | Edge of establishing mixing zone area (Edge of Zone of Initial Dilution) (47 feet from the outfall at a depth of approximately 10 feet)* |
| --- | RSW-003 | Outside Zone of Initial Dilution (100 feet from the outfall at a depth of approximately 10 feet)* |
| --- | RSW-004 | Upstream of discharge location to the Pacific Ocean (along Oxnard's 4500 transect)* |

* The proposed monitoring locations were selected based on the modeling results. These monitoring locations may be modified pending the results of the Mixing Zone Study.

The North latitude and West longitude information in Table E-1 are approximate for administrative purposes.

III. INFLUENT MONITORING REQUIREMENTS – NOT APPLICABLE

IV. EFFLUENT MONITORING REQUIREMENTS

A. Monitoring Location EFF-001

1. The Discharger shall monitor wastewater discharge at EFF-001 as follows. If more than one analytical test method is listed for a given parameter, the Discharger must select from the listed methods and corresponding Minimum Level:

Table E-2. Effluent Monitoring

| Parameter | Units | Sample Type | Minimum Sampling Frequency | Required Analytical Test Method |
|--|---------------------------|-------------|----------------------------|---------------------------------|
| Flow | MGD | Recorder | Continuous ² | 1 |
| Temperature | °F | Grab | 1/Month | 1 |
| pH | pH unit | Grab | 1/Month | 1 |
| Total Coliform | MPN/100 ml | Grab | 1/Month | 1 |
| Fecal Coliform | MPN/100 ml | Grab | 1/Month | 1 |
| Enterococcus | MPN/100 ml | Grab | 1/Month | 1 |
| Dissolved Oxygen | mg/L | Grab | 1/Month | 1 |
| Ammonia as N ³ | µg/L | Grab | 1/Month | 1 |
| Total Residual Chlorine ³ | µg/L | Grab | 1/Month | 1 |
| Chronic Toxicity ⁵ | Pass or Fail, % Effect | Grab | 1/Month | 1 |
| Biochemical Oxygen Demand (BOD), 5-day @ 20°C ³ | mg/L | Grab | 1/Quarter | 1 |
| Oil and Grease ^{2,3} | mg/L | Grab | 1/Quarter | 1 |
| Settleable Solids | ml/L | Grab | 1/Quarter | 1 |
| Total Suspended Solids (TSS) ³ | mg/L | Grab | 1/Quarter | 1 |
| Turbidity | NTU | Grab | 1/Quarter | 1 |
| Antimony, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Arsenic, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Beryllium Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Cadmium, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Chromium (III), Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Chromium (VI), Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Copper, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Lead, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |

| Parameter | Units | Sample Type | Minimum Sampling Frequency | Required Analytical Test Method |
|---|-------|-------------|----------------------------|---------------------------------|
| Mercury, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Nickel, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Selenium, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Silver, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Thallium, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Zinc, Total Recoverable ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Cyanide ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Phenolic Compounds (non-chlorinated) ^{3,6} | µg/L | Grab | 1/Month ⁴ | 1 |
| Chlorinated Phenolics ^{3,7} | µg/L | Grab | 1/Month ⁴ | 1 |
| TCDD Equivalents ^{3,8} | µg/L | Grab | 1/Month ⁴ | 1 |
| Acrolein ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Acrylonitrile ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Benzene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Carbon Tetrachloride ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Chlorobenzene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Chlorodibromomethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Chloroform ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Dichlorobromomethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,2-Dichloroethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,1-Dichloroethylene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,3-Dichloropropylene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Ethylbenzene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Halomethanes ^{3,9} | µg/L | Grab | 1/Month ⁴ | 1 |
| Dichloromethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,1,2,2-Tetrachloroethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Tetrachloroethylene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Toluene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,1,1-Trichloroethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,1,2-Trichloroethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Trichloroethylene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Vinyl Chloride ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 4,6-Dinitro-2-Methylphenol ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 2,4-Dinitrophenol ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 2,4,6-Trichlorophenol ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Benzidine ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| PAHs ^{3,10} | µg/L | Grab | 1/Month ⁴ | 1 |
| Bis(2-chloroethoxy)Methane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Bis(2-chloroethyl)Ether ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Bis(2-chloroisopropyl)Ether ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Bis(2-ethylhexyl)Phthalate ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Dichlorobenzenes ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,4-Dichlorobenzene ³ | µg/L | Grab | 1/Month ⁴ | 1 |

| Parameter | Units | Sample Type | Minimum Sampling Frequency | Required Analytical Test Method |
|---|-------|-------------|----------------------------|---------------------------------|
| 3,3'-Dichlorobenzidine ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Diethyl Phthalate ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Dimethyl Phthalate ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Di-n-Butyl Phthalate ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 2,4-Dinitrotoluene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| 1,2-Diphenylhydrazine ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Fluoranthene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Hexachlorobenzene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Hexachlorobutadiene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Hexachlorocyclopentadiene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Hexachloroethane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Isophorone ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Nitrobenzene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| N-Nitrosodimethylamine ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| N-Nitrosodi-N-propylamine ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| N-Nitrosodiphenylamine ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Aldrin ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| HCH ^{3,11} | µg/L | Grab | 1/Month ⁴ | 1 |
| Chlordane ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| DDT ^{3,12} | µg/L | Grab | 1/Month ⁴ | 1 |
| Dieldrin ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Endosulfan ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Endrin ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Heptachlor ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Heptachlor Epoxide ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| PCBs ^{3,13} | µg/L | Grab | 1/Month ⁴ | 1 |
| Toxaphene ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Tributyltin ³ | µg/L | Grab | 1/Month ⁴ | 1 |
| Radioactivity ¹⁴ (Including gross alpha, gross beta, combined radium-226 and radium-228, tritium, strontium-90 and uranium) | pCi/L | Grab | 2/Year | 1 |

- Pollutants shall be analyzed using the analytical methods described in Part 136. For priority pollutants, the methods must meet the lowest minimum levels (MLs) specified in Appendix II of the Ocean Plan (2012) that is required to demonstrate compliance. Where no methods are specified for a given pollutant, the methods must be approved by this Los Angeles Regional Water Board or the State Water Board.
- When continuous monitoring is required, the total daily flow (24-hour basis) shall be reported.
- The mass emission (lbs/day) for the discharge shall be calculated and reported using the actual concentration and the actual flow rate measured at the time of discharge, using the formula:

$$M = 8.34 \times C \times Q$$

Where: M = mass discharge for a pollutant, lbs/day
C = actual concentration for a pollutant, mg/L
Q = actual discharge flow rate, MGD

4. Upon the commencement of discharges from the RSMP, if after 2 years all monitoring results for this constituent are reported as non-detect, using detection limits that are sufficiently sensitive to demonstrate compliance with effluent limitations, the sampling frequency for this constituent may be reduced to once per quarter. However, if after the reduction in monitoring frequency for this constituent is allowed, monitoring results are reported at concentrations greater than the applicable effluent limitation, the monitoring frequency for this constituent reverts to monthly until at least four consecutive samples demonstrate compliance with the effluent limitation.
5. Refer to section V, Whole Effluent Toxicity Testing Requirements. "Pass" or "Fail" for Median Monthly Effluent Limitation (MMEL). "Pass" or "Fail" and "% Effect" for Maximum Daily Effluent Limitation (MDEL). The MMEL for chronic toxicity shall only apply when there is a discharge more than one day in a calendar month period. During such calendar months, exactly three independent toxicity tests are required when one toxicity test results in "Fail".
6. Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
7. Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
8. TCDD Equivalents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown in the table below. USEPA method 1613 may be used to analyze dioxin and furan congeners.

$$\text{Dioxin-TEQ (TCDD Equivalents)} = \sum (C_x \times \text{TEF}_x)$$

Where:

C_x = concentration of dioxin or furan congener x

TEF_x = TEF for congener x

Toxicity Equivalence Factors

| Isomer Group | Toxicity Equivalence Factor (TEF) |
|---------------------|-----------------------------------|
| 2,3,7,8-tetra CDD | 1.0 |
| 2,3,7,8-penta CDD | 0.5 |
| 2,3,7,8-hexa CDDs | 0.1 |
| 2,3,7,8-hepta CDD | 0.01 |
| Octa CDD | 0.001 |
| 2,3,7,8 tetra CDF | 0.1 |
| 1,2,3,7,8 penta CDF | 0.05 |
| 2,3,4,7,8 penta CDF | 0.5 |
| 2,3,7,8 hexa CDFs | 0.1 |
| 2,3,7,8 hepta CDFs | 0.01 |

9. Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
10. PAHs shall mean the sum of acenaphthylene, anthracene, 1,2-benzanthracene, 3,4-benzofluoranthene, benzo(k)fluoranthene, 1,12-benzoperylene, benzo(a)pyrene, chrysene, dibenzo(a,h)anthracene, fluorene, indeno(1,2,3-cd)pyrene, phenanthrene and pyrene.
11. HCH shall mean the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
12. DDT shall mean the sum of 4,4'-DDT, 2,4'-DDT, 4,4'-DDE, 2,4'-DDE, 4,4'-DDD and 2,4'-DDD.
13. PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254 and Aroclor-1260.
14. Analyze these radiochemicals by the following USEPA methods:

| | |
|--|---------------------------------------|
| Method 900.0 for gross alpha and gross beta; | Method 903.0 or 903.1 for radium-226; |
| Method 904.0 for radium-228; | Method 906.0 for tritium; |
| Method 905.0 for strontium-90; | Method 908.0 for uranium. |

Analysis for combined radium-226 & 228 shall be conducted only if gross alpha results for the same sample exceed 15 pCi/L or beta greater than 50 pCi/L. If radium-226 & 228 exceeds 5 pCi/L, analyze for tritium, strontium-90 and uranium.

V. WHOLE EFFLUENT TOXICITY TESTING REQUIREMENTS

A. Chronic Toxicity Testing

1. Discharge In-stream Waste Concentration (IWC) for Chronic Toxicity

The chronic toxicity IWC for this discharge is **1.37 percent** [1/(72+1)] effluent. For receiving water monitoring, the IWC shall be 100% of the sample collected at the specified station location for receiving water monitoring.

2. Sample Volume and Holding Time

The total sample volume shall be determined by the specific toxicity test method used. Sufficient sample volume shall be collected to perform the required toxicity test. For the receiving water, sufficient sample volume shall be collected for subsequent TIE studies, if necessary, at each sampling event. All toxicity tests shall be conducted as soon as possible following sample collection. No more than 36 hours shall elapse before the conclusion of sample collection and test initiation.

3. Chronic Marine and Estuarine Species and Test Methods

If effluent samples are collected from outfalls discharging to receiving waters with salinity ≥ 1 ppt, the Discharger shall conduct the following chronic toxicity tests on effluent samples—at the in-stream waste concentration for the discharge—in accordance with species and test methods in *Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to West Coast Marine and Estuarine Organisms* (EPA/600/R-95/136, 1995). Artificial sea salts shall be used to increase sample salinity. In no case shall these species be substituted with another test species unless written authorization from the Executive Officer is received.

- a. A static renewal toxicity test with the topsmelt, *Atherinops affinis* (Larval Survival and Growth Test Method 1006.01).
- b. A static non-renewal toxicity test with the purple sea urchin, *Strongylocentrotus purpuratus*, and the sand dollar, *Dendraster excentricus* (Fertilization Test Method 1008.0), or a static non-renewal toxicity test with the red abalone, *Haliotis rufescens* (Larval Shell Development Test Method).
- c. A static non-renewal toxicity test with the giant kelp, *Macrocystis pyrifera* (Germination and Growth Test Method 1009.0).

4. Chronic Freshwater Species and Test Methods

If effluent samples are collected from outfalls discharging to receiving waters with salinity < 1 ppt, the Discharger shall conduct the following chronic toxicity tests on effluent samples—at the in-stream waste concentration for the discharge—in accordance with species and test methods in *Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Freshwater Organisms* (EPA/821/R-02/013, 2002; Table IA, 40 CFR section 136). In no case shall these species be substituted with another test species unless written authorization from the Executive Officer is received.

- a. A static renewal toxicity test with the fathead minnow, *Pimephales promelas* (Larval Survival and Growth Test Method 1000.0).
- b. A static renewal toxicity test with the daphnid, *Ceriodaphnia dubia* (Survival and Reproduction Test Method 1002.01).

- c. A static renewal toxicity test with the green alga, *Selenastrum capricornutum* (also named *Raphidocelis subcapitata*) (Growth Test Method 1003.0).

5. **Species Sensitivity Screening**

Species sensitivity screening shall be conducted during this permit's first three monthly monitorings. For each monthly sampling event, the Discharger shall collect a single effluent sample and concurrently conduct three toxicity tests using the fish, an invertebrate, and the alga species previously referenced. The species that exhibits the highest "Percent Effect" at the discharge IWC during species sensitivity screening shall be used for the routine monthly monitoring.

Species sensitivity rescreening is required every 24 months. The Discharger shall rescreen with the fish, an invertebrate, and the alga species previously referenced and continue to monitor with the most sensitive species. If the first suite of rescreening tests demonstrates that the same species is the most sensitive then the rescreening does not need to include more than one suit of tests. If a different species is the most sensitive or if there is ambiguity, then the Discharger shall proceed with suites of screening tests for a minimum of three, but not to exceed five suites.

6. **Quality Assurance and Additional Requirements**

Quality assurance measures, instructions, and other recommendations and requirements are found in the test methods manual previously referenced. Additional requirements are specified below.

- a. The discharge is subject to determination of "Pass" or "Fail" and "Percent Effect" from a single-effluent concentration chronic toxicity test at the discharge IWC using the Test of Significant Toxicity (TST) approach described in *National Pollutant Discharge Elimination System Test of Significant Toxicity Implementation Document* (EPA 833-R-10-003, 2010), Appendix A, Figure A-1, and Table A-1. The null hypothesis (H_0) for the TST approach is: Mean discharge IWC response $\leq 0.75 \times$ Mean control response. A test result that rejects this null hypothesis is reported as "Pass". A test result that does not reject this null hypothesis is reported as "Fail". The relative "Percent Effect" at the discharge IWC is defined and reported as: $((\text{Mean control response} - \text{Mean discharge IWC response}) \div \text{Mean control response}) \times 100$.
- b. The Median Monthly Effluent Limit (MMEL) for chronic toxicity only applies when there is a discharge more than one day in a calendar month period. During such calendar months, exactly three independent toxicity tests are required when one toxicity test results in "Fail".
- c. If the effluent toxicity test does not meet all test acceptability criteria (TAC) specified in the referenced test method, then the Discharger must re-sample and re-test within 14 days.
- d. Dilution water and control water, including brine controls, shall be laboratory water prepared and used as specified in the test methods manual. If dilution water and control water is different from test organism culture water, then a second control using culture water shall also be used.
- e. Reference toxicant tests and effluent toxicity tests shall be conducted using the same test conditions (e.g., same test duration, etc.). Monthly reference toxicant testing is sufficient.

- f. All reference toxicant test results should be reviewed and reported according to EPA guidance on the evaluation of concentration-response relationships found in *Method Guidance and Recommendations for Whole Effluent Toxicity (WET) Testing* (40 CFR section 136) (EPA 821-B-00-004, 2000).
- g. The Discharger shall perform toxicity tests on final effluent samples. Chlorine and ammonia shall not be removed from the effluent sample prior to toxicity testing, unless explicitly authorized under this section of the Monitoring and Reporting Program and the rationale is explained in the Fact Sheet (Attachment F).

7. Preparation of Initial Investigation TRE Work Plan

The Discharger shall prepare or update and submit a generic Initial Investigation TRE Work Plan (1-2 pages) within **90 days** of the permit effective date, to be ready to respond to toxicity events. The Discharger shall review and update this work plan as necessary so it remains current and applicable to the discharge. At minimum, the work plan shall include:

- a. A description of the investigation and evaluation techniques that would be used to identify potential causes and sources of toxicity, effluent variability, and treatment system efficiency.
- b. A description of methods for maximizing in-house treatment system efficiency, good housekeeping practices, and a list of all chemicals used in operations at the facility.
- c. If a Toxicity Identification Evaluation (TIE) is necessary, an indication of who would conduct the TIEs (i.e., an in-house expert or outside contractor).

8. Accelerated Monitoring Schedule for Median Monthly Summary Result: "Fail" (or Maximum Daily Single Result: "Fail and % Effect ≥ 50 "). The summary result shall be used when there is discharge more than one day in a calendar month. The single result shall be used when there is discharge of only one day in a calendar month.

Within 24 hours of the time the Discharger becomes aware of this result, the Discharger shall implement an accelerated monitoring schedule consisting of four, five-concentration toxicity tests (including the discharge IWC), conducted at approximately two week intervals, over an eight week period. If each of the accelerated toxicity tests results in "Pass", the Discharger shall return to routine monitoring for the next monitoring period. If one of the accelerated toxicity tests results in "Fail", the Discharger shall immediately implement the Toxicity Reduction Evaluation (TRE) Process conditions set forth below.

9. Toxicity Reduction Evaluation (TRE) Process

- a. **Preparation and Implementation of Detailed TRE Work Plan.** The Discharger shall immediately initiate a TRE using, according to the type of treatment facility, EPA manual *Toxicity Reduction Evaluation Guidance for Municipal Wastewater Treatment Plants* (EPA/833/B-99/002, 1999) or EPA manual *Generalized Methodology for Conducting Industrial Toxicity Reduction Evaluations* (EPA/600/2-88/070, 1989) and, within 30 days, submit to the Executive Officer a Detailed TRE Work Plan, which shall follow the generic Initial Investigation TRE Work Plan revised as appropriate for this toxicity event. It shall include the following information, and comply with additional conditions set by the Executive Officer:
 - i. Further actions by the Discharger to investigate, identify, and correct the causes of toxicity.

- ii. Actions the Discharger will take to mitigate the effects of the discharge and prevent the recurrence of toxicity.
 - iii. A schedule for these actions, progress reports, and the final report.
- b. TIE Implementation.** The Discharger may initiate a TIE as part of a TRE to identify the causes of toxicity using the same species and test method and, as guidance, EPA manuals: *Methods for Aquatic Toxicity Identification Evaluations: Phase I Toxicity Characterization Procedures* (EPA/600/6-91/003, 1991); *Methods for Aquatic Toxicity Identification Evaluations, Phase II Toxicity Identification Procedures for Samples Exhibiting Acute and Chronic Toxicity* (EPA/600/R-92/080, 1993); *Methods for Aquatic Toxicity Identification Evaluations, Phase III Toxicity Confirmation Procedures for Samples Exhibiting Acute and Chronic Toxicity* (EPA/600/R-92/081, 1993); and *Marine Toxicity Identification Evaluation (TIE): Phase I Guidance Document* (EPA/600/R-96-054, 1996). The TIE should be conducted on the species demonstrating the most sensitive toxicity response.
- c.** Many recommended TRE elements parallel required or recommended efforts for source control, pollution prevention, and storm water control programs. TRE efforts should be coordinated with such efforts. As toxic substances are identified or characterized, the Discharger shall continue the TRE by determining the sources and evaluating alternative strategies for reducing or eliminating the substances from the discharge. All reasonable steps shall be taken to reduce toxicity to levels consistent with toxicity evaluation parameters.
- d.** The Discharger shall conduct routine effluent monitoring for the duration of the TRE process. Additional accelerated monitoring and TRE work plans are not required once a TRE is begun.
- e.** The Regional Water Board recognizes that toxicity may be episodic and identification of causes and reduction of sources of toxicity may not be successful in all cases. The TRE may be ended at any stage if monitoring finds there is no longer toxicity.
- 10. Reporting**

The Self Monitoring Report (SMR) shall include a full laboratory report for each toxicity test. This report shall be prepared using the format and content of the test methods manual chapter called Report Preparation, including:

- a.** The toxicity test results for the TST approach, reported as “Pass” or “Fail” and “Percent Effect” at the chronic toxicity IWC for the discharge.
- b.** Water quality measurements for each toxicity test (e.g., pH, dissolved oxygen, temperature, conductivity, hardness, salinity, chlorine, ammonia).
- c.** TRE/TIE results. The Executive Officer shall be notified no later than 30 days from completion of each aspect of TRE/TIE analyses.
- d.** Statistical program (e.g., TST calculator, CETIS, etc.) output results for each toxicity test.

VI. LAND DISCHARGE MONITORING REQUIREMENTS – NOT APPLICABLE

VII. RECYCLING MONITORING REQUIREMENTS – NOT APPLICABLE

VIII. RECEIVING WATER MONITORING REQUIREMENTS

A. Monitoring Location RSW-001, RSW-002, RSW-003, and RSW-004

1. The Discharger shall monitor the Pacific Ocean (Hueneme) at **RSW-001, RSW-002, RSW-003, and RSW-004** as follows:

Table E-3. Receiving Water Monitoring Requirements

| Parameter | Units | Sample Type | Minimum Sampling Frequency | Required Analytical Test Method |
|---|---------------------------|-------------|----------------------------|---------------------------------|
| Temperature | °F | Grab | 1/Quarter | 1 |
| BOD, 5-day @ 20°C | mg/L | Grab | 1/Quarter | 1 |
| Total Suspended Solids (TSS) | mg/L | Grab | 1/Quarter | 1 |
| pH | pH unit | Grab | 1/Quarter | 1 |
| Oil and Grease | mg/L | Grab | 1/Quarter | 1 |
| Settleable Solids | ml/L | Grab | 1/Quarter | 1 |
| Turbidity | NTU | Grab | 1/Quarter | 1 |
| Chronic Toxicity ² | Pass or Fail, % Effect | Grab | 1/Monthly ¹² | 1 |
| Dissolved Oxygen | mg/L | Grab | 1/Quarter | 1 |
| Total Residual Chlorine | µg/L | Grab | 1/Month ³ | 1 |
| Ammonia as N | µg/L | Grab | 1/Month ³ | 1 |
| Total Coliform | MPN/100 ml | Grab | 1/Month ³ | 1 |
| Fecal Coliform | MPN/100 ml | Grab | 1/Month ³ | 1 |
| Enterococcus | MPN/100 ml | Grab | 1/Month ³ | 1 |
| Antimony, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Arsenic, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Beryllium, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Cadmium, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Chromium (III), Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Chromium (VI), Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Copper, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Lead, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Mercury, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Nickel, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Selenium, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Silver, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Thallium, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Zinc, Total Recoverable | µg/L | Grab | 1/Month ³ | 1 |
| Cyanide | µg/L | Grab | 1/Month ³ | 1 |
| Phenolic Compounds (non-chlorinated) ⁴ | µg/L | Grab | 1/Month ³ | 1 |
| Chlorinated Phenolics ⁵ | µg/L | Grab | 1/Month ³ | 1 |

| Parameter | Units | Sample Type | Minimum Sampling Frequency | Required Analytical Test Method |
|-------------------------------|-------|-------------|----------------------------|---------------------------------|
| TCDD Equivalents ⁶ | µg/L | Grab | 1/Month ³ | 1 |
| Acrolein | µg/L | Grab | 1/Month ³ | 1 |
| Acrylonitrile | µg/L | Grab | 1/Month ³ | 1 |
| Benzene | µg/L | Grab | 1/Month ³ | 1 |
| Carbon Tetrachloride | µg/L | Grab | 1/Month ³ | 1 |
| Chlorobenzene | µg/L | Grab | 1/Month ³ | 1 |
| Chlorodibromomethane | µg/L | Grab | 1/Month ³ | 1 |
| Chloroform | µg/L | Grab | 1/Month ³ | 1 |
| Dichlorobromomethane | µg/L | Grab | 1/Month ³ | 1 |
| 1,2-Dichloroethane | µg/L | Grab | 1/Month ³ | 1 |
| 1,1-Dichloroethylene | µg/L | Grab | 1/Month ³ | 1 |
| 1,3-Dichloropropylene | µg/L | Grab | 1/Month ³ | 1 |
| Ethylbenzene | µg/L | Grab | 1/Month ³ | 1 |
| Halomethanes ⁷ | µg/L | Grab | 1/Month ³ | 1 |
| Dichloromethane | µg/L | Grab | 1/Month ³ | 1 |
| 1,1,2,2-Tetrachloroethane | µg/L | Grab | 1/Month ³ | 1 |
| Tetrachloroethylene | µg/L | Grab | 1/Month ³ | 1 |
| Toluene | µg/L | Grab | 1/Month ³ | 1 |
| 1,1,1-Trichloroethane | µg/L | Grab | 1/Month ³ | 1 |
| 1,1,2-Trichloroethane | µg/L | Grab | 1/Month ³ | 1 |
| Trichloroethylene | µg/L | Grab | 1/Month ³ | 1 |
| Vinyl Chloride | µg/L | Grab | 1/Month ³ | 1 |
| 4,6-Dinitro-2-Methylphenol | µg/L | Grab | 1/Month ³ | 1 |
| 2,4-Dinitrophenol | µg/L | Grab | 1/Month ³ | 1 |
| 2,4,6-Trichlorophenol | µg/L | Grab | 1/Month ³ | 1 |
| Benzidine | µg/L | Grab | 1/Month ³ | 1 |
| PAHs ⁸ | µg/L | Grab | 1/Month ³ | 1 |
| Bis(2-chloroethoxy)Methane | µg/L | Grab | 1/Month ³ | 1 |
| Bis(2-chlorotethyl)Ether | µg/L | Grab | 1/Month ³ | 1 |
| Bis(2-chloroisopropyl)Ether | µg/L | Grab | 1/Month ³ | 1 |
| Bis(2-ethylhexyl)Phthalate | µg/L | Grab | 1/Month ³ | 1 |
| Dichlorobenzenes | µg/L | Grab | 1/Month ³ | 1 |
| 1,4-Dichlorobenzene | µg/L | Grab | 1/Month ³ | 1 |
| 3,3'-Dichlorobenzidine | µg/L | Grab | 1/Month ³ | 1 |
| Diethyl Phthalate | µg/L | Grab | 1/Month ³ | 1 |
| Dimethyl Phthalate | µg/L | Grab | 1/Month ³ | 1 |
| Di-n-Butyl Phthalate | µg/L | Grab | 1/Month ³ | 1 |
| 2,4-Dinitrotoluene | µg/L | Grab | 1/Month ³ | 1 |
| 1,2-Diphenylhydrazine | µg/L | Grab | 1/Month ³ | 1 |
| Fluoranthene | µg/L | Grab | 1/Month ³ | 1 |
| Hexachlorobenzene | µg/L | Grab | 1/Month ³ | 1 |
| Hexachlorobutadiene | µg/L | Grab | 1/Month ³ | 1 |
| Hexachlorocyclopentadiene | µg/L | Grab | 1/Month ³ | 1 |

| Parameter | Units | Sample Type | Minimum Sampling Frequency | Required Analytical Test Method |
|---------------------------|-------|-------------|----------------------------|---------------------------------|
| Hexachloroethane | µg/L | Grab | 1/Month ³ | 1 |
| Isophorone | µg/L | Grab | 1/Month ³ | 1 |
| Nitrobenzene | µg/L | Grab | 1/Month ³ | 1 |
| N-Nitrosodimethylamine | µg/L | Grab | 1/Month ³ | 1 |
| N-Nitrosodi-N-propylamine | µg/L | Grab | 1/Month ³ | 1 |
| N-Nitrosodiphenylamine | µg/L | Grab | 1/Month ³ | 1 |
| Aldrin | µg/L | Grab | 1/Month ³ | 1 |
| HCH ⁹ | µg/L | Grab | 1/Month ³ | 1 |
| Chlordane | µg/L | Grab | 1/Month ³ | 1 |
| DDT ¹⁰ | µg/L | Grab | 1/Month ³ | 1 |
| Dieldrin | µg/L | Grab | 1/Month ³ | 1 |
| Endosulfan | µg/L | Grab | 1/Month ³ | 1 |
| Endrin | µg/L | Grab | 1/Month ³ | 1 |
| Heptachlor | µg/L | Grab | 1/Month ³ | 1 |
| Heptachlor Epoxide | µg/L | Grab | 1/Month ³ | 1 |
| PCBs ¹¹ | µg/L | Grab | 1/Month ³ | 1 |
| Toxaphene | µg/L | Grab | 1/Month ³ | 1 |
| Tributyltin | µg/L | Grab | 1/Month ³ | 1 |

1. Pollutants shall be analyzed using the analytical methods described in Part 136. For priority pollutants, the methods must meet the lowest minimum levels (MLs) specified in Appendix II of the Ocean Plan (2012) that is required to demonstrate compliance. Where no methods are specified for a given pollutant, the methods must be approved by this Los Angeles Regional Water Board or the State Water Board.
2. Refer to section V, Whole Effluent Toxicity Testing Requirements. A toxicity test sample is immediately subject to TIE procedures to identify the toxic chemical(s), if a chronic toxicity test shows "Fail and % Effect value ≥50". The Discharger shall initiate a TIE using, as guidance, EPA manuals: *Methods for Aquatic Toxicity Identification Evaluations: Phase I Toxicity Characterization Procedures* (EPA/600/6-91/003, 1991); *Methods for Aquatic Toxicity Identification Evaluations, Phase II Toxicity Identification Procedures for Samples Exhibiting Acute and Chronic Toxicity* (EPA/600/R-92/080, 1993); *Methods for Aquatic Toxicity Identification Evaluations, Phase III Toxicity Confirmation Procedures for Samples Exhibiting Acute and Chronic Toxicity* (EPA/600/R-92/081, 1993); and *Marine Toxicity Identification Evaluation (TIE): Phase I Guidance Document* (EPA/600/R-96-054, 1996). The TIE should be conducted on the species demonstrating the most sensitive toxicity response.
3. Monthly for the first year and quarterly after the first year. For RSW-003 and RSW-004, if a quarterly sample exceeds the water quality objectives in the Ocean Plan, the monitoring frequency returns to monthly for that constituent until at least four consecutive samples demonstrate compliance with the water quality objective.
4. Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
5. Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
6. TCDD Equivalents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown in the table below. USEPA method 1613 may be used to analyze dioxin and furan congeners.

$$\text{Dioxin-TEQ (TCDD Equivalents)} = \sum (C_x \times \text{TEF}_x)$$

Where:

C_x = concentration of dioxin or furan congener x

TEF_x = TEF for congener x

Toxicity Equivalence Factors

| Isomer Group | Toxicity Equivalence Factor (TEF) |
|---------------------|-----------------------------------|
| 2,3,7,8-tetra CDD | 1.0 |
| 2,3,7,8-penta CDD | 0.5 |
| 2,3,7,8-hexa CDDs | 0.1 |
| 2,3,7,8-hepta CDD | 0.01 |
| Octa CDD | 0.001 |
| 2,3,7,8 tetra CDF | 0.1 |
| 1,2,3,7,8 penta CDF | 0.05 |
| 2,3,4,7,8 penta CDF | 0.5 |
| 2,3,7,8 hexa CDFs | 0.1 |
| 2,3,7,8 hepta CDFs | 0.01 |

7. Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
8. PAHs shall mean the sum of acenaphthylene, anthracene, 1,2-benzanthracene, 3,4-benzofluoranthene, benzo(k)fluoranthene, 1,12-benzoperylene, benzo(a)pyrene, chrysene, dibenzo(a,h)anthracene, fluorene, indeno(1,2,3-cd)pyrene, phenanthrene and pyrene.
9. HCH shall mean the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
10. DDT shall mean the sum of 4,4'-DDT, 2,4'-DDT, 4,4'-DDE, 2,4'-DDE, 4,4'-DDD and 2,4'-DDD.
11. PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254 and Aroclor-1260.
12. Monthly for the first year. For receiving water monitoring locations RSW-001 and RSW-002, the monitoring frequency may be decreased to quarterly after the first year. For RSW-003 and RSW-004, if the testing results are determined to be in compliance, the frequency of monitoring may be decreased to quarterly. If a quarterly sample exceeds the chronic toxicity limitation, the monitoring frequency returns to monthly until at least four consecutive samples demonstrate compliance with the prescribed effluent chronic toxicity limitation.

IX. OTHER MONITORING REQUIREMENTS

A. Visual Monitoring of the Receiving Water

The following general observations or measurements at the receiving water stations shall be reported when collecting receiving water samples.

1. Tidal stage, time, and date of monitoring.
2. General water conditions.
3. Extent of visible turbidity or color patches.
4. Appearance of oil films or grease, or floatable material.
5. Depth at each station for each sampling point.
6. Presence or absence of red tide.
7. Presence of marine life.
8. Presence and activity of the California least tern and the California brown pelican.

B. Outfall and Diffuser Inspection

1. The ocean outfall shall be externally inspected a minimum of once per year. Inspections shall include observations and photographic/videographic records of the outfall pipes and adjacent ocean bottom. The pipes shall be visually inspected by a diver, manned submarine, or remotely operated vehicle. A summary report of the inspection findings of the previous year shall be included in the first quarterly monitoring report (due by May 1 of each year). This written report, augmented with videographic and/or photographic

images, will provide a description of the observed condition of the discharge pipes from shallow water to their respective termini.

X. REPORTING REQUIREMENTS

A. General Monitoring and Reporting Requirements

1. The Discharger shall comply with all Standard Provisions (Attachment D) related to monitoring, reporting, and recordkeeping.
2. If there is no discharge during any reporting period, the report shall so state.
3. If the Discharger monitors (other than for process/operational control, startup, research, or equipment testing) any influent, effluent, or receiving water constituent more frequently than required by this Permit using approved analytical methods, the results of those analyses shall be included in the monitoring report. These results shall be reflected in the calculation of the average (or median) used in demonstrating compliance with this Order/Permit.
4. Each monitoring report shall contain a separate section titled "Summary of Non-Compliance" which discusses the compliance record and corrective actions taken or planned that may be needed to bring the discharge into full compliance with waste discharge requirements. This section shall clearly list all non-compliance with waste discharge requirements, as well as all excursions of effluent limitations.
5. The Discharger shall inform the Regional Water Board well in advance of any proposed construction activity that could potentially affect compliance with applicable requirements.
6. The Discharger shall report the results of chronic toxicity testing, TRE and TIE as required in the Attachment E, Monitoring and Reporting, section V.

B. Self-Monitoring Reports (SMR's)

1. At any time during the term of this permit, the State or Regional Water Board may notify the Discharger to electronically submit Self-Monitoring Reports (SMRs) using the State Water Board's California Integrated Water Quality System (CIWQS) Program Web site (<http://www.waterboards.ca.gov/ciwqs/index.html>). The CIWQS Web site will provide additional directions for SMR submittal in the event there will be service interruption for electronic submittal.

Until such notification is given, the Discharger shall submit SMRs that are less than 10 MB by email to losangeles@waterboards.ca.gov. Documents that are 10 MB or larger should be transferred to disk and mailed to:

California Regional Water Quality Control Board
Los Angeles Region
320 West 4th Street, Suite 200
Los Angeles, CA 90013

2. The Discharger shall report in the SMR the results for all monitoring specified in this MRP under sections III through IX. The Discharger shall submit quarterly SMR's including the results of all required monitoring using U.S. EPA-approved test methods or other test methods specified in this Order. SMR's are to include all new monitoring results obtained since the last SMR was submitted. If the Discharger monitors any pollutant more frequently than required by this Order, the results of this monitoring shall be included in the calculations and reporting of the data submitted in the SMR.

3. Monitoring periods and reporting for all required monitoring shall be completed according to the following schedule:

Table E-4. Monitoring Periods and Reporting Schedule

| Sampling Frequency | Monitoring Period Begins On... | Monitoring Period | SMR Due Date |
|--------------------|--------------------------------|---|---|
| Continuous | May 1, 2014 | All | Submit with quarterly SMR |
| Monthly | May 1, 2014 | 1 st day of calendar month through last day of calendar month | Submit with quarterly SMR |
| Quarterly | May 1, 2014 | January 1 - March 31 April 1 - June 30 July 1 - September 30 October 1 - December 31 | May 1 August 1 November 1 February 1 |
| Semiannually | July 1, 2014 | January 1 - June 30 July 1 - December 31 | August 1 February 1 |

4. Reporting Protocols. The Discharger shall report with each sample result the applicable reported Minimum Level (reported ML, also known as the Reporting Level, or RL) and the current Method Detection Limit (MDL), as determined by the procedure in 40 C.F.R. part 136.

The Discharger shall report the results of analytical determinations for the presence of chemical constituents in a sample using the following reporting protocols:

- a. Sample results greater than or equal to the reported ML shall be reported as measured by the laboratory (i.e., the measured chemical concentration in the sample).
- b. Sample results less than the reported ML, but greater than or equal to the laboratory’s MDL, shall be reported as “Detected, but Not Quantified,” or DNQ. The estimated chemical concentration of the sample shall also be reported.

For the purposes of data collection, the laboratory shall write the estimated chemical concentration next to DNQ. The laboratory may, if such information is available, include numerical estimates of the data quality for the reported result. Numerical estimates of data quality may be percent accuracy (\pm a percentage of the reported value), numerical ranges (low to high), or any other means considered appropriate by the laboratory.

- c. Sample results less than the laboratory’s MDL shall be reported as “Not Detected,” or ND.
 - d. Dischargers are to instruct laboratories to establish calibration standards so that the ML value (or its equivalent if there is differential treatment of samples relative to calibration standards) is the lowest calibration standard. At no time is the Discharger to use analytical data derived from extrapolation beyond the lowest point of the calibration curve.
5. Compliance Determination. Compliance with effluent limitations for reportable pollutants shall be determined using sample reporting protocols defined above and Attachment A of this Order. For purposes of reporting and administrative enforcement by the Los Angeles Regional Water Board and State Water Board, the Discharger shall be deemed out of

compliance with effluent limitations if the concentration of the reportable pollutant in the monitoring sample is greater than the effluent limitation and greater than or equal to the reported Minimum Level (ML).

6. Multiple Sample Data. When determining compliance with a measure of central tendency (arithmetic mean, geometric mean, median, etc.) of multiple sample analyses and the data set contains one or more reported determinations of “Detected, but Not Quantified” (DNQ) or “Not Detected” (ND), the Discharger shall compute the median in place of the arithmetic mean in accordance with the following procedure:
 - a. The data set shall be ranked from low to high, ranking the reported ND determinations lowest, DNQ determinations next, followed by quantified values (if any). The order of the individual ND or DNQ determinations is unimportant.
 - b. The median value of the data set shall be determined. If the data set has an odd number of data points, then the median is the middle value. If the data set has an even number of data points, then the median is the average of the two values around the middle unless one or both of the points are ND or DNQ, in which case the median value shall be the lower of the two middle values where DNQ is lower than a value and ND is lower than DNQ.
7. The Discharger shall submit SMR’s in accordance with the following requirements:
 - a. The Discharger shall arrange all reported data in a tabular format. The data shall be summarized to clearly illustrate whether the facility is operating in compliance with interim and/or final effluent limitations. The Discharger is not required to duplicate the submittal of data that is entered in a tabular format within CIWQS. When electronic submittal of data is required and CIWQS does not provide for entry into a tabular format within the system, the Discharger shall electronically submit the data in a tabular format as an attachment.
 - b. The Discharger shall attach a cover letter to the SMR. The information contained in the cover letter shall clearly identify violations of the WDR’s; discuss corrective actions taken or planned; and the proposed time schedule for corrective actions. Identified violations must include a description of the requirement that was violated and a description of the violation.

C. Discharge Monitoring Reports (DMR’s)

1. At any time during the term of this permit, the State Water Board or the Los Angeles Regional Water Board may notify the Discharger to electronically submit DMR’s. Until such notification is given specifically for the submittal of DMR’s, the Discharger shall submit DMR’s in accordance with the requirements described below.
2. DMR’s must be signed and certified as required by the standard provisions (Attachment D). The Discharger shall submit the original DMR and one copy of the DMR to the address listed below:

| STANDARD MAIL | FEDEX/UPS/ OTHER PRIVATE CARRIERS |
|--|--|
| State Water Resources Control Board Division of Water Quality c/o DMR Processing Center PO Box 100 Sacramento, CA 95812-1000 | State Water Resources Control Board Division of Water Quality c/o DMR Processing Center 1001 I Street, 15 th Floor Sacramento, CA 95814 |

3. All discharge monitoring results must be reported on the official U.S. EPA pre-printed DMR forms (EPA Form 3320-1) or on self-generated forms that follow the exact same format of EPA Form 3320-1.

D. Other Reports

1. The Discharger shall report the results of any special studies, acute toxicity testing, chronic toxicity testing, and TRE/TIE required by Special Provisions – VI.C.2 and 3 of this Order. The Discharger shall submit reports in compliance with SMR reporting requirements described in subsection X.B above.
2. Within 90 days of the effective date of this permit, the Discharger is required to submit the following required by Special Provisions of this Order to the Regional Water Board:
 - a. An Initial Investigation TRE workplan.
 - b. An updated Storm Water Pollution Prevention Plan (SWPPP).
 - c. An updated Best Management Practices Plan (BMPP).
3. Within 90 days after the adoption of the permit, the Discharger is required to submit the following required by Special Provisions of this Order to the Regional Water Board:
 - a. Mixing Zone Study Work Plan.
 - b. Sediment Loading Study Work Plan.

ATTACHMENT F – FACT SHEET

Contents

- I. Permit Information F-3
- II. Facility Description F-4
 - A. Description of Wastewater and Biosolids Treatment and Controls F-5
 - B. Discharge Points and Receiving Waters F-7
 - C. Summary of Existing Requirements and Self-Monitoring Report (SMR) Data F-8
 - D. Compliance Summary F-11
 - E. Planned Changes F-11
- III. Applicable Plans, Policies, and Regulations F-12
 - A. Legal Authorities F-12
 - B. California Environmental Quality Act (CEQA) F-12
 - C. State and Federal Laws, Regulations, Policies, and Plans F-12
 - D. Impaired Water Bodies on CWA 303(d) List F-14
 - E. Other Plans, Policies and Regulations – Not Applicable F-15
- IV. Rationale for Effluent Limitations and Discharge Specifications F-15
 - A. Discharge Prohibitions F-15
 - B. Technology-Based Effluent Limitations F-16
 - 1. Scope and Authority F-16
 - 2. Applicable Technology-Based Effluent Limitations F-16
 - C. Water Quality-Based Effluent Limitations (WQBELs) F-17
 - 1. Scope and Authority F-17
 - 2. Applicable Beneficial Uses and Water Quality Criteria and Objectives F-18
 - 3. Determining the Need for WQBELs F-18
 - 4. WQBEL Calculations F-21
 - 5. Temperature F-22
 - 6. Whole Effluent Toxicity (WET) F-22
 - 7. Final WQBELs F-23
 - D. Final Effluent Limitation Considerations F-28
 - 1. Anti-Backsliding Requirements F-29
 - 2. Antidegradation Policies F-29
 - 3. Stringency of Requirements for Individual Pollutants F-29
 - E. Interim Effluent Limitations – Not Applicable F-35
 - F. Land Discharge Specifications – Not Applicable F-35
 - G. Recycling Specifications – Not Applicable F-35
- V. Rationale for Receiving Water Limitations F-36
 - A. Surface Water F-36
 - B. Groundwater – Not Applicable F-36
- VI. Rationale for Provisions F-36
 - A. Standard Provisions F-36
 - B. Special Provisions F-36
 - 1. Reopener Provisions F-36
 - 2. Special Studies and Additional Monitoring Requirements F-36
 - 3. Best Management Practices and Pollution Prevention F-37
 - 4. Construction, Operation, and Maintenance Specifications F-37
- VII. Rationale for Monitoring and Reporting Requirements F-37
 - A. Influent Monitoring – Not Applicable F-37
 - B. Effluent Monitoring F-37

C. Whole Effluent Toxicity Testing Requirements F-37
 D. Receiving Water Monitoring F-38
 E. Other Monitoring Requirements F-38
 VIII. Public Participation F-38
 A. Notification of Interested Parties F-38
 B. Written Comments F-38
 C. Public Hearing F-38
 D. Reconsideration of Waste Discharge Requirements F-39
 E. Information and Copying F-39
 F. Register of Interested Persons F-39
 G. Additional Information F-39

Tables

Table F-1. Facility Information F-3
 Table F-2. Summary of the Currently Identified Sources and Discharges to the RSMP F-6
 Table F-3. Characteristics of the Diffuser on the Hueneme Outfall F-7
 Table F-4. Historic Effluent Limitations and Monitoring Data F-8
 Table F-5. Basin Plan Beneficial Uses F-12
 Table F-6. Ocean Plan Beneficial Uses F-13
 Table F-7. Summary of Final Technology-based Effluent Limitations F-17
 Table F-8. Ocean Plan Water Quality Objectives F-18
 Table F-9. Background Seawater Concentrations (C_S) F-22
 Table F-10. Summary of Water Quality-based Effluent Limitations F-23
 Table F-11. Summary of Final Effluent Limitations F-30

ATTACHMENT F – FACT SHEET

As described in section I, the Los Angeles Regional Water Board incorporates this Fact Sheet as findings of the Los Angeles Regional Water Board supporting the issuance of this Order. This Fact Sheet includes the legal requirements and technical rationale that serve as the basis for the requirements of this Order.

This Order has been prepared under a standardized format to accommodate a broad range of discharge requirements for Dischargers in California. Only those sections or subsections of this Order that are specifically identified as “not applicable” have been determined not to apply to this Discharger. Sections or subsections of this Order not specifically identified as “not applicable” are fully applicable to this Discharger.

I. PERMIT INFORMATION

The following table summarizes administrative information related to the facility.

Table F-1. Facility Information

| | |
|---|--|
| WDID | 4A560130001 |
| Discharger | Calleguas Municipal Water District |
| Name of Facility | Regional Salinity Management Pipeline (RSMP) |
| Facility Address | 2100 Olsen Road |
| | Thousand Oaks, CA 91360 |
| | Ventura County |
| Facility Contact, Title and Phone | Amy Maday, Regulatory Compliance Supervisor, (805) 579-7117 |
| Authorized Person to Sign and Submit Reports | Tony Goff, Manager of Operations and Maintenance |
| Mailing Address | 2100 Olsen Road, Thousand Oaks, CA 91360 |
| Billing Address | Same as above |
| Type of Facility | Wholesale water supplier, SIC Code 4941 |
| Major or Minor Facility | Major |
| Threat to Water Quality | 3 |
| Complexity | C |
| Pretreatment Program | N/A |
| Recycling Requirements | N/A |
| Facility Permitted Flow | 17.52 MGD (million gallons per day) |
| Facility Design Flow | 19.1 MGD (million gallons per day) |
| Watershed | Ventura County Coastal |
| Receiving Water | Pacific Ocean |
| Receiving Water Type | Ocean waters |

- A. Calleguas Municipal Water District (hereinafter Discharger or CMWD) is a wholesale water supplier to cities and unincorporated areas in Ventura County south and east of the Santa Clara River. CMWD is in the process of constructing a pipeline (the Calleguas Regional Salinity Management Pipeline, or RSMP) that will collect and discharge treated effluent from publicly-owned treatment works (POTWs) and concentrates from brackish groundwater desalter plants and wastewater treatment facilities throughout the Calleguas Creek Watershed. CMWD is the owner and operator of the RSMP, or Facility. CMWD is hereinafter referred to as Discharger.

For the purposes of this Order, references to the “discharger” or “permittee” in applicable federal and state laws, regulations, plans, or policy are held to be equivalent to references to the Discharger herein.

- B. The Facility proposes to discharge wastewater and concentrates to the Pacific Ocean, at Port Hueneme Beach, a water of the United States. The Discharger was previously regulated by Order R4-2008-0014 and National Pollutant Discharge Elimination System (NPDES) Permit No. CA0064521, which was adopted on April 3, 2008, and expired on March 10, 2013. However, as per 40 CFR section 122 the permit has been administratively extended until the Board takes action on this item. Attachment B provides a map of the area around the Facility. Attachment C provides a flow schematic of the Facility.
- C. The Discharger filed a report of waste discharge and submitted an application for reissuance of its WDR’s and NPDES permit on September 14, 2012. The application was deemed complete on December 12, 2013. A site visit was conducted on October 9, 2012, to observe operations and collect additional data to develop permit limitations and requirements for waste discharge.

II. FACILITY DESCRIPTION

CMWD is building the Calleguas Regional Salinity Management Pipeline (RSMP), which will extend from Simi Valley to Port Hueneme, to discharge both tertiary-treated municipal wastewaters and concentrates generated by membrane treatment of groundwater and wastewater treatment facilities to the Pacific Ocean. The operation of the RSMP will effectively reduce the current salt loadings to the Calleguas Creek Watershed by conveying saline waters and concentrate for discharge to the Pacific Ocean. Portions of the RSMP are expected to be completed and operational by the end of 2013.

The RSMP diameter varies along the length of the pipeline and is a maximum of 48 inches in internal diameter near the downstream end. Pipeline materials also vary along the pipeline and include high-density polyethylene (HDPE), polyvinyl chloride (PVC), and welded steel (WSP).

The RSMP is scheduled for construction in multiple phases as described below:

- Phase 1 was comprised of five segments (i.e., 1A, 1B, 1C, 1D, and 1E) and constructed the RSMP from Camrosa Water Reclamation Facility (WRF) to the Hueneme Outfall.
- Phase 2 is also comprised of five segments, described as follows:
 - Phases 2A, 2B, and 2C run along Lewis Road, cross Highway 101 and extend up to Somis Road.
 - Phases 2D, and 2E will run along Somis Road and then adjacent to Highway 118/Los Angeles Avenue. This phase will collect concentrate from desalters in the Somis area and wastewater from the Moorpark Wastewater Treatment Plant.
- Phase 3 extends through Moorpark and Simi Valley. This phase will collect concentrate from desalters in the Moorpark and Simi Valley areas.

CMWD indicated that Phase 1 of the RSMP, from the Camrosa Water Reclamation Facility (WRF) to the Hueneme Outfall, has been completed. Phases 2A and 2C are also completed and expected to be operational in 2013/2014. The remaining portions of Phase 2 (i.e., 2B, 2D, and 2E) are in design and expected to be online within the timeframe of the next permit cycle, by 2018. Phase 3 is still being projected for future work. CMWD anticipates discharge from the RSMP to the Hueneme Outfall will commence in 2014.

A. Description of Wastewater and Biosolids Treatment and Controls

CMWD indicated in the ROWD that the sources for the RSMP over the permit term include highly treated effluent from two POTWs and concentrate from five membrane groundwater treatment plants not yet operational. In addition, concentrate generated by an existing brackish water reclamation demonstration facility will be discharged into the RSMP.

The eight sources currently identified for discharging flow into the RSMP are as follows:

- Camarillo Water Reclamation Plant (WRP) (existing)
- Camrosa WRF (existing)
- Ventura County Waterworks District Moorpark Desalter (future)
- Agricultural Somis Desalter (future)
- Camarillo North Pleasant Valley Desalter (future)
- Camrosa Round Mountain Water Treatment Plant (WTP) (existing)
- Agricultural Desalters (future)
- Port Hueneme Water Agency (PHWA) Brackish Water Reclamation Demonstration Facility (BWRDF) (existing)

Discharges from the Camarillo WRP are currently regulated by NPDES Permit No. CA0053597. The WRP has a treatment capacity of 6.75 MGD and provides wastewater treatment consisting of primary treatment, activated sludge treatment, nitrification/denitrification, secondary clarification, tertiary filtration, chlorination, and dechlorination. A portion of the effluent is recycled for landscape and agricultural use. Effluent flow in excess of recycled water demand is discharged into Conejo Creek and varies with the seasonal demand for recycled water. CMWD estimated in the ROWD the discharge flow from the Camarillo WRP would be 3.8 MGD for 30 days out of the year.

Discharges from the Camrosa WRF are regulated by NPDES Permit No. CA0059501. The WRF has a treatment capacity of 1.5 MGD. In 2000, the average flow was 1.34 MGD. Wastewater treatment is provided through extended aeration, nitrogen removal, secondary clarification, tertiary filtration, and disinfection. The WRF does not currently dechlorinate prior to discharge; however, the WRF's operations will change to include dechlorination prior to initiating discharge to the RSMP. Effluent from the WRF is recycled for landscaping and agricultural use. The NPDES Permit allows discharge into Calleguas Creek when the volume of wastewater exceeds the recycled demand and storage pond capacity. CMWD noted in the ROWD that most years, the WRF does not discharge into Calleguas Creek, but when they do occur, discharges extend for one to two weeks in the spring. The WRF would direct excess flows to the RSMP in lieu of discharges to Calleguas Creek.

Ventura County Waterworks District plans to build a desalter west of the City of Moorpark, generally along Highway 118, to treat the groundwater in the vicinity of the City of Moorpark, which has concentrations of chloride and TDS which make it unsuitable for potable water use. A feasibility study has been completed for the desalter, groundwater modeling is underway, and operation is expected in 2017. The desalter is expected to produce a brine discharge of approximately 1.49 MGD.

Agricultural pumpers, including mutual water companies and private entities, are working together to build one or more desalters to allow them to treat the shallow groundwater in the vicinity of Somis, to make it suitable for agricultural irrigation on crops. The desalter is expected to be located east of Somis, generally along Highway 118. A feasibility study has been completed for the desalter and operation is expected to begin in 2016. The desalter is expected to produce a brine discharge of 0.79 MGD.

The City of Camarillo currently operates two wells (Wells A & B) with high salinity which are blended with imported Calleguas water to achieve drinking water quality standards. The City of Camarillo plans to install one or two additional wells in the area and treat the water from all of the wells with the proposed North Pleasant Valley (NPV) Desalter. The desalter will be in the City of Camarillo at the intersection of Las Posas Road and Lewis Road. The treatment plant pilot testing and the groundwater modeling have been completed. The operation is expected to begin in 2016. It is expected to produce a brine discharge of 2.14 MGD.

The Camrosa Round Mountain WTP is currently located at the Camrosa WRF. The Facility includes a raw water supply pipeline from the existing University Well to the treatment plant site, finished water pipeline to pressure distribution system and a concentrate disposal line to the RSMP. The project began discharging to the RSMP in January 2014. The WTP is expected to produce a maximum brine discharge of 0.16 MGD.

CMWD is also expecting discharges from various agricultural users on the Oxnard Plain who are interested in attaining sources with lower salinity concentrations than their local groundwater. Agricultural interests in the area have expressed the desire to install reverse osmosis (RO) facilities at local irrigation wells and dispose of the RO reject to the RSMP. Brine water quality would vary based on the local water sources. Brine water quality should be similar to other nearby desalters. The schedule for construction of these desalters is not known. It is anticipated to be one or more agricultural desalters with brine discharges totaling approximately 2.55 MGD.

The BWRDF is owned by the PHWA and is located along Perkins Road in the City of Oxnard. The BWRDF was constructed in 1998, with startup in January 1999. The BWRDF incorporates a combination of desalting treatment technologies, including RO and nanofiltration (NF). Currently, chloraminated water is treated through the membranes at the BWRDF. Once PHWA begins discharging its concentrate streams into the RSMP, the Agency will change its operations to ensure dechlorination occurs before discharge. It is designed to treat 4.5 MGD of influent water and creates a combined concentrate stream of approximately 1.69 MGD.

CMWD indicated that the specific discharges listed above may not be inclusive of all flows that may discharge to the RSMP during the permit term. CMWD is required to notify the Los Angeles Regional Water Board of the location, type, and connection schedule for any new discharges to the RSMP that are not set forth in the proposed Order. CMWD indicated that additional flows will be allowed to discharge to the RSMP only if:

- They consist of potable water, groundwater, concentrate resulting from membrane treatment of potable water or groundwater, or concentrate resulting from membrane treatment of tertiary treated wastewater sources specifically listed in the Order;
- The discharge does not exceed effluent and receiving water quality-based limitations established in the Order;
- The total discharge does not exceed the maximum flow rate established by the Order.

All treatment of the discharges would be complete prior to entering the RSMP. The RSMP is used solely to transport the combined effluents to the discharge point at the Hueneme Outfall.

Table F-2. Summary of the Currently Identified Sources and Discharges to the RSMP

| Name of Facility | Flow (MGD) |
|---------------------------------|------------|
| POTWs: | |
| Camarillo Sanitary District WRP | 3.8 |

| Name of Facility | Flow (MGD) |
|-------------------------------------|--------------|
| Camrosa WRF | 1.5 |
| Desalters: | |
| VCWWD Moorpark Desalter | 1.49 |
| Somis Agricultural Desalter | 0.79 |
| Camarillo NPV Desalter | 2.14 |
| Camrosa Round Mountain Desalter | 0.16 |
| Oxnard Plain Agricultural Desalters | 2.55 |
| PHWA BWRDF | 1.69 |
| Total | 14.12 |

B. Discharge Points and Receiving Waters

The Discharger proposes to discharge up to 19.1 MGD of treated municipal wastewaters and concentrates generated by membrane treatment of groundwater and wastewater treatment facilities, into the Pacific Ocean at Port Hueneme Beach, a water of the United States, (Latitude 34° 08' 34.75" North, Longitude 119° 11' 33.72" West).

CMWD is the owner and operator of the Hueneme Outfall which will solely discharge flow from the RSMP. The landside portion of the RSMP connects with the Hueneme Outfall for discharge into the Pacific Ocean at Port Hueneme Beach. The discharge point for the Hueneme Outfall will be located approximately 4,000 feet offshore. The diffuser on the Hueneme Outfall is 380 feet in length and includes 30 ports. The port openings alternate so that they are at 26 foot centers on each side, staggered with ports at the same spacing on the opposite side, giving 13 foot spacing along the diffuser. Ports are above the pipe axis, discharging typically at about 20 degrees from the horizontal. The diffuser follows the sea bed slope, falling gradually offshore, from a high point at the connection to the main pipe. Characteristics of the diffuser are summarized in Table F-3.

Table F-3. Characteristics of the Diffuser on the Hueneme Outfall

| Parameter | Value |
|--------------------------------------|--------------------------------|
| Length | 5,000 feet |
| Conveyance piping inside diameter | 30 inches |
| Port diameter at opening | 5 inches |
| Port spacing | 13 feet |
| Port vertical angle | 20 degrees |
| Port horizontal angle | 132.3 degrees |
| Number of ports | 30 |
| Length of diffuser section | 380 feet |
| Ocean depth at riser | N/A |
| Approximate depth to the top of port | 47 feet (mean lower low water) |
| Exit design velocity | 10 feet per second |
| Dilution ratio | 72:1 |

CMWD has completed theoretical modeling for the Hueneme Outfall dilution ratio. The results of the modeling were originally included in the ROWD submitted on July 15, 2007. At the time of the submittal of the ROWD in 2007, the dilution ratio of the Hueneme Outfall was

determined by modeling the discharge using the USEPA-approved Visual Plumes (VP) program. Modeling runs were performed using ambient receiving water (Pacific Ocean) data collected in 2002 from the nearby Reliant Energy Ocean Outfall for salinity and temperature at various depths. Scenarios were evaluated over the range of flows expected on the RSMP, including 2, 6, 10, 14, and 19.1 MGD. The lowest dilution predicted by the VP model was 99.5:1, occurring at the highest flow rate of 19.1 MGD under 2002 summer conditions.

The modeling was updated in 2007 to use more recent (August 2006 and February 2007) receiving water data collected by the City of Oxnard. Summer and winter conditions were modeled with an assumed 19.4 MGD effluent flow in CORMIX, Visual Plumes (VP), and KOH & FAN using the updated receiving water data sets. The KOH & FAN models predicted 72:1, a lower, more conservative dilution upon reaching the surface. CORMIX predicted 94:1, and VP predicted 89:1. Discussions between RWQCB and SWRCB staff resulted in the approved dilution ratio in Calleguas' current SMP Permit (R4-2008-0014) of 72:1, the most conservative predicted by the updated models.

The State Water Board and the Los Angeles Regional Water Board reviewed the modeling and additional information provided by CMWD and granted a dilution ratio of 72:1 for discharges from the RSMP.

C. Summary of Existing Requirements and Self-Monitoring Report (SMR) Data

The RSMP has not commenced discharges yet; therefore, effluent limitations contained in the previous Order for discharges from Discharge Point 001 (Monitoring Location EFF-001) are summarized in Table F-4.

Table F-4. Historic Effluent Limitations and Monitoring Data

| Parameter | Units | Effluent Limitation | | | | | |
|---|----------------------|---------------------|----------------|---------------|--------------------|--------------------|----------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantan. Minimum | Instantan. Maximum | 6-Month Median |
| Biochemical Oxygen Demand (BOD), 5-day @ 20°C | mg/L | 30 | 45 | -- | -- | -- | -- |
| | lbs/day ¹ | 4,384 | 6,575 | -- | -- | -- | -- |
| Total Suspended Solids (TSS) | mg/L | 60 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 8,767 | -- | -- | -- | -- | -- |
| pH | s.u. | -- | -- | -- | 6.0 | 9.0 | -- |
| Oil and Grease | mg/L | 25 | 40 | -- | -- | -- | -- |
| | lbs/day ¹ | 3,653 | 5,845 | -- | -- | -- | -- |
| Settleable Solids | ml/L | 1.0 | 1.5 | -- | -- | -- | -- |
| Turbidity | NTU | 75 | 100 | -- | -- | -- | -- |
| Total Residual Chlorine | µg/L | -- | -- | 584 | -- | 4380 | 146 |
| | lbs/day ¹ | -- | -- | 85.3 | -- | 640 | 21 |
| Ammonia as N | µg/L | -- | -- | 175,200 | -- | 438,000 | 43,800 |
| | lbs/day ¹ | -- | -- | 25,600 | -- | 63,999 | 6,400 |
| Acute Toxicity | TU _a | -- | -- | 2.46 | -- | -- | -- |
| Chronic Toxicity | TU _c | -- | -- | 73 | -- | -- | -- |
| Total Coliform | MPN/100 ml | 2 | | | | | |
| Fecal Coliform | MPN/100 ml | 2 | | | | | |
| Enterococcus | MPN/100 ml | 2 | | | | | |
| Arsenic | µg/L | -- | -- | 2,120 | -- | 5,624 | 368 |
| | lbs/day ¹ | -- | -- | 310 | -- | 822 | 54 |
| Beryllium | µg/L | 2.4 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.4 | -- | -- | -- | -- | -- |

| Parameter | Units | Effluent Limitation | | | | | |
|---|----------------------|---------------------|----------------|---------------|--------------------|--------------------|----------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantan. Minimum | Instantan. Maximum | 6-Month Median |
| Cadmium | µg/L | -- | -- | 292 | -- | 730 | 73 |
| | lbs/day ¹ | -- | -- | 43 | -- | 107 | 11 |
| Chromium (VI) | µg/L | -- | -- | 584 | -- | 1,460 | 146 |
| | lbs/day ¹ | -- | -- | 85 | -- | 213 | 21 |
| Copper | µg/L | -- | -- | 732 | -- | 2,046 | 75 |
| | lbs/day ¹ | -- | -- | 107 | -- | 299 | 11 |
| Lead | µg/L | -- | -- | 584 | -- | 1,460 | 146 |
| | lbs/day ¹ | -- | -- | 85 | -- | 213 | 21 |
| Mercury | µg/L | -- | -- | 12 | -- | 29 | 3 |
| | lbs/day ¹ | -- | -- | 2 | -- | 4 | 0.4 |
| Nickel | µg/L | -- | -- | 1,460 | -- | 3,650 | 365 |
| | lbs/day ¹ | -- | -- | 213 | -- | 533 | 53 |
| Selenium | µg/L | -- | -- | 4,380 | -- | 10,950 | 1,095 |
| | lbs/day ¹ | -- | -- | 640 | -- | 1,600 | 160 |
| Silver | µg/L | -- | -- | 193 | -- | 500 | 40 |
| | lbs/day ¹ | -- | -- | 28 | -- | 73 | 6 |
| Thallium | µg/L | -- | -- | -- | -- | -- | -- |
| | lbs/day ¹ | -- | -- | -- | -- | -- | -- |
| Zinc | µg/L | -- | -- | 5,264 | -- | 14,024 | 884 |
| | lbs/day ¹ | -- | -- | 769 | -- | 2,049 | 129 |
| Cyanide | µg/L | -- | -- | 292 | -- | 730 | 73 |
| | lbs/day ¹ | -- | -- | 43 | -- | 107 | 11 |
| Phenolic Compounds (non-chlorinated) ³ | µg/L | -- | -- | 8,760 | -- | 21,900 | 2,190 |
| | lbs/day ¹ | -- | -- | 1,280 | -- | 3,200 | 320 |
| Chlorinated Phenolics ⁴ | µg/L | -- | -- | 292 | -- | 730 | 73 |
| | lbs/day ¹ | -- | -- | 43 | -- | 107 | 11 |
| TCDD Equivalents | µg/L | 2.85E-07 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 4.16E-08 | -- | -- | -- | -- | -- |
| Acrylonitrile | µg/L | 7.3 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 1.1 | -- | -- | -- | -- | -- |
| Benzene | µg/L | 431 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 63 | -- | -- | -- | -- | -- |
| Carbon Tetrachloride | µg/L | 66 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 9.6 | -- | -- | -- | -- | -- |
| Chlorodibromomethane | µg/L | 628 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 92 | -- | -- | -- | -- | -- |
| Dichlorobromomethane | µg/L | 453 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 66 | -- | -- | -- | -- | -- |
| 1,1-Dichloroethylene | µg/L | 65.7 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 9.6 | -- | -- | -- | -- | -- |
| 1,3-Dichloropropene | µg/L | 650 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 95 | -- | -- | -- | -- | -- |
| 1,1,2,2-Tetrachloroethane | µg/L | 168 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 24.5 | -- | -- | -- | -- | -- |
| Tetrachloroethylene | µg/L | 146 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 21.3 | -- | -- | -- | -- | -- |

| Parameter | Units | Effluent Limitation | | | | | |
|----------------------------|----------------------|---------------------|----------------|---------------|--------------------|--------------------|----------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantan. Minimum | Instantan. Maximum | 6-Month Median |
| 1,1,2-Trichloroethane | µg/L | 686 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 100 | -- | -- | -- | -- | -- |
| Tributyltin | µg/L | 0.102 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.015 | -- | -- | -- | -- | -- |
| 2,4-Dinitrophenol | µg/L | 292 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 43 | -- | -- | -- | -- | -- |
| 2,4,6-Trichlorophenol | µg/L | 21 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 3 | -- | -- | -- | -- | -- |
| Benzidine | µg/L | 0.005 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0007 | -- | -- | -- | -- | -- |
| Bis(2-Chloroethoxy)Methane | µg/L | 321 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 47 | -- | -- | -- | -- | -- |
| Bis(2-Chloroethyl)Ether | µg/L | 3 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.48 | -- | -- | -- | -- | -- |
| Bis(2-Ethylhexyl)Phthalate | µg/L | 256 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 37 | -- | -- | -- | -- | -- |
| 3,3'-Dichlorobenzidene | µg/L | 0.59 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.09 | -- | -- | -- | -- | -- |
| 2,4-Dinitrotoluene | µg/L | 190 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 28 | -- | -- | -- | -- | -- |
| 1,2-Diphenylhydrazine | µg/L | 12 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 1.7 | -- | -- | -- | -- | -- |
| Hexachlorobenzene | µg/L | 0.015 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.002 | -- | -- | -- | -- | -- |
| Hexachloroethane | µg/L | 182 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 27 | -- | -- | -- | -- | -- |
| Nitrobenzene | µg/L | 358 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 52 | -- | -- | -- | -- | -- |
| N-Nitrosodimethylamine | µg/L | 533 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 78 | -- | -- | -- | -- | -- |
| N-Nitrosodi-n-Propylamine | µg/L | 28 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 4 | -- | -- | -- | -- | -- |
| N-Nitrosodiphenylamine | µg/L | 182 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 27 | -- | -- | -- | -- | -- |
| Aldrin | µg/L | 0.002 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0002 | -- | -- | -- | -- | -- |
| Chlordane | µg/L | 0.002 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0002 | -- | -- | -- | -- | -- |
| DDT ⁵ | µg/L | 0.012 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.002 | -- | -- | -- | -- | -- |
| Dieldrin | µg/L | 0.003 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0004 | -- | -- | -- | -- | -- |
| Endosulfan | µg/L | -- | -- | 1.314 | -- | 1.971 | 0.657 |
| | lbs/day ¹ | -- | -- | 0.192 | -- | 0.288 | 0.096 |
| Endrin | µg/L | -- | -- | 0.292 | -- | 0.438 | 0.146 |
| | lbs/day ¹ | -- | -- | 0.043 | -- | 0.064 | 0.021 |

| Parameter | Units | Effluent Limitation | | | | | |
|--------------------|--|---------------------|----------------|---------------|--------------------|--------------------|----------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantan. Minimum | Instantan. Maximum | 6-Month Median |
| Heptachlor | µg/L | 0.004 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0005 | -- | -- | -- | -- | -- |
| Heptachlor Epoxide | µg/L | 0.002 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0002 | -- | -- | -- | -- | -- |
| PAH ⁶ | µg/L | 0.64 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.094 | -- | -- | -- | -- | -- |
| HCH ⁷ | µg/L | -- | -- | 0.58 | -- | 0.88 | 0.29 |
| | lbs/day ¹ | -- | -- | 0.085 | -- | 0.128 | 0.043 |
| PCBs ⁸ | µg/L | 0.001 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.0002 | -- | -- | -- | -- | -- |
| Toxaphene | µg/L | 0.015 | -- | -- | -- | -- | -- |
| | lbs/day ¹ | 0.002 | -- | -- | -- | -- | -- |
| Radioactivity | Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, §30253 of the California Code of Regulations. Reference to §30253 is prospective, including future changes to any incorporated provisions of federal law, as the changes take effect. | | | | | | |

1. Mass-based effluent limitations are based on a discharge flow rate of 17.52 MGD. It is the total estimated contributing flows when the previous Order was issued.
2. Bacterial Limitations:
 - a. 30-day Geometric Mean Limitations – The geometric mean shall be calculated using the five most recent sample results:
 - i. Total coliform density shall not exceed 1,000 per 100 ml;
 - ii. Fecal coliform density shall not exceed 200 per 100 ml; and
 - iii. Enterococcus density shall not exceed 35 per 100 ml.
 - b. Single-Sample Maximum (SSM)
 - i. Total coliform density shall not exceed 10,000 per 100 ml;
 - ii. Fecal coliform density shall not exceed 400 per 100 ml;
 - iii. Enterococcus density shall not exceed 104 per 100/ml; and
 - iv. The total coliform density shall not exceed 1,000 per 100 ml when the fecal coliform/total coliform ratio exceeds 0.1.
3. Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
4. Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
5. DDT shall mean the sum of 4,4'-DDT, 2,4'-DDT, 4,4'-DDE, 2,4'-DDE, 4,4'-DDD, and 2,4'-DDD.
6. PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorine; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.
7. HCH shall mean the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
8. PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, and Aroclor-1260.

D. Compliance Summary

The RSMP has not commenced discharges yet; therefore, there are no compliance issues present.

E. Planned Changes

CMWD indicated that Phase 1 of the RSMP, from the Camrosa Water Reclamation Facility (WRF) to the Hueneme Outfall, has been completed. Phases 2A and 2C are also completed and expected to be operational in 2013/2014. The remaining portions of Phase 2 (i.e., 2B, 2D,

and 2E) are in design and expected to be online within the timeframe of the next permit cycle, by 2018. Phase 3 is still being projected for future work. CMWD anticipates discharge from the RSMP to the Hueneme Outfall will commence in 2014.

III. APPLICABLE PLANS, POLICIES, AND REGULATIONS

The requirements contained in this Order are based on the requirements and authorities described in this section.

A. Legal Authorities

This Order serves as WDR’s pursuant to article 4, chapter 4, division 7 of the California Water Code (commencing with section 13260). This Order is also issued pursuant to section 402 of the federal Clean Water Act (CWA) and implementing regulations adopted by the U.S. EPA and chapter 5.5, division 7 of the Water Code (commencing with section 13370). It shall serve as an NPDES permit for point source discharges from this facility to surface waters.

B. California Environmental Quality Act (CEQA)

Under Water Code section 13389, this action to adopt an NPDES permit is exempt from the provisions of Chapter 3 of CEQA, (commencing with section 21100) of Division 13 of the Public Resources Code.

C. State and Federal Laws, Regulations, Policies, and Plans

- Water Quality Control Plan.** The Los Angeles Regional Water Board adopted a Water Quality Control Plan for the Los Angeles Region (hereinafter Basin Plan) on June 13, 1994 that designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for the Pacific Ocean and all waters addressed through the plan. In addition, the Basin Plan implements State Water Resources Control Board (State Water Board) Resolution 88-63, which established state policy that all waters, with certain exceptions, should be considered suitable or potentially suitable for municipal or domestic supply. Requirements in this Order implement the Basin Plan.

Beneficial uses applicable to the Pacific Ocean at Ventura County Coastal are as follows:

Table F-5. Basin Plan Beneficial Uses

| Discharge Point | Receiving Water Name | Beneficial Use(s) |
|-----------------|--|--|
| 001 | <p>Pacific Ocean at Port Hueneme Beach</p> <p><u>Nearshore Zone</u> (The zone bounded by the shoreline and a line 1000 feet from the shoreline or the 30-foot depth contours, whichever is further from the shoreline)</p> <p><u>Offshore Zone</u></p> | <p><u>Existing:</u> Industrial Service Supply (IND); Navigation (NAV); Water Contact (REC-1) and Non-Contact (REC-2) Recreation; Commercial and Sport Fishing (COMM); Marine Habitat (MAR); Wildlife Habitat (WILD); Preservation of Biological Habitats (BIOL)¹; Rare, Threatened or Endangered Species (RARE)²; Migration of Aquatic Organisms (MIGR)³; Spawning, Reproduction, and/or Early Development (SPWN)³; and Shellfish Harvesting (SHELL).</p> <p><u>Existing:</u> Industrial Service Supply (IND); Navigation (NAV); Water Contact (REC-1) and Non-Contact (REC-2) Recreation; Commercial and Sport Fishing (COMM); Marine Habitat (MAR); Wildlife Habitat</p> |

| Discharge Point | Receiving Water Name | Beneficial Use(s) |
|-----------------|----------------------|--|
| | | (WILD); Rare, Threatened or Endangered Species (RARE) ² ; Migration of Aquatic Organisms (MIGR) ³ ; Spawning, Reproduction, and/or Early Development (SPWN) ³ ; and Shellfish Harvesting (SHELL). |

1. Areas of Special Biological Significance (along coast from Latigo Point to Laguna Point) and Big Sycamore Canyon and Abalone Cove Ecological Reserves and Point Fermin Marine Life Refuge.
 2. One or more rare species utilize all ocean, bays, estuaries, and coastal wetlands for foraging and/or nesting.
 3. Aquatic organisms utilize all bays, estuaries, lagoons, and coastal wetlands, to a certain extent, for spawning and early development. This may include migration into areas which are heavily influenced by freshwater inputs.
2. **Thermal Plan.** The State Water Board adopted the Water Quality Control Plan for Control of Temperature in the Coastal and Interstate Waters and Enclosed Bays and Estuaries of California (Thermal Plan) on January 7, 1971, and amended this plan on September 18, 1975. This plan contains temperature objectives for coastal waters. Requirements of this Order implement the Thermal Plan.
 3. **California Ocean Plan.** The State Water Board adopted the Water Quality Control Plan for Ocean Waters of California, California Ocean Plan (Ocean Plan) in 1972 and amended it in 1978, 1983, 1988, 1990, 1997, 2000, 2005, 2009 and 2012. The State Water Board adopted the latest amendment on October 16, 2012, and it became effective on July 1, 2013. The Ocean Plan is applicable, in its entirety, to point source discharges to the ocean. The Ocean Plan identifies beneficial uses of ocean waters of the state to be protected as summarized below:

Table F-6. Ocean Plan Beneficial Uses

| Discharge Point | Receiving Water | Beneficial Uses |
|-----------------|-----------------|--|
| 001 | Pacific Ocean | Industrial water supply; water contact and non-contact recreation, including aesthetic enjoyment; navigation; commercial and sport fishing; mariculture; preservation and enhancement of designated Areas of Special Biological Significance (ASBS); rare and endangered species; marine habitat; fish spawning and shellfish harvesting |

In order to protect the beneficial uses, the Ocean Plan establishes water quality objectives and a program of implementation. Requirements of this Order implement the Ocean Plan.

4. **Antidegradation Policy.** Federal regulation 40 C.F.R. section 131.12 requires that the state water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California’s antidegradation policy in State Water Board Resolution 68-16. Resolution 68-16 is deemed to incorporate the federal antidegradation policy where the federal policy applies under federal law. Resolution 68-16 requires that existing water quality be maintained unless degradation is justified based on specific findings. The Los Angeles Regional Water Board’s Basin Plan implements, and incorporates by reference, both the state and federal antidegradation policies. The permitted discharge must be consistent with the antidegradation provision of section 131.12 and State Water Board Resolution 68-16.

The Ocean Plan (2012) Item III.C (Implementation Provisions for Table 1) 3 includes a requirement that “Effluent limits shall be imposed in a manner prescribed by the State

Water Board such that the concentrations set forth as water quality objectives shall not be exceeded in the receiving water upon completion of initial dilution, except that objectives indicated for radioactivity shall apply directly to the undiluted waste effluent.” Item III.F (Revision of Waste Discharge Requirements) 1 of the Ocean Plan states that “The Regional Boards may establish more restrictive water quality objectives and effluent limitations than those set forth in this Plan as necessary for the protection of beneficial uses of ocean waters.”

The RSMP proposes to discharge treated wastewater from POTWs and concentrates generated by membrane treatment of groundwater and wastewater treatment facilities. Up to the time of drafting this permit, there are no data available to characterize the mixed wastes as they will be discharged. The analysis of the discharge is based solely on theoretical modeling of the proposed individual components of the discharge, including historical monitoring data for the wastewater treatment plants and one of the desalters and assumptions for other desalters that are not yet operating. Therefore, this Order includes effluent limitations for all of the constituents listed in the Ocean Plan. Upon commencement of discharges from the RSMP, the Los Angeles Regional Water Board may use actual discharge data to evaluate the need for effluent limitations based on water quality objectives in the Ocean Plan.

5. **Anti-Backsliding Requirements.** Sections 402(o) and 303(d)(4) of the CWA and federal regulations at 40 C.F.R. section 122.44(l) restrict backsliding in NPDES permits. These anti-backsliding provisions require that effluent limitations in a reissued permit must be as stringent as those in the previous permit, with some exceptions in which limitations may be relaxed.
6. **Endangered Species Act Requirements.** This Order does not authorize any act that results in the taking of a threatened or endangered species or any act that is now prohibited, or becomes prohibited in the future, under either the California Endangered Species Act (Fish and Game Code, §§ 2050 to 2097) or the Federal Endangered Species Act (16 U.S.C.A. §§ 1531 to 1544). This Order requires compliance with effluent limits, receiving water limits, and other requirements to protect the beneficial uses of waters of the state, including protecting rare and endangered species. The discharger is responsible for meeting all requirements of the applicable Endangered Species Act.

D. Impaired Water Bodies on CWA 303(d) List

Section 303(d) of the CWA requires states to identify specific water bodies where water quality standards are not expected to be met after implementation of technology-based effluent limitations on point sources. For all 303(d)-listed water bodies and pollutants, the Los Angeles Regional Water Board plans to develop and adopt TMDLs that will specify WLAs for point sources and load allocations (LAs) for non-point sources, as appropriate.

On November 10, 2010, the USEPA approved the State Water Board’s 2010 303(d) List of Water Quality Limited Segments (hereinafter 303(d) list). The 303(d) list identifies water bodies where water quality standards are not expected to be met after implementation of technology-based effluent limitations by point sources (water quality limited water bodies).

Ormond Beach (including the area of Ormond Beach at Oxnard Drain) is on the 303(d) List for indicator bacteria. In addition, Port Hueneme Pier is listed for polychlorinated biphenyls (PCBs). Port Hueneme Harbor (Back Basins) is listed for DDT (tissue) and PCBs (tissue). Total Maximum Daily Loads (TMDLs) for these pollutants have not been completed. Completion of the TMDLs affecting Ormond Beach and Port Hueneme Pier is expected in 2015 and in 2019, respectively. The 303(d) List indicates the TMDL affecting Port Hueneme

Harbor is being addressed by an action other than a TMDL and attainment is expected in 2019.

E. Other Plans, Polices and Regulations – Not Applicable

IV. RATIONALE FOR EFFLUENT LIMITATIONS AND DISCHARGE SPECIFICATIONS

The CWA requires point source dischargers to control the amount of conventional, non-conventional, and toxic pollutants that are discharged into the waters of the United States. The control of pollutants discharged is established through effluent limitations and other requirements in NPDES permits. There are two principal bases for effluent limitations in the Code of Federal Regulations: 40 C.F.R. section 122.44(a) requires that permits include applicable technology-based limitations and standards; and 40 C.F.R. section 122.44(d) requires that permits include water quality-based effluent limitations to attain and maintain applicable numeric and narrative water quality criteria to protect the beneficial uses of the receiving water.

The RSMP has not commenced discharging at the time of the drafting of this Fact Sheet. The list of pollutants of concern is based on constituents that are regulated in the Ocean Plan, as well as pollutants listed in the 303(d) List for Ormond Beach, Port Hueneme Pier, and Port Hueneme Harbor (e.g., pesticides and PCBs). Further, as indicated in the permit renewal application, the combined flow from the eight sources identified for discharging into the RSMP consists of highly-treated municipal wastewater effluent and reject concentrates from treatment facilities. Pollutants of concern typically present in treated municipal wastewater would include pollutants contributing to biochemical oxygen demand (BOD), turbidity, total suspended solids, elevated temperatures, oil and grease, pH, pathogens, nutrients, and toxic parameters (e.g., metals, volatile organic compounds, and pesticides). Settleable solids is another parameter often measured in municipal wastewaters. In addition, pollutants expected to be present in the discharge of reject concentrates from groundwater treatment include parameters contributing to total dissolved solids (TDS), sulfate, chloride, sodium, and boron.

Further, pollutants in the combined discharge may contribute to toxicity in the receiving water. Whole effluent toxicity (WET) is an indicator of the combined effect of pollutants contained in the discharge. Chronic toxicity is a more stringent requirement than acute toxicity. Therefore, chronic toxicity is considered a pollutant of concern for evaluation of narrative Basin Plan Objectives and Water Quality Objectives in the Ocean Plan.

Generally, mass-based effluent limitations ensure that proper treatment, and not dilution, is employed to comply with the final effluent concentration limitations. Section 122.45(f)(1) requires that all permit limitations, standards or prohibitions be expressed in terms of mass units except under the following conditions: (1) for pH, temperature, radiation or other pollutants that cannot appropriately be expressed by mass limitations; (2) when applicable standards or limitations are expressed in terms of other units of measure; or (3) if in establishing technology-based permit limitation on a case-by-case basis limitation based on mass are infeasible because the mass or pollutant cannot be related to a measure of production. The limitations, however, must ensure that dilution will not be used as a substitute for treatment.

A. Discharge Prohibitions

The discharge prohibitions are based on the requirements of the Ocean Plan, State Water Board's plans and policies, the Water Code, and previous permit provisions, and are consistent with the requirements set for other discharges regulated by NPDES permits to the Pacific Ocean.

B. Technology-Based Effluent Limitations

1. Scope and Authority

Section 301(b) of the CWA and implementing USEPA permit regulations at 40 C.F.R. section 122.44 require that permits include conditions meeting applicable technology-based requirements at a minimum, and any more stringent effluent limitations necessary to meet applicable water quality standards. The discharge authorized by this Order must meet minimum federal technology-based requirements based on Best Professional Judgment (BPJ) in accordance with 40 C.F.R. section 125.3.

The CWA requires that technology-based effluent limitations be established based on several levels of controls:

- a.** Best practicable treatment control technology (BPT) represents the average of the best existing performance by well-operated facilities within an industrial category or subcategory. BPT standards apply to toxic, conventional, and non-conventional pollutants.
- b.** Best available technology economically achievable (BAT) represents the best existing performance of treatment technologies that are economically achievable within an industrial point source category. BAT standards apply to toxic and non-conventional pollutants.
- c.** Best conventional pollutant control technology (BCT) represents the control from existing industrial point sources of conventional pollutants including BOD, TSS, fecal coliform, pH, and oil and grease. The BCT standard is established after considering a two-part reasonableness test. The first test compares the relationship between the costs of attaining a reduction in effluent discharge and the resulting benefits. The second test examines the cost and level of reduction of pollutants from the discharge from publicly owned treatment works to the cost and level of reduction of such pollutants from a class or category of industrial sources. Effluent limitations must be reasonable under both tests.
- d.** New source performance standards (NSPS) represent the best available demonstrated control technology standards. The intent of NSPS guidelines is to set limitations that represent state-of-the-art treatment technology for new sources.

The CWA requires USEPA to develop effluent limitations, guidelines and standards (ELGs) representing application of BPT, BAT, BCT, and NSPS. Section 402(a)(1) of the CWA and 40 C.F.R. section 125.3 authorize the use of best professional judgment (BPJ) to derive technology-based effluent limitations on a case-by-case basis where ELGs are not available for certain industrial categories and/or pollutants of concern. Where BPJ is used, the Los Angeles Regional Water Board must consider specific factors outlined in 40 C.F.R. section 125.3.

2. Applicable Technology-Based Effluent Limitations

This Order includes technology-based effluent limitations based on BPJ in accordance with 40 C.F.R. section 125.3. The previous Order included effluent limitations for oil and grease, TSS, settleable solids, turbidity, and pH based on the effluent limitations contained in Table 2 of the Ocean Plan. The Ocean Plan indicates Table 2 effluent limitations apply only to publicly-owned treatment works and industrial discharges for which ELGs have not been established. The discharge from the RSMP is comprised in part of treated municipal wastewater; therefore, Table 2 effluent limitations are

appropriate for this discharge. In addition, this Order establishes technology-based effluent limitations for BOD₅ based on BPJ, applying Secondary Treatment Standards specified in 40 C.F.R. Part 133. This Order establishes limits for oil and grease, TSS, settleable solids, turbidity, and pH based on the effluent limitations contained in Table 2 of the Ocean Plan and for BOD₅ based on EPA’s Secondary Treatment Standards.

Section 402(o) of the CWA and 40 C.F.R. section 122.44(l) require that effluent limitations or conditions in reissued Orders be at least as stringent as those in the existing Orders. Table F-7 summarizes the final technology based effluent limitations:

Table F-7. Summary of Final Technology-based Effluent Limitations

| Parameter | Unit | Effluent Limitations | | | |
|-------------------|----------------------|----------------------|----------------|-----------------------|-----------------------|
| | | Average Monthly | Average Weekly | Instantaneous Minimum | Instantaneous Maximum |
| BOD ₅ | mg/L | 30 | 45 | -- | -- |
| | lbs/day ¹ | 4,400 | 6,600 | -- | -- |
| Oil and Grease | mg/L | 25 | 40 | -- | 75 |
| | lbs/day ¹ | 3,700 | 5,800 | -- | 11,000 |
| TSS | mg/L | 60 | -- | -- | -- |
| | lbs/day ¹ | 8,800 | -- | -- | -- |
| Settleable Solids | ml/L | 1.0 | 1.5 | -- | 3.0 |
| Turbidity | NTU | 75 | 100 | -- | 225 |
| pH | s.u. | -- | -- | 6.0 | 9.0 |

1. Mass-based effluent limitations are based on the facility design flow rate of 17.52 MGD.

This Order requires the Discharger to update and continue to implement the SWPPP and BMPP to prevent contaminated wastes/materials from being discharged to waters of the State. Further discussion of the SWPPP and BMPP are provided in Attachment G.

C. Water Quality-Based Effluent Limitations (WQBELs)

1. Scope and Authority

CWA Section 301(b) and 40 C.F.R. section 122.44(d) require that permits include limitations more stringent than applicable federal technology-based requirements where necessary to achieve applicable water quality standards.

Section 122.44(d)(1)(i) of 40 C.F.R. requires that permits include effluent limitations for all pollutants that are or may be discharged at levels that have the reasonable potential to cause or contribute to an exceedance of a water quality standard, including numeric and narrative objectives within a standard. Where reasonable potential has been established for a pollutant, but there is no numeric criterion or objective for the pollutant, water quality-based effluent limitations (WQBELs) must be established using: (1) USEPA criteria guidance under CWA section 304(a), supplemented where necessary by other relevant information; (2) an indicator parameter for the pollutant of concern; or (3) a calculated numeric water quality criterion, such as a proposed state criterion or policy interpreting the state’s narrative criterion, supplemented with other relevant information, as provided in section 122.44(d)(1)(vi).

The process for determining reasonable potential and calculating WQBELs when necessary is intended to protect the designated uses of the receiving water as specified in the Basin Plan, and achieve applicable water quality objectives and criteria that are

contained in other state plans and policies, or any applicable water quality criteria contained in the Ocean Plan.

2. Applicable Beneficial Uses and Water Quality Criteria and Objectives

As noted in Section III.C of this Fact Sheet, the State Water Board adopted an Ocean Plan that designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed through the Ocean Plan. The beneficial uses applicable to the Pacific Ocean are summarized in Section III.C.1 of this Fact Sheet. The Ocean Plan includes both narrative and numeric water quality objectives applicable to the receiving water.

Table 1 of the Ocean Plan (2012) includes the following water quality objectives for toxic pollutants and whole effluent toxicity:

- 1) 6-month median, daily maximum, and instantaneous maximum objectives for 21 chemicals and chemical characteristics, including total residual chlorine and chronic toxicity, for the protection of marine aquatic life.
- 2) 30-day average objectives for 20 non-carcinogenic chemicals for the protection of human health.
- 3) 30-day average objectives for 42 carcinogenic chemicals for the protection of human health.
- 4) Daily maximum objectives for acute and chronic toxicity.

3. Determining the Need for WQBELS

The need for effluent limitations based on water quality objectives in Table 1 of the Ocean plan was evaluated in accordance with 40 CFR section 122.44(d) and guidance for statistically determining the "reasonable potential" for a discharged pollutant to exceed an objective, as outlined in the California Ocean Plan Reasonable Potential Analysis (RPA) Amendment that was adopted by the State Water Board on April 21, 2005. The statistical approach combines knowledge of effluent variability (as estimated by a coefficient-of variation) with the uncertainty due to a limited amount of effluent data to estimate a maximum effluent value at a high level of confidence. This estimated maximum effluent value is based on a lognormal distribution of daily effluent values. Projected receiving water values (based on the estimated maximum effluent value or the reported maximum effluent value and minimum probable initial dilution); can then be compared to the appropriate objective to determine the potential for an exceedance of that objective and the need for an effluent limitation.

The water quality objectives contained in the Ocean Plan for Table 1 pollutants are summarized in Table F-8 below.

Table F-8. Ocean Plan Water Quality Objectives

| Parameter | 6-Month Median (µg/L) | Daily Maximum (µg/L) | Instantaneous Maximum (µg/L) | 30-Day Average (µg/L) |
|-------------|-----------------------|----------------------|------------------------------|-----------------------|
| Arsenic | 8 | 32 | 80 | -- |
| Cadmium | 1 | 4 | 10 | -- |
| Chromium VI | 2 | 8 | 20 | -- |
| Copper | 3 | 12 | 30 | -- |
| Lead | 2 | 8 | 20 | -- |

| Parameter | 6-Month Median (µg/L) | Daily Maximum (µg/L) | Instantaneous Maximum (µg/L) | 30-Day Average (µg/L) |
|-----------------------------|-----------------------|----------------------|------------------------------|-----------------------|
| Mercury | 0.04 | 0.16 | 0.4 | -- |
| Nickel | 5 | 20 | 50 | -- |
| Selenium | 15 | 60 | 150 | -- |
| Silver | 0.7 | 2.8 | 7 | -- |
| Zinc | 20 | 80 | 200 | -- |
| Cyanide | 1 | 4 | 10 | -- |
| Total Residual Chlorine | 2 | 8 | 60 | -- |
| Ammonia (as N) | 600 | 2400 | 6000 | -- |
| Acute Toxicity | -- | 0.3 | -- | -- |
| Chronic Toxicity | -- | 1 | -- | -- |
| Phenolic Compounds | 30 | 120 | 300 | -- |
| Chlorinated Phenolics | 1 | 4 | 10 | -- |
| Endosulfan | 0.009 | 0.018 | 0.027 | -- |
| Endrin | 0.002 | 0.004 | 0.006 | -- |
| HCH | 0.004 | 0.008 | 0.012 | -- |
| Acrolein | -- | -- | -- | 220 |
| Antimony | -- | -- | -- | 1,200 |
| Bis(2-chloroethoxy)Methane | -- | -- | -- | 4.4 |
| Bis(2-chloroisopropyl)Ether | -- | -- | -- | 1,200 |
| Chlorobenzene | -- | -- | -- | 570 |
| Chromium (III) | -- | -- | -- | 190,000 |
| Di-n-butyl-phthalate | -- | -- | -- | 3,500 |
| Dichlorobenzenes | -- | -- | -- | 5,100 |
| Diethyl Phthalate | -- | -- | -- | 33,000 |
| Dimethyl Phthalate | -- | -- | -- | 820,000 |
| 4,6-Dinitro-2-Methylphenol | -- | -- | -- | 220 |
| 2,4-Dinitrophenol | -- | -- | -- | 4.0 |
| Ethylbenzene | -- | -- | -- | 4,100 |
| Fluoranthene | -- | -- | -- | 15 |
| Hexachlorocyclopentadiene | -- | -- | -- | 58 |
| Nitrobenzene | -- | -- | -- | 4.9 |
| Thallium | -- | -- | -- | 2 |
| Toluene | -- | -- | -- | 85,000 |
| Tributyltin | -- | -- | -- | 0.0014 |
| 1,1,1-Trichloroethane | -- | -- | -- | 540,000 |
| Acrylonitrile | -- | -- | -- | 0.10 |
| Aldrin | -- | -- | -- | 0.000022 |
| Benzene | -- | -- | -- | 5.9 |
| Benzidine | -- | -- | -- | 0.000069 |
| Beryllium | -- | -- | -- | 0.033 |
| Bis(2-chloroethyl)Ether | -- | -- | -- | 0.045 |
| Bis(2-ethylhexyl)Phthalate | -- | -- | -- | 3.5 |
| Carbon Tetrachloride | -- | -- | -- | 0.90 |

| Parameter | 6-Month Median (µg/L) | Daily Maximum (µg/L) | Instantaneous Maximum (µg/L) | 30-Day Average (µg/L) |
|---------------------------|--|----------------------|------------------------------|-----------------------|
| Chlordane | -- | -- | -- | 0.000023 |
| Chlorodibromomethane | -- | -- | -- | 8.6 |
| Chloroform | -- | -- | -- | 130 |
| DDT | -- | -- | -- | 0.00017 |
| 1,4-Dichlorobenzene | -- | -- | -- | 18 |
| 3,3'-Dichlorobenzidine | -- | -- | -- | 0.0081 |
| 1,2-Dichloroethane | -- | -- | -- | 28 |
| 1,1-Dichloroethylene | -- | -- | -- | 0.9 |
| Dichlorobromomethane | -- | -- | -- | 6.2 |
| Dichloromethane | -- | -- | -- | 450 |
| 1,3-Dichloropropene | -- | -- | -- | 8.9 |
| Dieldrin | -- | -- | -- | 0.00004 |
| 2,4-Dinitrotoluene | -- | -- | -- | 2.6 |
| 1,2-Diphenylhydrazine | -- | -- | -- | 0.16 |
| Halomethanes | -- | -- | -- | 130 |
| Heptachlor | -- | -- | -- | 0.00005 |
| Heptachlor Epoxide | -- | -- | -- | 0.00002 |
| Hexachlorobenzene | -- | -- | -- | 0.00021 |
| Hexachlorobutadiene | -- | -- | -- | 14 |
| Hexachloroethane | -- | -- | -- | 2.5 |
| Isophorone | -- | -- | -- | 730 |
| N-Nitrosodmethylamine | -- | -- | -- | 7.3 |
| N-nitrosodi-N-propylamine | -- | -- | -- | 0.38 |
| N-Nitrosodiphenylamine | -- | -- | -- | 2.5 |
| PAHs | -- | -- | -- | 0.0088 |
| PCBs | -- | -- | -- | 0.000019 |
| TCDD equivalents | -- | -- | -- | 0.0000000039 |
| 1,1,2,2-Tetrachloroethane | -- | -- | -- | 2.3 |
| Tetrachloroethylene | -- | -- | -- | 2.0 |
| Toxaphene | -- | -- | -- | 0.00021 |
| Trichloroethylene | -- | -- | -- | 27 |
| 1,1,2-Trichloroethane | -- | -- | -- | 9.4 |
| 2,4,6-Trichlorophenol | -- | -- | -- | 0.29 |
| Vinyl Chloride | -- | -- | -- | 36 |
| Radioactivity | Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, Section 30253 of the California Code of Regulations. Reference to Section 30253 is prospective, including future changes to any incorporated provisions of federal law, as the changes take effect. | | | |

According to the 2012 Ocean Plan, the reasonable potential analysis (RPA) can yield three endpoints:

Endpoint 1: An effluent limitation is required and monitoring is required;

Endpoint 2: An effluent limitation is not required and the Los Angeles Regional Water Board may require monitoring; and

Endpoint 3: The RPA is inconclusive, monitoring is required, and an existing effluent limitation may be retained or a permit reopener clause may be included to allow inclusion of an effluent limitation if future monitoring warrants the inclusion.

This Order establishes new WQBELs for certain pollutants included in Table 1 of the Ocean Plan that were not established in the previous Order and it includes limits for all pollutants included in Order No. R4-2008-0014, because there are no actual data available to determine reasonable potential.

4. WQBEL Calculations

CMWD completed theoretical modeling for the Hueneme Outfall dilution ratio. The results of the modeling were originally included in the ROWD submitted and accepted on July 15, 2007. At the time of the submittal of the ROWD in 2007, the dilution ratio of the Hueneme Outfall was determined by modeling the discharge using the USEPA-approved Visual Plumes (VP) program. Modeling runs were performed using ambient receiving water (Pacific Ocean) data collected in 2002 from the nearby Reliant Energy Ocean Outfall for salinity and temperature at various depths. Scenarios were evaluated over the range of flows expected on the SMP, including 2, 6, 10, 14, and 19.1 MGD. The lowest dilution predicted by the VP model was 99.5:1, occurring at the highest flow rate of 19.1 MGD under 2002 summer conditions.

The modeling was updated in 2007 to use more recent (August 2006 and February 2007) receiving water data collected by the City of Oxnard. Summer and winter conditions were modeled with an assumed 19.4 MGD effluent flow in CORMIX, Visual Plumes (VP), and KOH & FAN using the updated receiving water data sets. The KOH & FAN models predicted 72:1, a lower, more conservative dilution upon reaching the surface. CORMIX predicted 94:1, and VP predicted 89:1. The approved dilution ratio in Calleguas' current permit (R4-2008-0014) is 72:1, the most conservative predicted by the updated models.

The State Water Board and the Los Angeles Regional Water Board reviewed the modeling and additional information provided by CMWD and granted a dilution ratio of 72:1 for discharges from the RSMP.

From the Table 1 water quality objectives of the Ocean Plan, effluent limitations are calculated according to Equation 1 of the Ocean Plan for all pollutants, except for acute toxicity (if applicable) and radioactivity:

$$C_e = C_o + D_m(C_o - C_s)$$

Where:

- C_e = the effluent limitation ($\mu\text{g/L}$)
- C_o = the water quality objective to be met at the completion of initial dilution ($\mu\text{g/L}$)
- C_s = background seawater concentration ($\mu\text{g/L}$)
- D_m = minimum probable initial dilution expressed as parts seawater per part wastewater

The D_m is based on observed waste flow characteristics, receiving water density structure, and the assumption that no currents of sufficient strength to influence the initial dilution process flow across the discharge structure.

The State Water Board had determined the minimum initial dilution factor, D_m , for the ocean outfall to be 72 to 1. Initial dilution is the process that results in the rapid and irreversible turbulent mixing of wastewater with ocean water around the point of discharge. As stated above, the water quality objective to be met at the completion of initial dilution is contained in Table 1 of the Ocean Plan. The values provided in Table 3 of the Ocean Plan are presented in Table F-9, below. C_s equals zero for all pollutants, except the following:

Table F-9. Background Seawater Concentrations (C_s)

| Parameter | Ocean Plan Table 3 Background Concentration ($\mu\text{g/L}$) |
|-----------|--|
| Arsenic | 3 |
| Copper | 2 |
| Mercury | 0.0005 |
| Silver | 0.16 |
| Zinc | 8 |

WQBELs based on the dilution provided at the outfall for all parameters in Table 1 of the Ocean Plan is developed using Equation 1 of the Ocean Plan and Ocean Plan background concentrations.

WQBELs Calculation Example

The following demonstrates how the WQBELs for arsenic, are established.

Arsenic

$$C_e = 8 \mu\text{g/L} + 72 (8 \mu\text{g/L} - 3) = 368 \mu\text{g/L} \text{ (6-Month Median)}$$

$$C_e = 32 \mu\text{g/L} + 72 (32 \mu\text{g/L} - 3) = 2,120 \mu\text{g/L} \text{ (Daily Maximum)}$$

$$C_e = 80 \mu\text{g/L} + 72 (80 \mu\text{g/L} - 3) = 5,624 \mu\text{g/L} \text{ (Instantaneous Maximum)}$$

5. Temperature

The temperature limitations prescribed in the previous Order were based on specific water quality objectives for new coastal water dischargers in the Thermal Plan. Those limitations were retained in this Order

6. Whole Effluent Toxicity (WET)

Whole effluent toxicity (WET) protects the receiving water quality from the aggregate toxic effect of a mixture of pollutants in the effluent. WET tests measure the degree of response of exposed aquatic test organisms to an effluent. The WET approach allows for protection of the narrative “no toxics in toxic amounts” criterion while implementing numeric criteria for toxicity. There are two types of WET tests: acute and chronic. An acute toxicity test is conducted over a short time period and measures mortality. A chronic toxicity test is conducted over a longer period of time and may measure mortality, reproduction, and growth.

The previous permit included both the acute toxicity and the chronic toxicity limits based on water quality objectives in the Ocean Plan. To implement the USEPA toxicity policy,

this Order includes the chronic toxicity limit using USEPA's 2010 Test of Significant Toxicity (TST) hypothesis testing approach. Since a chemical at a low concentration can have chronic effects but no acute effects until it reach a higher level, the acute toxicity limit is not included in the Order. The chronic toxicity effluent limitations in this Order are as stringent as necessary to protect the Ocean Plan Water Quality Objective for chronic toxicity.

7. Final WQBELs

This Order includes all effluent limitations established in Order R4-2008-0014 and establishes new effluent limitations for the remainder of pollutants for which water quality objectives exist in Table 1 of the Ocean Plan. The RSMP has not commenced discharge at the time of this permit reissuance and there are no actual discharge data available with which to evaluate reasonable potential; therefore, this Order includes effluent limitations for BOD₅ consistent with those included in Order No. R4-2008-0014 based on BPJ and EPA's Secondary Treatment Standards. This Order retains WQBELs for total residual chlorine, ammonia (as N), chronic toxicity, and other pollutants included in Order No. R4-2008-0014.

This Order establishes new WQBELs for the remaining pollutants for which water quality objectives exist, based on Table 1 of the Ocean Plan.

For radioactivity, no numeric water quality objectives are included in the Ocean Plan. Therefore, the effluent limitations for radioactivity in this Order are based on Maximum Contaminant Levels specified in Title 22, Chapter 15, Article 5, Section 64443, California Code of Regulations.

Effluent limitations for temperature and bacteria have been retained from the previous Order.

Table F-10. Summary of Water Quality-based Effluent Limitations

| Parameter | Units | Effluent Limitations | | | |
|-------------------------------|------------------------|----------------------|----------------------|-----------------------|------------------|
| | | Average Monthly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Total Residual Chlorine | µg/L | -- | 580 | 4,400 | 150 |
| | lbs/day ¹ | -- | 85 | 640 | 22 |
| Ammonia as N | µg/L | -- | 180,000 | 440,000 | 44,000 |
| | lbs/day ¹ | -- | 26,000 | 64,000 | 6,400 |
| Chronic Toxicity ² | Pass or Fail, % Effect | Pass ³ | Pass or % Effect <50 | -- | -- |
| Total coliform | MPN/100ml | 4 | | | |
| Fecal coliform | MPN/100ml | 4 | | | |
| Enterococcus | MPN/100ml | 4 | | | |
| Antimony | µg/L | 88,000 | -- | -- | -- |
| | lbs/day ¹ | 13,000 | -- | -- | -- |
| Arsenic, Total Recoverable | µg/L | -- | 2100 | 5,600 | 370 |
| | lbs/day ¹ | -- | 310 | 820 | 54 |
| Beryllium | µg/L | 2.4 | -- | -- | -- |
| | lbs/day ¹ | 0.35 | -- | -- | -- |
| Cadmium, Total Recoverable | µg/L | -- | 290 | 730 | 73 |
| | lbs/day ¹ | -- | 42 | 110 | 11 |

| Parameter | Units | Effluent Limitations | | | |
|---|----------------------|----------------------|---------------|-----------------------|------------------|
| | | Average Monthly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Chromium (III) , Total Recoverable | µg/L | 1.4E+07 | -- | -- | -- |
| | lbs/day ¹ | 2.0E+06 | -- | -- | -- |
| Chromium (VI) , Total Recoverable | µg/L | -- | 580 | 1,500 | 150 |
| | lbs/day ¹ | -- | 85 | 210 | 22 |
| Copper, Total Recoverable | µg/L | -- | 730 | 2,000 | 75 |
| | lbs/day ¹ | -- | 110 | 290 | 11 |
| Lead, Total Recoverable | µg/L | -- | 580 | 1500 | 150 |
| | lbs/day ¹ | -- | 85 | 220 | 22 |
| Mercury | µg/L | -- | 12 | 29 | 2.9 |
| | lbs/day ¹ | -- | 1.8 | 4.2 | 0.42 |
| Nickel, Total Recoverable | µg/L | -- | 1,500 | 3,700 | 370 |
| | lbs/day ¹ | -- | 220 | 530 | 53 |
| Selenium, Total Recoverable | µg/L | -- | 4,400 | 11,000 | 1,100 |
| | lbs/day ¹ | -- | 640 | 1600 | 160 |
| Silver, Total Recoverable | µg/L | -- | 190 | 500 | 40 |
| | lbs/day ¹ | -- | 28 | 73 | 5.8 |
| Thallium | µg/L | 150 | -- | -- | -- |
| | lbs/day ¹ | 22 | -- | -- | -- |
| Zinc, Total Recoverable | µg/L | -- | 5,300 | 14,000 | 880 |
| | lbs/day ¹ | -- | 770 | 2,000 | 130 |
| Cyanide | µg/L | -- | 290 | 730 | 73 |
| | lbs/day ¹ | -- | 42 | 110 | 11 |
| Phenolic Compounds (non-chlorinated) ⁵ | µg/L | -- | 8,800 | 22,00 | 2,200 |
| | lbs/day ¹ | -- | 1,300 | 3,200 | 320 |
| Chlorinated Phenolics ⁶ | µg/L | -- | 290 | 730 | 73 |
| | lbs/day ¹ | -- | 42 | 110 | 11 |
| TCDD Equivalentents ⁷ | µg/L | 2.8E-07 | -- | -- | -- |
| | lbs/day ¹ | 4.1E-08 | -- | -- | -- |
| Acrolein | µg/L | 16,000 | -- | -- | -- |
| | lbs/day ¹ | 2,300 | -- | -- | -- |
| Acrylonitrile | µg/L | 7.3 | -- | -- | -- |
| | lbs/day ¹ | 1.1 | -- | -- | -- |
| Benzene | µg/L | 430 | -- | -- | -- |
| | lbs/day ¹ | 63 | -- | -- | -- |
| Carbon Tetrachloride | µg/L | 66 | -- | -- | -- |
| | lbs/day ¹ | 9.6 | -- | -- | -- |
| Chlorobenzene | µg/L | 42,000 | -- | -- | -- |
| | lbs/day ¹ | 6,100 | -- | -- | -- |
| Chlorodibromomethane | µg/L | 630 | -- | -- | -- |
| | lbs/day ¹ | 92 | -- | -- | -- |
| Chloroform | µg/L | 9,500 | -- | -- | -- |
| | lbs/day ¹ | 1,400 | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | |
|---|----------------------|----------------------|---------------|-----------------------|------------------|
| | | Average Monthly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Dichlorobromomethane | µg/L | 450 | -- | -- | -- |
| | lbs/day ¹ | 66 | -- | -- | -- |
| 1,2-Dichloroethane | µg/L | 2,000 | -- | -- | -- |
| | lbs/day ¹ | 290 | -- | -- | -- |
| 1,1-Dichloroethylene | µg/L | 66 | -- | -- | -- |
| | lbs/day ¹ | 9.6 | -- | -- | -- |
| 1,3-Dichloropropylene | µg/L | 650 | -- | -- | -- |
| | lbs/day ¹ | 95 | -- | -- | -- |
| Ethylbenzene | µg/L | 3.0E+5 | -- | -- | -- |
| | lbs/day ¹ | 44,000 | -- | -- | -- |
| Halomethanes ⁸ | µg/L | 9,500 | -- | -- | -- |
| | lbs/day ¹ | 1,400 | -- | -- | -- |
| Dichloromethane | µg/L | 33,000 | -- | -- | -- |
| | lbs/day ¹ | 4,800 | -- | -- | -- |
| 1,1,2,2-Tetrachloroethane | µg/L | 170 | -- | -- | -- |
| | lbs/day ¹ | 25 | -- | -- | -- |
| Tetrachloroethylene | µg/L | 150 | -- | -- | -- |
| | lbs/day ¹ | 22 | -- | -- | -- |
| Toluene | µg/L | 6.2E+06 | -- | -- | -- |
| | lbs/day ¹ | 9.1E+05 | -- | -- | -- |
| 1,1,1-Trichloroethane | µg/L | 3.9E+07 | -- | -- | -- |
| | lbs/day ¹ | 5.7E+06 | -- | -- | -- |
| 1,1,2-Trichloroethane | µg/L | 690 | -- | -- | -- |
| | lbs/day ¹ | 100 | -- | -- | -- |
| Trichloroethylene | µg/L | 2,000 | -- | -- | -- |
| | lbs/day ¹ | 290 | -- | -- | -- |
| Vinyl Chloride | µg/L | 2,600 | -- | -- | -- |
| | lbs/day ¹ | 380 | -- | -- | -- |
| 4,6-Dinitro-2-Methylphenol | µg/L | 16,000 | -- | -- | -- |
| | lbs/day ¹ | 2,300 | -- | -- | -- |
| 2,4-Dinitrophenol | µg/L | 290 | -- | -- | -- |
| | lbs/day ¹ | 42 | -- | -- | -- |
| 2,4,6-Trichlorophenol | µg/L | 21 | -- | -- | -- |
| | lbs/day ¹ | 3.1 | -- | -- | -- |
| Benzidine | µg/L | 0.0050 | -- | -- | -- |
| | lbs/day ¹ | 0.00073 | -- | -- | -- |
| Polynuclear Aromatic Hydrocarbons (PAHs) ⁹ | µg/L | 0.64 | -- | -- | -- |
| | lbs/day ¹ | 0.094 | -- | -- | -- |
| Bis(2-chloroethoxy)Methane | µg/L | 320 | -- | -- | -- |
| | lbs/day ¹ | 47 | -- | -- | -- |
| Bis(2-chlorotethyl)Ether | µg/L | 3.3 | -- | -- | -- |
| | lbs/day ¹ | 0.48 | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | |
|-----------------------------|----------------------|----------------------|---------------|-----------------------|------------------|
| | | Average Monthly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| Bis(2-chloroisopropyl)Ether | µg/L | 88,000 | -- | -- | -- |
| | lbs/day ¹ | 13,000 | -- | -- | -- |
| Bis(2-ethylhexyl)Phthalate | µg/L | 260 | -- | -- | -- |
| | lbs/day ¹ | 38 | -- | -- | -- |
| Dichlorobenzenes | µg/L | 3.7E+05 | -- | -- | -- |
| | lbs/day ¹ | 54,000 | -- | -- | -- |
| 1,4-Dichlorobenzene | µg/L | 1300 | -- | -- | -- |
| | lbs/day ¹ | 190 | -- | -- | -- |
| 3,3'-Dichlorobenzidine | µg/L | 0.59 | -- | -- | -- |
| | lbs/day ¹ | 0.086 | -- | -- | -- |
| Diethyl Phthalate | µg/L | 2.4E+06 | -- | -- | -- |
| | lbs/day ¹ | 3.5E+05 | -- | -- | -- |
| Dimethyl Phthalate | µg/L | 6.0E+07 | -- | -- | -- |
| | lbs/day ¹ | 8.8E+06 | -- | -- | -- |
| Di-n-Butyl Phthalate | µg/L | 2.6E+05 | -- | -- | -- |
| | lbs/day ¹ | 38,000 | -- | -- | -- |
| 2,4-Dinitrotoluene | µg/L | 190 | -- | -- | -- |
| | lbs/day ¹ | 28 | -- | -- | -- |
| 1,2-Diphenylhydrazine | µg/L | 12 | -- | -- | -- |
| | lbs/day ¹ | 1.8 | -- | -- | -- |
| Fluoranthene | µg/L | 1,100 | -- | -- | -- |
| | lbs/day ¹ | 160 | -- | -- | -- |
| Hexachlorobenzene | µg/L | 0.015 | -- | -- | -- |
| | lbs/day ¹ | 0.0022 | -- | -- | -- |
| Hexachlorobutadiene | µg/L | 1,000 | -- | -- | -- |
| | lbs/day ¹ | 150 | -- | -- | -- |
| Hexachlorocyclopentadiene | µg/L | 4,200 | -- | -- | -- |
| | lbs/day ¹ | 610 | -- | -- | -- |
| Hexachloroethane | µg/L | 180 | -- | -- | -- |
| | lbs/day ¹ | 26 | -- | -- | -- |
| Isophorone | µg/L | 53,000 | -- | -- | -- |
| | lbs/day ¹ | 7,700 | -- | -- | -- |
| Nitrobenzene | µg/L | 360 | -- | -- | -- |
| | lbs/day ¹ | 53 | -- | -- | -- |
| N-Nitrosodimethylamine | µg/L | 530 | -- | -- | -- |
| | lbs/day ¹ | 77 | -- | -- | -- |
| N-Nitrosodi-N-propylamine | µg/L | 28 | -- | -- | -- |
| | lbs/day ¹ | 4.1 | -- | -- | -- |
| N-Nitrosodiphenylamine | µg/L | 180 | -- | -- | -- |
| | lbs/day ¹ | 26 | -- | -- | -- |
| Aldrin | µg/L | 0.0016 | -- | -- | -- |
| | lbs/day ¹ | 0.00023 | -- | -- | -- |

| Parameter | Units | Effluent Limitations | | | |
|--|--|----------------------|---------------|-----------------------|------------------|
| | | Average Monthly | Maximum Daily | Instantaneous Maximum | Six-Month Median |
| HCH ¹⁰ | µg/L | -- | 0.58 | 0.88 | 0.29 |
| | lbs/day ¹ | -- | 0.085 | 0.13 | 0.042 |
| Chlordane | µg/L | 0.0017 | -- | -- | -- |
| | lbs/day ¹ | 0.00025 | -- | -- | -- |
| DDT ¹¹ | µg/L | 0.012 | -- | -- | -- |
| | lbs/day ¹ | 0.0018 | -- | -- | -- |
| Dieldrin | µg/L | 0.0029 | -- | -- | -- |
| | lbs/day ¹ | 0.00042 | -- | -- | -- |
| Endosulfan | µg/L | -- | 1.3 | 2.0 | 0.66 |
| | lbs/day ¹ | -- | 0.19 | 0.29 | 0.096 |
| Endrin | µg/L | -- | 0.29 | 0.44 | 0.15 |
| | lbs/day ¹ | -- | 0.042 | 0.064 | 0.022 |
| Heptachlor | µg/L | 0.0037 | -- | -- | -- |
| | lbs/day ¹ | 0.00054 | -- | -- | -- |
| Heptachlor Epoxide | µg/L | 0.0015 | -- | -- | -- |
| | lbs/day ¹ | 0.00022 | -- | -- | -- |
| Polychlorinated Biphenyls (PCBs) ¹² | µg/L | 0.0014 | -- | -- | -- |
| | lbs/day ¹ | 0.00020 | -- | -- | -- |
| Toxaphene | µg/L | 0.015 | -- | -- | -- |
| | lbs/day ¹ | 0.0022 | -- | -- | -- |
| Tributyltin | µg/L | 0.10 | -- | -- | -- |
| | lbs/day ¹ | 0.015 | -- | -- | -- |
| Radioactivity | Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, Section 30253 of the California Code of Regulations. Reference to Section 30253 is prospective, including future changes to any incorporated provisions of federal law, as the changes take effect. | | | | |

1. The mass-based effluent limitations are based on the facility design flow rate of 17.52 MGD.
2. "Pass" or "Fail" for Median Monthly Effluent Limitation (MMEL). "Pass" or "Fail" and "% Effect" for Maximum Daily Effluent Limitation (MDEL). The MMEL for chronic toxicity shall only apply when there is a discharge more than one day in a calendar month period. During such calendar months, exactly three independent toxicity tests are required when one toxicity test results in "Fail".
3. This is a Median Monthly Effluent Limitation.
4. Bacteria limitations:
 - a. 30-day Geometric Mean – The geometric mean shall be calculated using the results of five most recent samples.
 - i. Total coliform density shall not exceed 1,000/100 ml;
 - ii. Fecal coliform density shall not exceed 200/100 ml; and
 - iii. Enterococcus density shall not exceed 35/100 ml.
 - b. Single Sample Maximum (SSM)
 - i. Total coliform density shall not exceed 10,000/100 ml;
 - ii. Fecal coliform density shall not exceed 400/100 ml;
 - iii. Enterococcus density shall not exceed 104/100 ml; and
 - iv. Total coliform density shall not exceed 1,000/100 ml, when the fecal coliform/total coliform ratio exceeds 0.1.

If a single sample exceeds any of the single sample maximum (SSM) standards, repeat sampling shall be conducted to determine the extent and persistence of the exceedance. Repeat sampling shall be conducted within 24 hours of receiving analytical results and continued until the sample result is less than the SSM standard.

When repeat sampling is required because of an exceedance of any one single sample density, values from all samples collected during that 30-day period will be used to calculate the geometric mean.

5. Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
6. Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
7. TCDD Equivalents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown in the table below. USEPA method 1613 may be used to analyze dioxin and furan congeners.

$$\text{Dioxin-TEQ (TCDD Equivalents)} = \sum (C_x \times \text{TEF}_x)$$

Where:

C_x = concentration of dioxin or furan congener x

TEF_x = TEF for congener x

Toxicity Equivalency Factors

| Isomer Group | Toxicity Equivalency Factor (TEF) |
|---------------------|-----------------------------------|
| 2,3,7,8-tetra CDD | 1.0 |
| 2,3,7,8-penta CDD | 0.5 |
| 2,3,7,8-hexa CDDs | 0.1 |
| 2,3,7,8-hepta CDD | 0.01 |
| Octa CDD | 0.001 |
| 2,3,7,8 tetra CDF | 0.1 |
| 1,2,3,7,8 penta CDF | 0.05 |
| 2,3,4,7,8 penta CDF | 0.5 |
| 2,3,7,8 hexa CDFs | 0.1 |
| 2,3,7,8 hepta CDFs | 0.01 |
| Octa CDF | 0.001 |

8. Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
9. PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorine; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.
10. HCH shall mean the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
11. DDT shall mean the sum of 4,4'-DDT, 2,4'-DDT, 4,4'-DDE, 2,4'-DDE, 4,4'-DDD, and 2,4'-DDD.
12. PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, and Aroclor-1260.

D. Final Effluent Limitation Considerations

Section 402(o) of the CWA and section 122.44(l) require that effluent limitations or conditions in reissued Orders be at least as stringent as those in the existing Orders based on the submitted sampling data. Technology-based effluent limitations for settleable solids, TSS, oil and grease, turbidity, and pH have been included and are based on the effluent limitations established in Table 2 of the Ocean Plan. Technology-based effluent limitations for BOD₅ are established using BPJ and applying Secondary Treatment Standards to the discharge, as it is comprised of highly-treated municipal wastewater. This Order retains WQBELs based on Ocean Plan water quality objectives for all Ocean Plan Table 1 pollutants.

Order R4-2008-0014 did not establish effluent limits for certain pollutants for which the Ocean Plan establishes water quality objectives. However, based on the lack of actual discharge data with which to evaluate reasonable potential, this Order establishes WQBELs for all

pollutants regulated in the Ocean Plan. Therefore, this Order establishes new WQBELs for acrolein, antimony, bis(2-chloroisopropyl)ether, chlorobenzene, chromium (III), di-n-butyl-phthalate, dichlorobenzenes, diethyl phthalate, dimethyl phthalate, 4,6-dinitro-2-methylphenol, ethylbenzene, fluoranthene, hexachlorocyclopentadiene, toluene, 1,1,1-trichloroethane, chloroform, 1,4-dichlorobenzene, 1,2-dichloroethane, dichloromethane (methylene chloride), halomethanes, hexachlorobutadiene, isophorone, and vinyl chloride based on the water quality objectives contained in Table 1 of the Ocean Plan.

1. Anti-Backsliding Requirements

Sections 402(o) and 303(d)(4) of the CWA and federal regulations at 40 C.F.R. section 122.44(l) prohibit backsliding in NPDES permits. These anti-backsliding provisions require effluent limitations in a reissued permit to be as stringent as those in the previous permit, with some exceptions where limitations may be relaxed. All concentration-based effluent limitations in this Order are at least as stringent as the effluent limitations in the previous Order.

The mass effluent limitations in this Order were calculated based on the permitted flow of 17.52 MGD as specified in the previous Order. During this permit term, it is projected that the total discharging flows through the RSMP will be 14.12 MGD that is less than the permitted flow of 17.52 MGD. The permit allows for a phased increase in the discharge flow as various sources discharging to the RSMP connect to the pipeline and begin discharging.

2. Antidegradation Policies

Section 131.12 requires that the state water quality standards include an anti-degradation policy consistent with the federal policy. The State Water Board established California's antidegradation policy in State Water Board Resolution 68-16. Resolution 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution 68-16 requires that existing water quality be maintained unless degradation is justified based on specific findings. The Los Angeles Regional Water Board's Basin Plan implements, and incorporates by reference, both the State and federal antidegradation policies.

The permitted discharge is consistent with the antidegradation provision of section 131.12 and State Water Board Resolution 68-16. This Order does not provide for an increase in the permitted flow or allow for a reduction in the level of treatment. The final limitations in this Order hold the Discharger to performance levels that will not cause or contribute to water quality impairment or degradation of water quality.

3. Stringency of Requirements for Individual Pollutants

This Order contains both technology-based and water quality-based effluent limitations for individual pollutants. The technology-based effluent limitations consist of restrictions on BOD, oil and grease, TSS, settleable solids, turbidity, and pH. Restrictions on these pollutants are discussed in section IV.B. This Order's technology-based pollutant restrictions implement the minimum, applicable federal technology-based requirements.

Water quality-based effluent limitations have been derived to implement water quality objectives that protect beneficial uses. Both the beneficial uses and the water quality objectives have been approved pursuant to federal law and are the applicable federal water quality standards. The procedures for calculating the individual water quality-based effluent limitations are based on the Ocean Plan, most recently amended, effective August 19, 2013. All beneficial uses and water quality objectives contained in the Ocean Plan were approved under state law and submitted to and approved by USEPA and are

applicable water quality standards pursuant to 40 C.F.R. section 131.21(c)(2). Collectively, this Order's restrictions on individual pollutants are no more stringent than required to implement the requirements of the CWA.

Table F-11. Summary of Final Effluent Limitations

| Parameter | Units | Effluent Limitations | | | | | Basis ¹ |
|---|------------------------|----------------------|----------------|----------------------|-----------------------|------------------|--------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median | |
| Biochemical Oxygen Demand (BOD), 5-day @ 20°C | mg/L | 30 | 45 | -- | -- | -- | BPJ |
| | lbs/day ² | 4,400 | 6,600 | | -- | -- | |
| Oil and Grease | mg/L | 25 | 40 | -- | 75 | -- | OP |
| | lbs/day ² | 3,700 | 5,800 | -- | 11,000 | -- | |
| pH | s.u. | 6.0 - 9.0 | | | | | OP |
| Settleable Solids | ml/L | 1.0 | 1.5 | -- | 3.0 | -- | OP |
| Total Suspended Solids (TSS) | mg/L | 60 | -- | -- | -- | -- | OP |
| | lbs/day ² | 8,800 | -- | -- | -- | -- | |
| Turbidity | NTU | 75 | 100 | -- | 225 | -- | OP |
| Total Residual Chlorine | µg/L | -- | -- | 580 | 4,400 | 150 | OP |
| | lbs/day ² | -- | -- | 85 | 640 | 22 | |
| Ammonia as N | µg/L | -- | -- | 180,000 | 440,000 | 44,000 | OP |
| | lbs/day ² | -- | -- | 26,000 | 64,000 | 6,400 | |
| Chronic Toxicity ³ | Pass or Fail, % Effect | Pass ⁴ | | Pass or % Effect <50 | -- | -- | OP |
| Total coliform | MPN/100ml | ⁵ | | | | | OP |
| Fecal coliform | MPN/100ml | ⁵ | | | | | OP |
| Enterococcus | MPN/100ml | ⁵ | | | | | OP |
| Antimony | µg/L | 88,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 13,000 | -- | -- | -- | -- | |
| Arsenic, Total Recoverable | µg/L | -- | -- | 2100 | 5,600 | 370 | OP |
| | lbs/day ² | -- | -- | 310 | 820 | 54 | |
| Beryllium | µg/L | 2.4 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.35 | -- | -- | -- | -- | |
| Cadmium, Total Recoverable | µg/L | -- | -- | 290 | 730 | 73 | OP |
| | lbs/day ² | -- | -- | 42 | 110 | 11 | |
| Chromium (III) , Total Recoverable | µg/L | 1.4E+07 | -- | -- | -- | -- | OP |
| | lbs/day ² | 2.0E+06 | -- | -- | -- | -- | |
| Chromium (VI) , Total Recoverable | µg/L | -- | -- | 580 | 1,500 | 150 | OP |
| | lbs/day ² | -- | -- | 85 | 210 | 22 | |
| Copper, Total Recoverable | µg/L | -- | -- | 730 | 2,000 | 75 | OP |
| | lbs/day ² | -- | -- | 110 | 290 | 11 | |
| Lead, Total Recoverable | µg/L | -- | -- | 580 | 1500 | 150 | OP |
| | lbs/day ² | -- | -- | 85 | 220 | 22 | |

| Parameter | Units | Effluent Limitations | | | | | Basis ¹ |
|---|----------------------|----------------------|----------------|---------------|-----------------------|------------------|--------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median | |
| Mercury | µg/L | -- | -- | 12 | 29 | 2.9 | OP |
| | lbs/day ² | -- | -- | 1.8 | 4.2 | 0.42 | |
| Nickel, Total Recoverable | µg/L | -- | -- | 1,500 | 3,700 | 370 | OP |
| | lbs/day ² | -- | -- | 220 | 530 | 53 | |
| Selenium, Total Recoverable | µg/L | -- | -- | 4,400 | 11,000 | 1,100 | OP |
| | lbs/day ² | -- | -- | 640 | 1600 | 160 | |
| Silver, Total Recoverable | µg/L | -- | -- | 190 | 500 | 40 | OP |
| | lbs/day ² | -- | -- | 28 | 73 | 5.8 | |
| Thallium | µg/L | 150 | -- | -- | -- | -- | OP |
| | lbs/day ² | 22 | -- | -- | -- | -- | |
| Zinc, Total Recoverable | µg/L | -- | -- | 5,300 | 14,000 | 880 | OP |
| | lbs/day ² | -- | -- | 770 | 2,000 | 130 | |
| Cyanide | µg/L | -- | -- | 290 | 730 | 73 | OP |
| | lbs/day ² | -- | -- | 42 | 110 | 11 | |
| Phenolic Compounds (non-chlorinated) ⁶ | µg/L | -- | -- | 8,800 | 22,000 | 2,200 | OP |
| | lbs/day ² | -- | -- | 1,300 | 3,200 | 320 | |
| Chlorinated Phenolics ⁷ | µg/L | -- | -- | 290 | 730 | 73 | OP |
| | lbs/day ² | -- | -- | 42 | 110 | 11 | |
| TCDD Equivalents ⁸ | µg/L | 2.8E-07 | -- | -- | -- | -- | OP |
| | lbs/day ² | 4.1E-08 | -- | -- | -- | -- | |
| Acrolein | µg/L | 16,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 2,300 | -- | -- | -- | -- | |
| Acrylonitrile | µg/L | 7.3 | -- | -- | -- | -- | OP |
| | lbs/day ² | 1.1 | -- | -- | -- | -- | |
| Benzene | µg/L | 430 | -- | -- | -- | -- | OP |
| | lbs/day ² | 63 | -- | -- | -- | -- | |
| Carbon Tetrachloride | µg/L | 66 | -- | -- | -- | -- | OP |
| | lbs/day ² | 9.6 | -- | -- | -- | -- | |
| Chlorobenzene | µg/L | 42,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 6,100 | -- | -- | -- | -- | |
| Chlorodibromomethane | µg/L | 630 | -- | -- | -- | -- | OP |
| | lbs/day ² | 92 | -- | -- | -- | -- | |
| Chloroform | µg/L | 9,500 | -- | -- | -- | -- | OP |
| | lbs/day ² | 1,400 | -- | -- | -- | -- | |
| Dichlorobromomethane | µg/L | 450 | -- | -- | -- | -- | OP |
| | lbs/day ² | 66 | -- | -- | -- | -- | |
| 1,2-Dichloroethane | µg/L | 2,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 290 | -- | -- | -- | -- | |

| Parameter | Units | Effluent Limitations | | | | | Basis ¹ |
|--|----------------------|----------------------|----------------|---------------|-----------------------|------------------|--------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median | |
| 1,1-Dichloroethylene | µg/L | 66 | -- | -- | -- | -- | OP |
| | lbs/day ² | 9.6 | -- | -- | -- | -- | |
| 1,3-Dichloropropylene | µg/L | 650 | -- | -- | -- | -- | OP |
| | lbs/day ² | 95 | -- | -- | -- | -- | |
| Ethylbenzene | µg/L | 3.0E+5 | -- | -- | -- | -- | OP |
| | lbs/day ² | 44,000 | -- | -- | -- | -- | |
| Halomethanes ⁹ | µg/L | 9,500 | -- | -- | -- | -- | OP |
| | lbs/day ² | 1,400 | -- | -- | -- | -- | |
| Dichloromethane | µg/L | 33,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 4,800 | -- | -- | -- | -- | |
| 1,1,2,2-Tetrachloroethane | µg/L | 170 | -- | -- | -- | -- | OP |
| | lbs/day ² | 25 | -- | -- | -- | -- | |
| Tetrachloroethylene | µg/L | 150 | -- | -- | -- | -- | OP |
| | lbs/day ² | 22 | -- | -- | -- | -- | |
| Toluene | µg/L | 6.2E+06 | -- | -- | -- | -- | OP |
| | lbs/day ² | 9.1E+05 | -- | -- | -- | -- | |
| 1,1,1-Trichloroethane | µg/L | 3.9E+07 | -- | -- | -- | -- | OP |
| | lbs/day ² | 5.7E+06 | -- | -- | -- | -- | |
| 1,1,2-Trichloroethane | µg/L | 690 | -- | -- | -- | -- | OP |
| | lbs/day ² | 100 | -- | -- | -- | -- | |
| Trichloroethylene | µg/L | 2,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 290 | -- | -- | -- | -- | |
| Vinyl Chloride | µg/L | 2,600 | -- | -- | -- | -- | OP |
| | lbs/day ² | 380 | -- | -- | -- | -- | |
| 4,6-Dinitro-2-Methylphenol | µg/L | 16,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 2,300 | -- | -- | -- | -- | |
| 2,4-Dinitrophenol | µg/L | 290 | -- | -- | -- | -- | OP |
| | lbs/day ² | 42 | -- | -- | -- | -- | |
| 2,4,6-Trichlorophenol | µg/L | 21 | -- | -- | -- | -- | OP |
| | lbs/day ² | 3.1 | -- | -- | -- | -- | |
| Benzidine | µg/L | 0.0050 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00073 | -- | -- | -- | -- | |
| Polynuclear Aromatic Hydrocarbons (PAHs) ¹⁰ | µg/L | 0.64 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.094 | -- | -- | -- | -- | |
| Bis(2-chloroethoxy)Methane | µg/L | 320 | -- | -- | -- | -- | OP |
| | lbs/day ² | 47 | -- | -- | -- | -- | |
| Bis(2-chlorotethyl)Ether | µg/L | 3.3 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.48 | -- | -- | -- | -- | |

| Parameter | Units | Effluent Limitations | | | | | Basis ¹ |
|-----------------------------|----------------------|----------------------|----------------|---------------|-----------------------|------------------|--------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median | |
| Bis(2-chloroisopropyl)Ether | µg/L | 88,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 13,000 | -- | -- | -- | -- | |
| Bis(2-ethylhexyl)Phthalate | µg/L | 260 | -- | -- | -- | -- | OP |
| | lbs/day ² | 38 | -- | -- | -- | -- | |
| Dichlorobenzenes | µg/L | 3.7E+05 | -- | -- | -- | -- | OP |
| | lbs/day ² | 54,000 | -- | -- | -- | -- | |
| 1,4-Dichlorobenzene | µg/L | 1300 | -- | -- | -- | -- | OP |
| | lbs/day ² | 190 | -- | -- | -- | -- | |
| 3,3'-Dichlorobenzidine | µg/L | 0.59 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.086 | -- | -- | -- | -- | |
| Diethyl Phthalate | µg/L | 2.4E+06 | -- | -- | -- | -- | OP |
| | lbs/day ² | 3.5E+05 | -- | -- | -- | -- | |
| Dimethyl Phthalate | µg/L | 6.0E+07 | -- | -- | -- | -- | OP |
| | lbs/day ² | 8.8E+06 | -- | -- | -- | -- | |
| Di-n-Butyl Phthalate | µg/L | 2.6E+05 | -- | -- | -- | -- | OP |
| | lbs/day ² | 38,000 | -- | -- | -- | -- | |
| 2,4-Dinitrotoluene | µg/L | 190 | -- | -- | -- | -- | OP |
| | lbs/day ² | 28 | -- | -- | -- | -- | |
| 1,2-Diphenylhydrazine | µg/L | 12 | -- | -- | -- | -- | OP |
| | lbs/day ² | 1.8 | -- | -- | -- | -- | |
| Fluoranthene | µg/L | 1,100 | -- | -- | -- | -- | OP |
| | lbs/day ² | 160 | -- | -- | -- | -- | |
| Hexachlorobenzene | µg/L | 0.015 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.0022 | -- | -- | -- | -- | |
| Hexachlorobutadiene | µg/L | 1,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 150 | -- | -- | -- | -- | |
| Hexachlorocyclopentadiene | µg/L | 4,200 | -- | -- | -- | -- | OP |
| | lbs/day ² | 610 | -- | -- | -- | -- | |
| Hexachloroethane | µg/L | 180 | -- | -- | -- | -- | OP |
| | lbs/day ² | 26 | -- | -- | -- | -- | |
| Isophorone | µg/L | 53,000 | -- | -- | -- | -- | OP |
| | lbs/day ² | 7,700 | -- | -- | -- | -- | |
| Nitrobenzene | µg/L | 360 | -- | -- | -- | -- | OP |
| | lbs/day ² | 53 | -- | -- | -- | -- | |
| N-Nitrosodimethylamine | µg/L | 530 | -- | -- | -- | -- | OP |
| | lbs/day ² | 77 | -- | -- | -- | -- | |
| N-Nitrosodi-N-propylamine | µg/L | 28 | -- | -- | -- | -- | OP |
| | lbs/day ² | 4.1 | -- | -- | -- | -- | |

| Parameter | Units | Effluent Limitations | | | | | Basis ¹ |
|--|--|----------------------|----------------|---------------|-----------------------|------------------|--------------------|
| | | Average Monthly | Average Weekly | Maximum Daily | Instantaneous Maximum | Six-Month Median | |
| N-Nitrosodiphenylamine | µg/L | 180 | -- | -- | -- | -- | OP |
| | lbs/day ² | 26 | -- | -- | -- | -- | |
| Aldrin | µg/L | 0.0016 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00023 | -- | -- | -- | -- | |
| HCH ¹¹ | µg/L | -- | -- | 0.58 | 0.88 | 0.29 | OP |
| | lbs/day ² | -- | -- | 0.085 | 0.13 | 0.042 | |
| Chlordane | µg/L | 0.0017 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00025 | -- | -- | -- | -- | |
| DDT ¹² | µg/L | 0.012 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.0018 | -- | -- | -- | -- | |
| Dieldrin | µg/L | 0.0029 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00042 | -- | -- | -- | -- | |
| Endosulfan | µg/L | -- | -- | 1.3 | 2.0 | 0.66 | OP |
| | lbs/day ² | -- | -- | 0.19 | 0.29 | 0.096 | |
| Endrin | µg/L | -- | -- | 0.29 | 0.44 | 0.15 | OP |
| | lbs/day ² | -- | -- | 0.042 | 0.064 | 0.022 | |
| Heptachlor | µg/L | 0.0037 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00054 | -- | -- | -- | -- | |
| Heptachlor Epoxide | µg/L | 0.0015 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00022 | -- | -- | -- | -- | |
| Polychlorinated Biphenyls (PCBs) ¹³ | µg/L | 0.0014 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.00020 | -- | -- | -- | -- | |
| Toxaphene | µg/L | 0.015 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.0022 | -- | -- | -- | -- | |
| Tributyltin | µg/L | 0.10 | -- | -- | -- | -- | OP |
| | lbs/day ² | 0.015 | -- | -- | -- | -- | |
| Radioactivity | Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, Section 30253 of the California Code of Regulations. Reference to Section 30253 is prospective, including future changes to any incorporated provisions of federal law, as the changes take effect. | | | | | | OP |

1. Basis for Effluent Limitations: BPJ = Best Professional Judgment. This Order establishes effluent limitations for BOD₅ because the discharge is comprised of treated municipal wastewater from POTWs. OP = 2012 Ocean Plan. MCL = Maximum Contaminant Levels specified in Title 22, Chapter 15, Article 5, Section 64443, California Code of Regulations.
2. The mass-based effluent limitations are based on the facility design flow rate of 17.52 MGD.
3. "Pass" or "Fail" for Median Monthly Effluent Limitation (MMEL). "Pass" or "Fail" and "% Effect" for Maximum Daily Effluent Limitation (MDEL). The MMEL for chronic toxicity shall only apply when there is a discharge more than one day in a calendar month period. During such calendar months, exactly three independent toxicity tests are required when one toxicity test results in "Fail".
4. This is a Median Monthly Effluent Limitation.
5. Bacteria limitations:
 - a. 30-day Geometric Mean – The geometric mean shall be calculated using the results of five most recent samples.

- i. Total coliform density shall not exceed 1,000/100 ml;
- ii. Fecal coliform density shall not exceed 200/100 ml; and
- iii. Enterococcus density shall not exceed 35/100 ml.
- b. Single Sample Maximum (SSM)
 - i. Total coliform density shall not exceed 10,000/100 ml;
 - ii. Fecal coliform density shall not exceed 400/100 ml;
 - iii. Enterococcus density shall not exceed 104/100 ml; and
 - iv. Total coliform density shall not exceed 1,000/100 ml, when the fecal coliform/total coliform ratio exceeds 0.1.
- 6. Non-chlorinated phenolic compounds represent the sum of 2-nitrophenol; phenol; 2,4-dimethylphenol; 2,4-dinitrophenol; 2-methyl-4,6-dinitrophenol; and 4-nitrophenol.
- 7. Chlorinated phenolic compounds represent the sum of 2-chlorophenol; 2,4-dichlorophenol; 2,4,6-trichlorophenol; 4-chloro-3-methylphenol; and pentachlorophenol.
- 8. TCDD Equivalents shall mean the sum of the concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown in the table below. USEPA method 1613 may be used to analyze dioxin and furan congeners.

$$\text{Dioxin-TEQ (TCDD Equivalents)} = \sum (C_x \times \text{TEF}_x)$$

Where:

C_x = concentration of dioxin or furan congener x

TEF_x = TEF for congener x

Toxicity Equivalency Factors

| Isomer Group | Toxicity Equivalency Factor (TEF) |
|---------------------|-----------------------------------|
| 2,3,7,8-tetra CDD | 1.0 |
| 2,3,7,8-penta CDD | 0.5 |
| 2,3,7,8-hexa CDDs | 0.1 |
| 2,3,7,8-hepta CDD | 0.01 |
| Octa CDD | 0.001 |
| 2,3,7,8 tetra CDF | 0.1 |
| 1,2,3,7,8 penta CDF | 0.05 |
| 2,3,4,7,8 penta CDF | 0.5 |
| 2,3,7,8 hexa CDFs | 0.1 |
| 2,3,7,8 hepta CDFs | 0.01 |
| Octa CDF | 0.001 |

- 9. Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
- 10. PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorine; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.
- 11. HCH shall mean the sum of alpha, beta, gamma (lindane), and delta isomers of hexachlorocyclohexane.
- 12. DDT shall mean the sum of 4,4'-DDT, 2,4'-DDT, 4,4'-DDE, 2,4'-DDE, 4,4'-DDD, and 2,4'-DDD.
- 13. PCBs shall mean the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, and Aroclor-1260.

E. Interim Effluent Limitations – Not Applicable

F. Land Discharge Specifications – Not Applicable

G. Recycling Specifications – Not Applicable

V. RATIONALE FOR RECEIVING WATER LIMITATIONS

A. Surface Water

The Ocean Plan contains numeric and narrative water quality objectives applicable to the coastal waters of California. Water quality objectives include an objective to maintain the high quality waters pursuant to federal regulations (section 131.12) and State Water Board Resolution No. 68-16. Receiving water limitations in this Order are included to ensure protection of beneficial uses of the receiving water and are based on the water quality objectives contained in the Ocean Plan.

B. Groundwater – Not Applicable

VI. RATIONALE FOR PROVISIONS

A. Standard Provisions

Standard Provisions, which apply to all NPDES permits in accordance with 40 C.F.R. section 122.41, and additional conditions applicable to specified categories of permits in accordance with 40 C.F.R. section 122.42, are provided in Attachment D to the order.

Sections 122.41(a)(1) and (b) through (n) of 40 C.F.R. establish conditions that apply to all State-issued NPDES permits. These conditions must be incorporated into the permits either expressly or by reference. If incorporated by reference, a specific citation to the regulations must be included in the Order. Section 123.25(a)(12) allows the state to omit or modify conditions to impose more stringent requirements. In accordance with 40 C.F.R. section 123.25, this Order omits federal conditions that address enforcement authority specified in 40 C.F.R. sections 122.41(j)(5) and (k)(2) because the enforcement authority under the Water Code is more stringent. In lieu of these conditions, this Order incorporates by reference Water Code section 13387(e).

B. Special Provisions

1. Reopener Provisions

These provisions are based on section 123 and the previous Order. The Regional Water Board may reopen the permit to modify permit conditions and requirements. Causes for modifications include the promulgation of new federal regulations, modification in toxicity requirements, or adoption of new regulations by the State Water Board or Regional Water Board, including revisions to the Basin Plan and/or Ocean Plan.

2. Special Studies and Additional Monitoring Requirements

- a. **Initial Investigation Toxicity Reduction Evaluation Workplan.** This provision is based on section III.C.9 of the Ocean Plan.
- b. **Mixing Zone Study Work Plan.** The Discharger is required to develop and submit to the Los Angeles Regional Water Board for review a work plan detailing how the Discharger will conduct a Mixing Zone Study. The Mixing Zone Study shall be designed to confirm the assumption included in the modeling of the discharge.
- c. **Sediment Loading Study Work Plan.** The Discharger is required to develop and submit to the Los Angeles Regional Water Board for review a work plan detailing how the Discharger will conduct a Sediment Loading Study. The Sediment Loading Study shall be designed to monitor the concentrations of constituents present in the sediment inside and outside of the mixing zone. The sampling must target all constituents present in the discharge that bioaccumulate in the tissue of aquatic life that may be present in the area.

3. Best Management Practices and Pollution Prevention

These provisions are based on section 122.44(k) and includes the requirement to develop and implement a SWPPP, BMPP and a SPCC Plan.

4. Construction, Operation, and Maintenance Specifications

This provision is based on the requirements of section 122.41(e) and the previous Order.

VII. RATIONALE FOR MONITORING AND REPORTING REQUIREMENTS

Section 122.48 of 40 C.F.R. requires that all NPDES permits specify requirements for recording and reporting monitoring results. Water Code sections 13267 and 13383 authorize the Los Angeles Regional Water Board to require technical and monitoring reports. The Monitoring and Reporting Program (MRP), Attachment E, establishes monitoring and reporting requirements that implement federal and state requirements. The following provides the rationale for the monitoring and reporting requirements contained in the MRP for this facility.

A. Influent Monitoring – Not Applicable

B. Effluent Monitoring

Monitoring for those pollutants expected to be present in discharges from Discharge Point 001 (Monitoring Location EFF-001) will be required as shown in the MRP (Attachment E). For the most part, monitoring requirements from the previous Order are included in this Order. To determine compliance with effluent limitations, the MRP retains monthly monitoring for total residual chlorine, ammonia, bacteria, and chronic toxicity. The MRP newly establishes daily monitoring for total effluent flow, to record the volume of discharge from the RSMP. In addition, the MRP requires monthly monitoring for all pollutants included in Table 1 of the Ocean Plan, to determine compliance with effluent limitations for those pollutants. The previous Order required quarterly monitoring for some of these parameters, identified in the previous MRP as “all other Table B (Table 1 in the 2012 Ocean Plan) constituents”; however, because new WQBELs are established for these parameters, monthly monitoring is required. In addition to assessing compliance with effluent limitations, routine monitoring of Table 1 parameters will provide data for evaluating reasonable potential for the new discharge to cause or contribute to an exceedance of applicable water quality objectives contained in the Ocean Plan.

Upon the commencement of discharges from the RSMP, if after 2 years all monitoring results for certain constituents are reported as non-detect, using detection limits that are sufficiently sensitive to demonstrate compliance with effluent limitations, the sampling frequency for certain constituents may be reduced to 1/Quarter. However, if after the reduction in monitoring frequency for these constituents is allowed, monitoring results are reported at concentrations greater than the applicable effluent limitation, the monitoring frequency for these constituents reverts to 1/Month.

C. Whole Effluent Toxicity Testing Requirements

Whole effluent toxicity (WET) protects the receiving water quality from the aggregate toxic effect of a mixture of pollutants in the effluent. An acute toxicity test is conducted over a short time period and measures mortality. A chronic toxicity test is conducted over a longer period of time and may measure mortality, reproduction, and growth. Chronic toxicity is a more stringent requirement than acute toxicity. A chemical at a low concentration can have chronic effects but no acute effects. For this permit, chronic toxicity in the discharge is limited and evaluated using USEPA’s 2010 TST hypothesis testing approach. The chronic toxicity

effluent limitations are as stringent as necessary to protect the Ocean Plan Water Quality Objective for chronic toxicity.

Section III.C.3.c.(4) of the Ocean Plan requires dischargers to conduct chronic toxicity testing if the minimum initial dilution of the effluent is below 100:1. The Facility has an initial dilution ratio of 72 to 1. Therefore, this Order includes monitoring requirements for chronic toxicity in the MRP (Attachment E).

D. Receiving Water Monitoring

Monitoring requirements are included in the MRP (Attachment E) to determine compliance with the receiving water limitations established in Limitations and Discharge Requirements, Receiving Water Limitations, Section V.A. Receiving water monitoring requirements have been included from the previous Order with modification. This Order requires monthly monitoring for the first year. If monitoring results demonstrate compliance with water quality objectives in the Ocean Plan the frequency of monitoring for that constituent may be reduced to quarterly. If a quarterly sample exceeds the water quality objectives in the Ocean Plan, the monitoring frequency returns to monthly for that constituent until at least four consecutive samples demonstrate compliance with the water quality objective.

E. Other Monitoring Requirements

1. Outfall and Diffuser Inspection

The annual inspection is required to ensure a periodic assessment of the integrity of the outfall pipes and ballasting system.

VIII. PUBLIC PARTICIPATION

The Los Angeles Regional Water Board has considered the issuance of WDR's that will serve as an NPDES permit for Calleguas Municipal Water District, Regional Salinity Management Pipeline. As a step in the WDR adoption process, the Los Angeles Regional Water Board staff has developed tentative WDR's and has encouraged public participation in the WDR adoption process.

A. Notification of Interested Parties

The Los Angeles Regional Water Board notified the Discharger and interested agencies and persons of its intent to prescribe WDR's for the discharge and provided them an opportunity to submit written comments and recommendations.

The public had access to the agenda and any changes in dates and locations through the Los Angeles Regional Water Board's website at:

<http://www.waterboards.ca.gov/losangeles>

B. Written Comments

The staff determinations are tentative. Interested persons were invited to submit written comments concerning tentative WDRs as provided through the notification process electronically at losangeles@waterboards.ca.gov with a copy to jrchen@waterboards.ca.gov.

To be fully responded to by staff and considered by the Los Angeles Regional Water Board, the written comments were due at the Regional Water Board offices by 5:00 p.m. on **February 10, 2014**.

C. Public Hearing

The Los Angeles Regional Water Board held a public hearing on the tentative WDR's during its regular Board meeting on the following date and time and at the following location:

Date: March 6, 2014

Time: 9:00 A.M
Location: City of Culver City, Council Chambers
9770 Culver Boulevard
Culver City, California

Interested persons were invited to attend. At the public hearing, the Los Angeles Regional Water Board heard testimony, pertinent to the discharge, WDR's, and permit. For accuracy of the record, important testimony was requested in writing.

Please be aware that dates and venues may change. Our Web address is <http://www.waterboards.ca.gov/losangeles> where you can access the current agenda for changes in dates and locations.

D. Reconsideration of Waste Discharge Requirements

Any aggrieved person may petition the State Water Board to review the decision of the Regional Water Board regarding the final WDR's. The petition must be received by the State Water Board at the following address within 30 calendar days of the Regional Water Board's action.

State Water Resources Control Board
Office of Chief Counsel
P.O. Box 100, 1001 I Street
Sacramento, CA 95812-0100

For instructions on how to file a petition for review, see:
http://www.waterboards.ca.gov/public_notices/petitions/water_quality/wqpetition_instr.shtml

E. Information and Copying

The Report of Waste Discharge, other supporting documents, and comments received are on file and may be inspected at the address above at any time between 8:30 a.m. and 4:45 p.m., Monday through Friday. Copying of documents may be arranged through the Los Angeles Regional Water Board by calling (213) 576-6600.

F. Register of Interested Persons

Any person interested in being placed on the mailing list for information regarding the WDR's and NPDES permit should contact the Los Angeles Regional Water Board, reference this facility, and provide a name, address, and phone number.

G. Additional Information

Requests for additional information or questions regarding this order should be directed to Jau Ren Chen at (213) 576-6656.

ATTACHMENT G – STORM WATER POLLUTION PREVENTION PLAN REQUIREMENTS

I. Implementation Schedule

A storm water pollution prevention plan (SWPPP) shall be developed and submitted to the Regional Water Board within 90 days following the adoption of this Order. The SWPPP shall be implemented for each facility covered by this Permit within 10 days of approval from the Regional Water Board, or 6-months from the date of the submittal of the SWPPP to the Regional Water Board (whichever comes first).

II. Objectives

The SWPPP has two major objectives: (a) to identify and evaluate sources of pollutants associated with industrial activities that may affect the quality of storm water discharges and authorized non-storm water discharges from the facility; and (b) to identify and implement site-specific best management practices (BMPs) to reduce or prevent pollutants associated with industrial activities in storm water discharges and authorized non-storm water discharges. BMPs may include a variety of pollution prevention measures or other low-cost and pollution control measures. They are generally categorized as non-structural BMPs (activity schedules, prohibitions of practices, maintenance procedures, and other low-cost measures) and as structural BMPs (treatment measures, run-off controls, over-head coverage.) To achieve these objectives, facility operators should consider the five phase process for SWPPP development and implementation as shown in Table A.

The SWPPP requirements are designed to be sufficiently flexible to meet the needs of various facilities. SWPPP requirements that are not applicable to a facility should not be included in the SWPPP.

A facility's SWPPP is a written document that shall contain a compliance activity schedule, a description of industrial activities and pollutant sources, descriptions of BMPs, drawings, maps, and relevant copies or references of parts of other plans. The SWPPP shall be revised whenever appropriate and shall be readily available for review by facility employees or Regional Water Board inspectors.

III. Planning and Organization

A. Pollution Prevention Team

The SWPPP shall identify a specific individual or individuals and their positions within the facility organization as members of a storm water pollution prevention team responsible for developing the SWPPP, assisting the facility manager in SWPPP implementation and revision, and conducting all monitoring program activities required in Attachment E of this Permit. The SWPPP shall clearly identify the Permit related responsibilities, duties, and activities of each team member. For small facilities, storm water pollution prevention teams may consist of one individual where appropriate.

B. Review Other Requirements and Existing Facility Plans

The SWPPP may incorporate or reference the appropriate elements of other regulatory requirements. Facility operators should review all local, State, and Federal requirements that impact, complement, or are consistent with the requirements of this General Permit. Facility

operators should identify any existing facility plans that contain storm water pollutant control measures or relate to the requirements of this Permit. As examples, facility operators whose facilities are subject to Federal Spill Prevention Control and Countermeasures' requirements should already have instituted a plan to control spills of certain hazardous materials. Similarly, facility operators whose facilities are subject to air quality related permits and regulations may already have evaluated industrial activities that generate dust or particulates.

IV. Site Map

The SWPPP shall include a site map. The site map shall be provided on an 8-½ x 11 inch or larger sheet and include notes, legends, and other data as appropriate to ensure that the site map is clear and understandable. If necessary, facility operators may provide the required information on multiple site maps.

**TABLE A
 FIVE PHASES FOR DEVELOPING AND IMPLEMENTING INDUSTRIAL
 STORM WATER POLLUTION PREVENTION PLANS**

| |
|---|
| <p>PLANNING AND ORGANIZATION</p> <ul style="list-style-type: none"> Form Pollution Prevention Team Review other plans |
| <p>ASSESSMENT PHASE</p> <ul style="list-style-type: none"> Develop a site map Identify potential pollutant sources Inventory of materials and chemicals List significant spills and leaks Identify non-storm water discharges Assess pollutant risks |
| <p>BEST MANAGEMENT PRACTICES IDENTIFICATION PHASE</p> <ul style="list-style-type: none"> Non-structural BMPs Structural BMPs Select activity and site-specific BMPs |
| <p>IMPLEMENTATION PHASE</p> <ul style="list-style-type: none"> Train employees Implement BMPs Conduct recordkeeping and reporting |
| <p>EVALUATION / MONITORING</p> <ul style="list-style-type: none"> Conduct annual site evaluation Review monitoring information Evaluate BMPs Review and revise SWPPP |

The following information shall be included on the site map:

- A.** The facility boundaries; the outline of all storm water drainage areas within the facility boundaries; portions of the drainage area impacted by run-on from surrounding areas; and direction of flow of each drainage area, on-site surface water bodies, and areas of soil erosion. The map shall also identify nearby water bodies (such as rivers, lakes, and ponds) and municipal storm drain inlets where the facility's storm water discharges and authorized non-storm water discharges may be received.
- B.** The location of the storm water collection and conveyance system, associated points of discharge, and direction of flow. Include any structural control measures that affect storm water discharges, authorized non-storm water discharges, and run-on. Examples of structural control measures are catch basins, berms, detention ponds, secondary containment, oil/water separators, diversion barriers, etc.
- C.** An outline of all impervious areas of the facility, including paved areas, buildings, covered storage areas, or other roofed structures.
- D.** Locations where materials are directly exposed to precipitation and the locations where significant spills or leaks identified in Section A.6.a.iv. below have occurred.
- E.** Areas of industrial activity. This shall include the locations of all storage areas and storage tanks, shipping and receiving areas, fueling areas, vehicle and equipment storage/maintenance areas, material handling and processing areas, waste treatment and disposal areas, dust or particulate generating areas, cleaning and rinsing areas, and other areas of industrial activity which are potential pollutant sources.

V. List of Significant Materials

The SWPPP shall include a list of significant materials handled and stored at the site. For each material on the list, describe the locations where the material is being stored, received, shipped, and handled, as well as the typical quantities and frequency. Materials shall include raw materials, intermediate products, final or finished products, recycled materials, and waste or disposed materials.

VI. Description of Potential Pollutant Sources

- A.** The SWPPP shall include a narrative description of the facility's industrial activities, as identified in Section A.4.e above, associated potential pollutant sources, and potential pollutants that could be discharged in storm water discharges or authorized non-storm water discharges. At a minimum, the following items related to a facility's industrial activities shall be considered:
 - 1. Industrial Processes.** Describe each industrial process, the type, characteristics, and quantity of significant materials used in or resulting from the process, and a description of the manufacturing, cleaning, rinsing, recycling, disposal, or other activities related to the process. Where applicable, areas protected by containment structures and the corresponding containment capacity shall be described.
 - 2. Material Handling and Storage Areas.** Describe each handling and storage area, type, characteristics, and quantity of significant materials handled or stored, description of the shipping, receiving, and loading procedures, and the spill or leak prevention and response

procedures. Where applicable, areas protected by containment structures and the corresponding containment capacity shall be described.

3. **Dust and Particulate Generating Activities.** Describe all industrial activities that generate dust or particulates that may be deposited within the facility's boundaries and identify their discharge locations; the characteristics of dust and particulate pollutants; the approximate quantity of dust and particulate pollutants that may be deposited within the facility boundaries; and a description of the primary areas of the facility where dust and particulate pollutants would settle.
4. **Significant Spills and Leaks.** Describe materials that have spilled or leaked in significant quantities in storm water discharges or non-storm water discharges since April 17, 1994. Include toxic chemicals (listed in 40 C.F.R., section 302) that have been discharged to storm water as reported on USEPA Form R, and oil and hazardous substances in excess of reportable quantities (see 40 Code of Federal Regulations [C.F.R.], sections 110, 117, and 302).

The description shall include the type, characteristics, and approximate quantity of the material spilled or leaked, the cleanup or remedial actions that have occurred or are planned, the approximate remaining quantity of materials that may be exposed to storm water or non-storm water discharges, and the preventative measures taken to ensure spill or leaks do not reoccur. Such list shall be updated as appropriate during the term of this Permit.

5. **Non-Storm Water Discharges.** Facility operators shall investigate the facility to identify all non-storm water discharges and their sources. As part of this investigation, all drains (inlets and outlets) shall be evaluated to identify whether they connect to the storm drain system.

All non-storm water discharges shall be described. This shall include the source, quantity, frequency, and characteristics of the non-storm water discharges and associated drainage area.

Non-storm water discharges (other boiler blowdown and boiler condensate permitted under the Order) that contain significant quantities of pollutants or that do not meet the conditions provided in Special Conditions D of the storm water general permit are prohibited by this Permit (Examples of prohibited non-storm water discharges are contact and non-contact cooling water, rinse water, wash water, etc.). Non-storm water discharges that meet the conditions provided in Special Condition D of the general storm water permit are authorized by this Permit. The SWPPP must include BMPs to prevent or reduce contact of non-storm water discharges with significant materials or equipment.

6. **Soil Erosion.** Describe the facility locations where soil erosion may occur as a result of industrial activity, storm water discharges associated with industrial activity, or authorized non-storm water discharges.
- B. The SWPPP shall include a summary of all areas of industrial activities, potential pollutant sources, and potential pollutants. This information should be summarized similar to Table B. The last column of Table B, "Control Practices", should be completed in accordance with Section A.8. below.

VII. Assessment of Potential Pollutant Sources

- A.** The SWPPP shall include a narrative assessment of all industrial activities and potential pollutant sources as described in A.6. above to determine:
- 1.** Which areas of the facility are likely sources of pollutants in storm water discharges and authorized non-storm water discharges, and
 - 2.** Which pollutants are likely to be present in storm water discharges and authorized non-storm water discharges. Facility operators shall consider and evaluate various factors when performing this assessment such as current storm water BMPs; quantities of significant materials handled, produced, stored, or disposed of; likelihood of exposure to storm water or authorized non-storm water discharges; history of spill or leaks; and run-on from outside sources.
- B.** Facility operators shall summarize the areas of the facility that are likely sources of pollutants and the corresponding pollutants that are likely to be present in storm water discharges and authorized non-storm water discharges.

Facility operators are required to develop and implement additional BMPs as appropriate and necessary to prevent or reduce pollutants associated with each pollutant source. The BMPs will be narratively described in section VIII below.

VIII. Storm Water Best Management Practices

The SWPPP shall include a narrative description of the storm water BMPs to be implemented at the facility for each potential pollutant and its source identified in the site assessment phase (Sections A.6. and 7. above). The BMPs shall be developed and implemented to reduce or prevent pollutants in storm water discharges and authorized non-storm water discharges. Each pollutant and its source may require one or more BMPs. Some BMPs may be implemented for multiple pollutants and their sources, while other BMPs will be implemented for a very specific pollutant and its source.

TABLE B
EXAMPLE
ASSESSMENT OF POTENTIAL POLLUTION SOURCES AND
CORRESPONDING BEST MANAGEMENT PRACTICES
SUMMARY

| Area | Activity | Pollutant Source | Pollutant | Best Management Practices |
|-----------------------------|-----------------|---|------------------|--|
| Vehicle & Equipment Fueling | Fueling | Spills and leaks during delivery. Spills caused by topping off fuel tanks. Hosing or washing down fuel oil fuel area. Leaking storage tanks. Rainfall running off fuel oil, and rainfall running onto and off fueling area. | fuel oil | Use spill and overflow protection. Minimize run-on of storm water into the fueling area. Cover fueling area. Use dry cleanup methods rather than hosing down area. Implement proper spill prevention control program. Implement adequate preventative maintenance program to preventive tank and line leaks. Inspect fueling areas regularly to detect problems before they occur. Train employees on proper fueling, cleanup, and spill response techniques. |

The description of the BMPs shall identify the BMPs as (1) existing BMPs, (2) existing BMPs to be revised and implemented, or (3) new BMPs to be implemented. The description shall also include a discussion on the effectiveness of each BMP to reduce or prevent pollutants in storm water discharges and authorized non-storm water discharges. The SWPPP shall provide a summary of all BMPs implemented for each pollutant source. This information should be summarized similar to Table B.

Facility operators shall consider the following BMPs for implementation at the facility:

A. Non-Structural BMPs

Non-structural BMPs generally consist of processes, prohibitions, procedures, schedule of activities, etc., that prevent pollutants associated with industrial activity from contacting with storm water discharges and authorized non-storm water discharges. They are considered low technology, cost-effective measures. Facility operators should consider all possible non-

structural BMPs options before considering additional structural BMPs (see Section A.8.b. below). Below is a list of non-structural BMPs that should be considered:

1. **Good Housekeeping.** Good housekeeping generally consists of practical procedures to maintain a clean and orderly facility.
2. **Preventive Maintenance.** Preventive maintenance includes the regular inspection and maintenance of structural storm water controls (catch basins, oil/water separators, etc.) as well as other facility equipment and systems.
3. **Spill Response.** This includes spill clean-up procedures and necessary clean-up equipment based upon the quantities and locations of significant materials that may spill or leak.
4. **Material Handling and Storage.** This includes all procedures to minimize the potential for spills and leaks and to minimize exposure of significant materials to storm water and authorized non-storm water discharges.
5. **Employee Training.** This includes training of personnel who are responsible for (1) implementing activities identified in the SWPPP, (2) conducting inspections, sampling, and visual observations, and (3) managing storm water. Training should address topics such as spill response, good housekeeping, and material handling procedures, and actions necessary to implement all BMPs identified in the SWPPP. The SWPPP shall identify periodic dates for such training. Records shall be maintained of all training sessions held.
6. **Waste Handling/Recycling.** This includes the procedures or processes to handle, store, or dispose of waste materials or recyclable materials.
7. **Recordkeeping and Internal Reporting.** This includes the procedures to ensure that all records of inspections, spills, maintenance activities, corrective actions, visual observations, etc., are developed, retained, and provided, as necessary, to the appropriate facility personnel.
8. **Erosion Control and Site Stabilization.** This includes a description of all sediment and erosion control activities. This may include the planting and maintenance of vegetation, diversion of run-on and runoff, placement of sandbags, silt screens, or other sediment control devices, etc.
9. **Inspections.** This includes, in addition to the preventative maintenance inspections identified above, an inspection schedule of all potential pollutant sources. Tracking and follow-up procedures shall be described to ensure adequate corrective actions are taken and SWPPPs are made.
10. **Quality Assurance.** This includes the procedures to ensure that all elements of the SWPPP and Monitoring Program are adequately conducted.

B. Structural BMPs.

Where non-structural BMPs as identified in Section A.8.a. above are not effective, structural BMPs shall be considered. Structural BMPs generally consist of structural devices that reduce or prevent pollutants in storm water discharges and authorized non-storm water discharges. Below is a list of structural BMPs that should be considered:

1. **Overhead Coverage.** This includes structures that provide horizontal coverage of materials, chemicals, and pollutant sources from contact with storm water and authorized non-storm water discharges.
2. **Retention Ponds.** This includes basins, ponds, surface impoundments, bermed areas, etc. that do not allow storm water to discharge from the facility.
3. **Control Devices.** This includes berms or other devices that channel or route run-on and runoff away from pollutant sources.
4. **Secondary Containment Structures.** This generally includes containment structures around storage tanks and other areas for the purpose of collecting any leaks or spills.
5. **Treatment.** This includes inlet controls, infiltration devices, oil/water separators, detention ponds, vegetative swales, etc. that reduce the pollutants in storm water discharges and authorized non-storm water discharges.

IX. Annual Comprehensive Site Compliance Evaluation

The facility operator shall conduct one comprehensive site compliance evaluation (evaluation) in each reporting period (July 1-June 30). Evaluations shall be conducted within 8-16 months of each other. The SWPPP shall be revised, as appropriate, and the revisions implemented within 90 days of the evaluation. Evaluations shall include the following:

- A. A review of all visual observation records, inspection records, and sampling and analysis results.
- B. A visual inspection of all potential pollutant sources for evidence of, or the potential for, pollutants entering the drainage system.
- C. A review and evaluation of all BMPs (both structural and non-structural) to determine whether the BMPs are adequate, properly implemented and maintained, or whether additional BMPs are needed. A visual inspection of equipment needed to implement the SWPPP, such as spill response equipment, shall be included.
- D. An evaluation report that includes, (i) identification of personnel performing the evaluation, (ii) the date(s) of the evaluation, (iii) necessary SWPPP revisions, (iv) schedule, as required in Section A.10.e, for implementing SWPPP revisions, (v) any incidents of non-compliance and the corrective actions taken, and (vi) a certification that the facility operator is in compliance with this Permit. If the above certification cannot be provided, explain in the evaluation report why the facility operator is not in compliance with this General Permit. The evaluation report shall be submitted as part of the annual report, retained for at least five years, and signed and certified in accordance with Standard Provisions V.D.5 of Attachment D.

X. SWPPP General Requirements

- A. The SWPPP shall be retained on site and made available upon request of a representative of the Regional Water Board and/or local storm water management agency (local agency) which receives the storm water discharges.

- B.** The Regional Water Board and/or local agency may notify the facility operator when the SWPPP does not meet one or more of the minimum requirements of this Section. As requested by the Regional Water Board and/or local agency, the facility operator shall submit an SWPPP revision and implementation schedule that meets the minimum requirements of this section to the Regional Water Board and/or local agency that requested the SWPPP revisions. Within 14 days after implementing the required SWPPP revisions, the facility operator shall provide written certification to the Regional Water Board and/or local agency that the revisions have been implemented.
- C.** The SWPPP shall be revised, as appropriate, and implemented prior to changes in industrial activities which (i) may significantly increase the quantities of pollutants in storm water discharge, (ii) cause a new area of industrial activity at the facility to be exposed to storm water, or (iii) begin an industrial activity which would introduce a new pollutant source at the facility.
- D.** The SWPPP shall be revised and implemented in a timely manner, but in no case more than 90 days after a facility operator determines that the SWPPP is in violation of any requirement(s) of this Permit.
- E.** When any part of the SWPPP is infeasible to implement due to proposed significant structural changes, the facility operator shall submit a report to the Regional Water Board prior to the applicable deadline that (i) describes the portion of the SWPPP that is infeasible to implement by the deadline, (ii) provides justification for a time extension, (iii) provides a schedule for completing and implementing that portion of the SWPPP, and (iv) describes the BMPs that will be implemented in the interim period to reduce or prevent pollutants in storm water discharges and authorized non-storm water discharges. Such reports are subject to Regional Water Board approval and/or modifications. Facility operators shall provide written notification to the Regional Water Board within 14 days after the SWPPP revisions are implemented.
- F.** The SWPPP shall be provided, upon request, to the Regional Water Board. The SWPPP is considered a report that shall be available to the public by the Regional Water Board under Section 308(b) of the Clean Water Act.

ATTACHMENT H – STATE WATER BOARD MINIMUM LEVELS

The Minimum Levels identified in this appendix represent the lowest concentration of a pollutant that can be quantitatively measured in a sample given the current state of performance in analytical chemistry methods in California. These Minimum Levels were derived from data provided by state-certified analytical laboratories in 1997 and 1998 for pollutants regulated by the California Ocean Plan and shall be used until new values are adopted by the State Water Board. There are four major chemical groupings: volatile chemicals, semi-volatile chemicals, inorganics, pesticides & PCB's. "No Data" is indicated by "--".

**TABLE II-1
MINIMUM LEVELS – VOLATILE CHEMICALS**

| Volatile Chemicals | CAS Number | Minimum Level* (µ/L) | |
|--------------------------------|------------|------------------------|--------------------------|
| | | GC Method ^a | GCMS Method ^b |
| Acrolein | 107028 | 2. | 5 |
| Acrylonitrile | 107131 | 2. | 2 |
| Benzene | 71432 | 0.5 | 2 |
| Bromoform | 75252 | 0.5 | 2 |
| Carbon Tetrachloride | 56235 | 0.5 | 2 |
| Chlorobenzene | 108907 | 0.5 | 2 |
| Chlorodibromomethane | 124481 | 0.5 | 2 |
| Chloroform | 67663 | 0.5 | 2 |
| 1,2-Dichlorobenzene (volatile) | 95501 | 0.5 | 2 |
| 1,3-Dichlorobenzene (volatile) | 541731 | 0.5 | 2 |
| 1,4-Dichlorobenzene (volatile) | 106467 | 0.5 | 2 |
| Dichlorobromomethane | 75274 | 0.5 | 2 |
| 1,1-Dichloroethane | 75343 | 0.5 | 1 |
| 1,2-Dichloroethane | 107062 | 0.5 | 2 |
| 1,1-Dichloroethylene | 75354 | 0.5 | 2 |
| Dichloromethane | 75092 | 0.5 | 2 |
| 1,3-Dichloropropene (volatile) | 542756 | 0.5 | 2 |
| Ethyl benzene | 100414 | 0.5 | 2 |
| Methyl Bromide | 74839 | 1. | 2 |
| Methyl Chloride | 74873 | 0.5 | 2 |
| 1,1,2,2-Tetrachloroethane | 79345 | 0.5 | 2 |
| Tetrachloroethylene | 127184 | 0.5 | 2 |
| Toluene | 108883 | 0.5 | 2 |
| 1,1,1-Trichloroethane | 71556 | 0.5 | 2 |
| 1,1,2-Trichloroethane | 79005 | 0.5 | 2 |
| Trichloroethylene | 79016 | 0.5 | 2 |
| Vinyl Chloride | 75014 | 0.5 | 2 |

Table II-1 Notes

a) GC Method = Gas Chromatography

b) GCMS Method = Gas Chromatography / Mass Spectrometry

* To determine the lowest standard concentration in an instrument calibration curve for these techniques, use the given ML (see Ocean Plan, Chapter III, "Use of Minimum Levels").

**TABLE II-2
MINIMUM LEVELS – SEMI VOLATILE CHEMICALS**

| Semi-Volatile Chemicals | CAS Number | Minimum* Level (µg/L) | | | |
|------------------------------------|------------|------------------------|--------------------------|--------------------------|---------------------------|
| | | GC Method ^a | GCMS Method ^b | HPLC Method ^c | COLOR Method ^d |
| Acenaphthylene | 208968 | -- | 10 | 0.2 | -- |
| Anthracene | 120127 | -- | 10 | 2 | -- |
| Benzidine | 92875 | -- | 5 | -- | -- |
| Benzo(a)anthracene | 56553 | -- | 10 | 2 | -- |
| Benzo(a)pyrene | 50328 | -- | 10 | 2 | -- |
| Benzo(b)fluoranthene | 205992 | -- | 10 | 10 | -- |
| Benzo(g,h,i)perylene | 191242 | -- | 5 | 0.1 | -- |
| Benzo(k)fluoranthene | 207089 | -- | 10 | 2 | -- |
| Bis2-(1-Chloroethoxy) methane | 111911 | -- | 5 | -- | -- |
| Bis(2-Chloroethyl)ether | 111444 | 10 | 1 | -- | -- |
| Bis(2-Chloroisopropyl)ether | 39638329 | 10 | 2 | -- | -- |
| Bis(2-Ethylhexyl) phthalate | 117817 | 10 | 5 | -- | -- |
| 2-Chlorophenol | 95578 | 2 | 5 | -- | -- |
| Chrysene | 218019 | -- | 10 | 5 | -- |
| Di-n-butyl phthalate | 84742 | -- | 10 | -- | -- |
| Dibenzo(a,h)anthracene | 53703 | -- | 10 | 0.1 | -- |
| 1,2-Dichlorobenzene (semivolatile) | 95504 | 2 | 2 | -- | -- |
| 1,3-Dichlorobenzene (semivolatile) | 541731 | 2 | 1 | -- | -- |
| 1,4-Dichlorobenzene (semivolatile) | 106467 | 2 | 1 | -- | -- |
| 3,3-Dichlorobenzidine | 91941 | -- | 5 | -- | -- |
| 2,4-Dichlorophenol | 120832 | 1 | 5 | -- | -- |
| 1,3-Dichloropropene | 542756 | -- | 5 | -- | -- |
| Diethyl phthalate | 84662 | 10 | 2 | -- | -- |
| Dimethyl phthalate | 131113 | 10 | 2 | -- | -- |
| 2,4-Dimethylphenol | 105679 | 1 | 2 | -- | -- |
| 2,4-Dinitrophenol | 51285 | 5 | 5 | -- | -- |
| 2,4-Dinitrotoluene | 121142 | 10 | 5 | -- | -- |
| 1,2-Diphenylhydrazine | 122667 | -- | 1 | -- | -- |
| Fluoranthene | 206440 | 10 | 1 | 0.05 | -- |
| Fluorene | 86737 | -- | 10 | 0.1 | -- |
| Hexachlorobenzene | 118741 | 5 | 1 | -- | -- |
| Hexachlorobutadiene | 87683 | 5 | 1 | -- | -- |
| Hexachlorocyclopentadiene | 77474 | 5 | 5 | -- | -- |
| Hexachloroethane | 67721 | 5 | 1 | -- | -- |
| Indeno(1,2,3-cd)pyrene | 193395 | -- | 10 | 0.05 | -- |
| Isophorone | 78591 | 10 | 1 | -- | -- |
| 2-methyl-4,6-dinitrophenol | 534521 | 10 | 5 | -- | -- |
| 3-methyl-4-chlorophenol | 59507 | 5 | 1 | -- | -- |
| N-nitrosodi-n-propylamine | 621647 | 10 | 5 | -- | -- |
| N-nitrosodimethylamine | 62759 | 10 | 5 | -- | -- |

| Semi-Volatile Chemicals | CAS Number | Minimum* Level (µg/L) | | | |
|-------------------------|------------|------------------------|--------------------------|--------------------------|---------------------------|
| | | GC Method ^a | GCMS Method ^b | HPLC Method ^c | COLOR Method ^d |
| N-nitrosodiphenylamine | 86306 | 10 | 1 | -- | -- |
| Nitrobenzene | 98953 | 10 | 1 | -- | -- |
| 2-Nitrophenol | 88755 | -- | 10 | -- | -- |
| 4-Nitrophenol | 100027 | 5 | 10 | -- | -- |
| Pentachlorophenol | 87865 | 1 | 5 | -- | -- |
| Phenanthrene | 85018 | -- | 5 | 0.05 | -- |
| Phenol | 108952 | 1 | 1 | -- | 50 |
| Pyrene | 129000 | -- | 10 | 0.05 | -- |
| 2,4,6-Trichlorophenol | 88062 | 10 | 10 | -- | -- |

Table II-2 Notes:

- a) GC Method = Gas Chromatography
- b) GCMS Method = Gas Chromatography / Mass Spectrometry
- c) HPLC Method = High Pressure Liquid Chromatography
- d) COLOR Method = Colorimetric

* To determine the lowest standard concentration in an instrument calibration curve for this technique, multiply the given ML by 1000 (see Ocean Plan, Chapter III, "Use of Minimum Levels").

**TABLE II-3
 MINIMUM* LEVELS – INORGANICS**

| Inorganic Substances | CAS Number | Minimum* Level (µg/L) | | | | | | | | |
|----------------------|------------|---------------------------|-------------------------|-------------------------|--------------------------|-----------------------------|-------------------------|---------------------------|----------------------------|--------------------------|
| | | COLOR Method ^a | DCP Method ^b | FAA Method ^c | GFAA Method ^d | HYBRIDE Method ^e | ICP Method ^f | ICPMS Method ^g | SPGFAA Method ^h | CVAA Method ⁱ |
| Antimony | 7440360 | -- | 1000. | 10. | 5. | 0.5 | 50. | 0.5 | 5. | -- |
| Arsenic | 7440382 | 20. | 1000. | -- | 2. | 1. | 10. | 2. | 2. | -- |
| Beryllium | 7440417 | -- | 1000. | 20. | 0.5 | -- | 2. | 0.5 | 1. | -- |
| Cadmium | 7440439 | -- | 1000. | 10. | 0.5 | -- | 10. | 0.2 | 0.5 | -- |
| Chromium (total) | -- | -- | 1000. | 50. | 2. | -- | 10. | 0.5 | 1. | -- |
| Chromium (VI) | 18540299 | 10. | -- | 5. | -- | -- | -- | -- | -- | -- |
| Copper | 7440508 | -- | 1000. | 20. | 5. | -- | 10. | 0.5 | 2. | -- |
| Cyanide | 57125 | 5. | -- | -- | -- | -- | -- | -- | -- | -- |
| Lead | 7439921 | -- | 10000. | 20. | 5. | -- | 5. | 0.5 | 2. | -- |
| Mercury | 7439976 | -- | -- | -- | -- | -- | -- | 0.5 | -- | 0.2 |
| Nickel | 7440020 | -- | 1000. | 50. | 5. | -- | 20. | 1. | 5. | -- |
| Selenium | 7782492 | -- | 1000. | -- | 5. | 1. | 10. | 2. | 5. | -- |
| Silver | 7440224 | -- | 1000. | 10. | 1. | -- | 10. | 0.2 | 2. | -- |
| Thallium | 7440280 | -- | 1000. | 10. | 2. | -- | 10. | 1. | 5. | -- |
| Zinc | 7440666 | -- | 1000. | 20. | -- | -- | 20. | 1. | 10. | -- |

Table II-3 Notes

- a) COLOR Method = Colorimetric
- b) DCP Method = Direct Current Plasma
- c) FAA Method = Flame Atomic Absorption
- d) GFAA Method = Graphite Furnace Atomic Absorption
- e) HYBRIDE Method = Gaseous Hydride Atomic Absorption
- f) ICP Method = Inductively Coupled Plasma
- g) ICPMS Method = Inductively Coupled Plasma / Mass Spectrometry
- h) SPGFAA Method = Stabilized Platform Graphite Furnace Atomic Absorption (i.e., US EPA 200.9)
- i) CVAA Method = Cold Vapor Atomic Absorption

* To determine the lowest standard concentration in an instrument calibration curve for these techniques, use the given ML (see Ocean Plan, Chapter III, "Use of Minimum* Levels").

**TABLE II-4
 MINIMUM* LEVELS – PESTICIDES AND PCBs***

| Pesticides – PCB's | CAS Number | Minimum* Level (µg/L) |
|-----------------------------------|------------|------------------------|
| | | GC Method ^a |
| Aldrin | 309002 | 0.005 |
| Chlordane | 57749 | 0.1 |
| 4,4'-DDD | 72548 | 0.05 |
| 4,4'-DDE | 72559 | 0.05 |
| 4,4'-DDT | 50293 | 0.01 |
| Dieldrin | 60571 | 0.01 |
| a-Endosulfan | 959988 | 0.02 |
| b-Endosulfan | 33213659 | 0.01 |
| Endosulfan Sulfate | 1031078 | 0.05 |
| Endrin | 72208 | 0.01 |
| Heptachlor | 76448 | 0.01 |
| Heptachlor Epoxide | 1024573 | 0.01 |
| a-Hexachlorocyclohexane | 319846 | 0.01 |
| b-Hexachlorocyclohexane | 319857 | 0.005 |
| d-Hexachlorocyclohexane | 319868 | 0.005 |
| g-Hexachlorocyclohexane (Lindane) | 58899 | 0.02 |
| PCB1016 | -- | 0.5 |
| PCB1221 | -- | 0.5 |
| PCB1232 | -- | 0.5 |
| PCB1242 | -- | 0.5 |
| PCB1248 | -- | 0.5 |
| PCB1254 | -- | 0.5 |
| PCB1260 | -- | 0.5 |
| Toxaphene | 8001352 | 0.5 |

Table II-4 Notes

a) GC Method = Gas Chromatography

* To determine the lowest standard concentration in an instrument calibration curve for this technique, multiply the given ML by 100 (see Ocean Plan, Chapter III, "Use of Minimum Level")